



Marathon Petroleum Company LP
1300 South Fort Street
Detroit, MI 48217

RECEIVED

MAY 31 2016

AIR QUALITY DIV.

REPORT ON COMPLIANCE TESTING

Performed for:
MARATHON PETROLEUM COMPANY LP
GOHT HEATER STACK (SV08-H1)
DETROIT REFINERY


Client Reference No: 4100665755
CleanAir Project No: 12950
Revision 0: May 18, 2016

To the best of our knowledge, the data presented in this report are accurate, complete, error free, legible and representative of the actual emissions during the test program. Clean Air Engineering operates in conformance with the requirements of ASTM D7036-04 Standard Practice for Competence of Air Emission Testing Bodies.

Submitted by,


Andy Obuchowski
Midwest Engineering Group Leader
aobuchowski@cleanair.com
(800) 627-0033 ext. 4537

Reviewed by,


Scott Lehmann
Engineering Group Business Leader
slehmann@cleanair.com
(800) 627-0033 ext. 4660

PROJECT OVERVIEW

1-1

INTRODUCTION

Marathon Petroleum Company LP (MPC) contracted Clean Air Engineering (CleanAir) to perform emission measurements at the Detroit Refinery for compliance purposes.

All testing was conducted in accordance with the regulations set-forth by the United States Environmental Protection Agency (EPA) and the Michigan Department of Environmental Quality (DEQ). The permit limits are referenced in Michigan Department of Environmental Quality, Air Quality Division Permit to Install No. 63-08D, issued May 12, 2014.

Key Project Participants

Individuals responsible for coordinating and conducting the test program were:

Crystal Davis – MPC
Joe Reidy – MPC
Chad Eilering – CleanAir

Test Program Parameters

The testing was performed at the GOHT Heater Stack (Emission Unit ID No. EU08-GOHTCHARHTR-S1; Stack ID No. SV08-H1) on March 30, 2016, and included the following emissions measurements:

- particulate matter (PM), assumed equivalent to filterable particulate matter (FPM) only
- flue gas composition (e.g. O₂, CO₂, H₂O)
- flue gas flow rate

RECEIVED
MAY 31 2016
AIR QUALITY DIV.

PROJECT OVERVIEW**TEST PROGRAM SYNOPSIS****Test Schedule**

The on-site schedule followed during the test program is outlined in Table 1-1.

**Table 1-1:
Schedule of Activities**

Run Number	Location	Method	Analyte	Date	Start Time	End Time
1	GOHT Heater Stack	USEPA Method 5	FPM	03/30/16	09:43	11:54
2	GOHT Heater Stack	USEPA Method 5	FPM	03/30/16	12:32	14:42
3	GOHT Heater Stack	USEPA Method 5	FPM	03/30/16	15:15	17:26

042716 161454

Results Summary

Table 1-2 summarizes the results of the test program. A more detailed presentation of the test conditions and results of analysis are shown on pages 2-1 and 2-2.

**Table 1-2:
Summary of Emission Compliance Results**

Source	Constituent (units)	Sampling Method	Average Emission	Permit Limit ¹
<u>GOHT Heater Stack</u>				
	PM (lb/MMBtu)	USEPA 5	0.0005	0.0019

¹ Permit limits obtained from MDEQ Permit To Install No. 63-08D.

042716 162556

PROJECT OVERVIEW

1-3

Discussion of Test Program

FPM Testing - USEPA Method 5

For this test program, PM emission rate is assumed equivalent to FPM emission rate. Three (3) 120-minute Method 5 test runs were performed on March 30. The final result was expressed as the average of three (3) valid runs.

Calculation of Final Results

Emission results in units of dry volume-based concentration (lb/dscf, ppm_{dv}) were converted to units of pounds per million Btu (lb/MMBtu) by calculating an oxygen-based fuel factor (F_d) for refinery gas per USEPA Method 19 specifications. The heat content and F_d factor were calculated from percent volume composition analytical data provided by MPC and tabulated heating values for each of the measured constituents.

End of Section 1 – Project Overview

RESULTS**Table 2-1:
GOHT Heater Stack – FPM Emissions (USEPA M5)**

Run No.	1	2	3	Average
Date (2016)	Mar 30	Mar 30	Mar 30	
Start Time (approx.)	09:43	12:32	15:15	
Stop Time (approx.)	11:54	14:42	17:26	
Process Conditions				
P ₁ Fuel Gas Flow Rate (Mscf/day)	2,417	2,486	2,488	2,464
P ₂ Charge Rate (bpd)	46,292	46,404	46,450	46,382
F _d Oxygen-based F-factor (dscf/MMBtu)	7,279	7,279	7,279	7,279
H _i Heat input (MMBtu/hr)	82	84	84	83
Cap Capacity factor (hours/year)	8,760	8,760	8,760	8,760
Gas Conditions				
O ₂ Oxygen (dry volume %)	4.2	4.3	4.9	4.5
CO ₂ Carbon dioxide (dry volume %)	7.0	7.2	7.3	7.2
T _s Sample temperature (°F)	296	295	303	298
B _w Actual water vapor in gas (% by volume)	18.7	19.9	18.7	19.1
Gas Flow Rate				
Q _a Volumetric flow rate, actual (acfm)	28,300	31,000	32,700	30,700
Q _s Volumetric flow rate, standard (scfm)	19,500	21,400	22,300	21,000
Q _{std} Volumetric flow rate, dry standard (dscfm)	15,800	17,100	18,100	17,000
Sampling Data				
V _{mstd} Volume metered, standard (dscf)	73.04	79.92	78.93	77.30
%I Isokinetic sampling (%)	107.3	108.6	101.4	105.8
Laboratory Data				
m _{filter} Matter collected on filter(s) (g)	0.00092	0.00095	0.00105	
m _s Matter collected in solvent rinse(s) (g)	0.00132	0.00064	0.00068	
m _n Total FPM (g)	0.00224	0.00159	0.00173	
DLC Detection level classification	ADL	ADL	ADL	
FPM Results				
C _{sd} Particulate Concentration (lb/dscf)	6.76E-08	4.39E-08	4.83E-08	5.33E-08
E _{lb/hr} Particulate Rate (lb/hr)	0.0642	0.0450	0.0525	0.0539
E _{T/yr} Particulate Rate (Ton/yr)	0.281	0.197	0.230	0.236
E _{Fd} Particulate Rate - F _d -based (lb/MMBtu)	6.16E-04	4.02E-04	4.60E-04	4.93E-04

Average includes 3 runs.

Detection level classifications are defined as follows:

ADL = Above Detection Level - all fractions are above detection limit

042716 162556

RECEIVED
MAY 31 2016
AIR QUALITY DIV.

RESULTS**Table 2-2:
GOHT Heater Stack – Uncertainty Analysis – FPM (USEPA M5)**

	FPM Results (lb/dscf)		FPM Results (lb/hr)		FPM Results (lb/MMBtu)	
Method	5		5		5	
Run No.	1	6.76E-08	1	0.0642	1	6.16E-04
	2	4.39E-08	2	0.0450	2	4.02E-04
	3	4.83E-08	3	0.0525	3	4.60E-04
SD	1.26E-08		0.00969		1.11E-04	
AVG	5.33E-08		0.0539		4.93E-04	
RSD	23.7%		18.0%		22.5%	
N	3		3		3	
SE	7.29E-09		0.00559		6.39E-05	
RSE	13.7%		10.4%		13.0%	
P	95.0%		95.0%		95.0%	
TINV	4.303		4.30		4.30	
CI +	8.46E-08		0.0780		7.68E-04	
AVG	5.33E-08		0.0539		4.93E-04	
CI -	2.19E-08		0.0298		2.17E-04	
TB +	1.50E-07		0.128		1.34E-03	

AVG (average) is the mean value of the runs; N is the number of individual runs.

SD (standard deviation) and RSD (relative standard deviation) are measures of the variability of individual runs.

SE (standard error) and RSE (relative standard error) are measures of the variability of the average of the runs.

P (probability) is the confidence level associated with the two-tailed Student's t-distribution.

TINV (t-value) is the value of the Student's t-distribution as a function of P (probability) and N-1 (degrees of freedom).

CI (confidence interval) indicates that if the test is conducted again under the same conditions, the average would be expected to fall within the interval (CI- to CI+) about 95% of the time.

TB+ (upper tolerance bound) is the value below which 95% of future runs are expected to fall (assuming testing at the same conditions).

End of Section 2 – Results