

1.0 EXECUTIVE SUMMARY

Mostardi Platt conducted a continuous emissions monitoring system (CEMS) relative accuracy test audit (RATA) program for Holcim (US) Inc. Lafarge Alpena at the Alpena Cement Plant in Alpena, Michigan, on the below listed test locations. This report summarizes the results of the test program and test methods.

The test locations, test dates, and test parameters are summarized below.

TEST INFORMATION		
Test Locations	Test Dates	Test Parameters
Kilns 19, 20, and 21	August 31, 2022 and September 1 and 15, 2022	Mercury (Hg), Oxygen (O ₂), Carbon Dioxide (CO ₂), Nitrogen Oxides (NO _x), Sulfur Dioxide (SO ₂), Carbon Monoxide (CO), Total Hydrocarbons (THC), and Volumetric Flow Rate
Kilns 22 and 23	August 30, 2022 and September 13, 2022	O ₂ , CO ₂ , NO _x , CO, and Volumetric Flow Rate
Raw Mills 14 and 15	August 23 and 24, 2022	THC

The purpose of the test program was to demonstrate the relative accuracies of the above CEMS during the specified operating condition. The test results from this test program indicate that each CEMS meets the United States Environmental Protection Agency (USEPA) annual performance specification for relative accuracy and certification as published in 40 Code of Federal Regulations Part 60 (40CFR60).

TEST RESULTS			
Kiln 19			
Parameter	Units	Required Performance	Actual Performance
O ₂	% (Dry)	≤ 20.0% of the mean reference method value	11.35%
CO ₂	% (Wet)	≤ 20.0% of the mean reference method value	5.59%
NO _x	ppmvd	≤ 20.0% of the mean reference method value	3.28%
	lb/hr	≤ 20.0% of the mean reference method value	7.90%
	lb/ton	≤ 20.0% of the mean reference method value	6.60%
SO ₂	ppmvd	≤ 20.0% of the mean reference method value	18.76%
	lb/hr	≤ 10.0% of the applicable source standard of 136 lb/hr	5.47%
	lb/ton	≤ 10.0% of the applicable source standard of 4.07 lb/ton	3.79%
CO	ppmvd	≤ 10% of the mean reference method value	5.11%
	lb/hr	≤ 10.0% of the mean reference method value	7.93%
THC	ppmvd @ 7% O ₂	≤ 10.0% of the applicable standard of 24 ppmvd @ 7 % O ₂	6.15
Volumetric Flow	scfh	≤ 10.0% of the mean reference method value	4.44%
Hg	ug/wscm	≤ 20.0% of the mean reference method value	11.80%

Kiln 20			
Parameter	Units	Required Performance	Actual Performance
O ₂	% (Dry)	≤ 20.0% of the mean reference method value	15.91%
CO ₂	% (Wet)	≤ 20.0% of the mean reference method value	12.90%
NO _x	ppmvd	≤ 20.0% of the mean reference method value	15.98%
	lb/hr	≤ 20.0% of the mean reference method value	11.86%
	lb/ton	≤ 20.0% of the mean reference method value	12.31%
SO ₂	ppmvd	≤ 20.0% of the mean reference method value	8.35%
	lb/hr	≤ 20.0% of the mean reference method value	5.00%
	lb/ton	≤ 20.0% of the mean reference method value	5.13%
CO	ppmvd	≤ 10.0% of the mean reference method value	3.07%
	lb/hr	≤ 10.0% of the mean reference method value	4.16%
THC	ppmvd @ 7% O ₂	≤ 10.0% of the applicable standard of 24 ppmvd @ 7 % O ₂	4.51%
Volumetric Flow	scfh	≤ 10.0% of the mean reference method value	3.31%
Hg	ug/wscm	≤ 20.0% of the mean reference method value	6.53%

Kiln 21			
Parameter	Units	Required Performance	Actual Performance
O ₂	% (Dry)	≤ 20.0% of the mean reference method value	10.81%
CO ₂	% (Wet)	≤ 20.0% of the mean reference method value	5.47%
NO _x	ppmvd	≤ 20.0% of the mean reference method value	7.76%
	lb/hr	≤ 10.0% of the applicable standard of 200 lb/hr	7.31%
	lb/ton	≤ 10.0% of the applicable standard of 4.48 lb/ton	7.89%
SO ₂	ppmvd	≤ 20.0% of the mean reference method value	1.75%
	lb/hr	≤ 20.0% of the mean reference method value	3.42%
	lb/ton	≤ 10.0% of the applicable standard of 4.09 lb/ton	2.74%
CO	ppmvd	≤ 10.0% of the mean reference method value	4.19%
	lb/hr	≤ 10.0% of the mean reference method value	2.73%
THC	ppmvd @ 7% O ₂	≤ 10.0% of the applicable standard of 24 ppmvd @ 7 % O ₂	0.59%
Volumetric Flow	scfh	≤ 10.0% of the mean reference method value	1.99%
Hg	ug/wscm	≤ 20.0% of the mean reference method value	6.06%

Kiln 22			
Parameter	Units	Required Performance	Actual Performance
O ₂	% (Dry)	≤ 20.0% of the mean reference method value	3.18%
CO ₂	% (Dry)	≤ 20.0% of the mean reference method value	3.61%
NO _x	ppmvd	≤ 20.0% of the mean reference method value	14.62%
	lb/hr	≤ 20.0% of the mean reference method value	13.91%
	lb/ton	≤ 20.0% of the mean reference method value	14.12%
CO	ppmvd	≤ +/- 5ppm mean difference plus confidence coefficient	4.61 ppm + cc difference
	lb/hr	≤ 5.0% of the applicable source standard of 122.6 lb/hr	2.03%
Volumetric Flow	scfh	≤ 10.0% of the mean reference method value	6.07%

Kiln 23			
Parameter	Units	Required Performance	Actual Performance
O ₂	% (Dry)	≤ 20.0% of the mean reference method value	2.29%
CO ₂	% (Dry)	≤ 20.0% of the mean reference method value	2.37%
NO _x	ppmvd	≤ 20.0% of the mean reference method value	3.64%
	lb/hr	≤ 20.0% of the mean reference method value	7.99%
	lb/ton	≤ 20.0% of the mean reference method value	7.81%
CO	ppmvd	≤ 10.0% of the mean reference method value	6.74%
	lb/hr	≤ 20.0% of the mean reference method value	9.19%
Volumetric Flow	scfh	≤ 20.0% of the mean reference method value	9.61%

WGS			
Parameter	Units	Required Performance	Actual Performance
O ₂	% (Dry)	≤ 20.0% of the mean reference method value	0.60%
SO ₂	ppmvd	≤ 20.0% of the mean reference method value	4.96%
	lb/hr	≤ 20.0% of the mean reference method value	6.41%
	lb/ton	≤ 20.0% of the mean reference method value	9.15%
THC	ppmvd @ 7% O ₂	≤ 20.0% of the mean reference method value	10.79%
Volumetric Flow	scfh	≤ 10.0% of the mean reference method value	1.51%
Hg	ug/wscm	≤ 20.0% of the mean reference method value	19.06%

Raw Mill 14			
Parameter	Units	Required Performance	Actual Performance
THC	ppmvd	≤ 20.0% of the mean reference method value	2.13%

Raw Mill 15			
Parameter	Units	Required Performance	Actual Performance
THC	ppmvd	≤ 20.0% of the mean reference method value	2.70%

The identifications of the individuals associated with the test program are summarized below.

TEST PERSONNEL INFORMATION		
Location	Address	Contact
Test Facility	Holcim (US) Inc. 1435 Ford Avenue Alpena, Michigan 49707	Mallory Miller Area Environmental Engineer (224) 517-6896 mallory.miller@holcim.com
Testing Company Supervisor	Mostardi Platt 888 Industrial Drive Elmhurst, Illinois 60126	Stuart Sands Senior Project Manager 630-993-2663 (phone) ssands@mp-mail.com
Testing Company Personnel		Joshua Kukla Project Supervisor Jared Priesz Test Engineer Mitchell Neessen Test Engineer Joseph Devereux Test Technician Aaron Benninghoff Test Technician Willie Drake Test Technician

2.0 TEST METHODOLOGY

Emission testing was conducted following the United States Environmental Protection Agency (USEPA) methods specified in 40CFR60, Appendix A in addition the Mostardi Platt Quality Manual. Schematics of the test section diagrams and sampling trains used are included in Appendix A and B respectively. Calculation nomenclature are included in Appendix C. Copies of analyzer print-outs for each test run are included in Appendix D. CEM data and process data as provided by Holcim (US) Inc. are also included in Appendix E.

The following methodologies were used during the test program:

Method 1 Sample and Velocity Traverse Determination

Test measurement points were selected in accordance with USEPA Method 1, 40CFR60, Appendix A. The characteristics of the measurement locations are summarized below.

SAMPLE LOCATION INFORMATION							
Test Location	Duct Dimensions (Feet)	Duct Area (Square Feet)	No. of Ports	Upstream Diameters	Downstream Diameters	Test Parameter	Number of Sampling Points
Kiln 19 Breaching Duct	8 x 9.91667	79.33	3	0.730	0.790	Volumetric Flow Rate	42
						O ₂ , CO ₂ , NO _x , SO ₂ ,	3

SAMPLE LOCATION INFORMATION							
Test Location	Duct Dimensions (Feet)	Duct Area (Square Feet)	No. of Ports	Upstream Diameters	Downstream Diameters	Test Parameter	Number of Sampling Points
						CO, THC, and Hg	
Kiln 20 Breaching Duct	8 x 8.75	70.00	3	0.47	1.11	Volumetric Flow Rate	42
						O ₂ , CO ₂ , NO _x , SO ₂ , CO, THC, and Hg	3
Kiln 21 Breaching Duct	8 x 8.67	69.36	3	<0.5	>2.0	Volumetric Flow Rate	42
						O ₂ , CO ₂ , NO _x , SO ₂ , CO, THC, and Hg	3
Kiln 22 and 23 Baghouse Outlets (Identical)	10 diameter	78.54	2	0.19	1.46	Volumetric Flow Rate	16
						O ₂ , CO ₂ , NO _x , and CO	3
WGS Stack	12	113.10	4	6.0	4.5	Volumetric Flow Rate	42
						O ₂ , SO ₂ , THC, and Hg	3
Raw Mill 14 and 15 Exhausts (Identical)	5.45833 diameter	23.40	1	>2.0	~4.0	THC	3

Method 2 Volumetric Flow Rate Determination

Gas velocity was measured following USEPA Method 2, 40CFR60, Appendix A, for purposes of calculating stack gas volumetric flow rate. S-type pitot tubes, 0-10-inch differential pressure gauge, and K-type thermocouple and temperature readout were used to determine gas velocity at each sample point. All of the equipment used was calibrated in accordance with the specifications of the Method. Copies of field data sheets are included in Appendix F. Calibration data are presented in Appendix G. This testing met the performance specifications as outlined in the Method.

Method 2F Volumetric Flow Rate Determination

Gas velocity for the WGS was measured following USEPA Method 2F, 40CFR60, Appendix A, for purposes of calculating stack gas volumetric flow rate.

At each traverse point, the probe is yaw-nulled. Then, the yaw angle, differential pressures and temperatures were measured and recorded at each traverse point. The axial velocity at each traverse point is then calculated and used to calculate the stack gas volumetric flow rate using the appropriate calibration curves.

All of the equipment used is calibrated in accordance with the specifications of the method.

Method 3A Oxygen (O_2) Determination

Flue gas O_2 concentrations and emission rates were determined in accordance with USEPA Method 3A for volumetric flow molecular weight and the O_2 RATAs. A Thermo IQ 410 analyzer was used to determine the O_2 concentrations in the manner specified in the Method. The instrument has a paramagnetic detector and the O_2 operates in the nominal range of 0% to 25% with the specific range determined by the high-level calibration gas. High-range calibrations were performed using USEPA Protocol gas. Zero nitrogen (a low ppm pollutant in balance nitrogen calibration gases) was introduced during other instrument calibrations to check instrument zero. High- and a mid-range % O_2 levels in balance nitrogen were also introduced. Zero and mid-range calibrations were performed using USEPA Protocol gas after each series of test runs. Copies of the gas cylinder certifications are found in Appendix H. This testing met the performance specifications as outlined in the Method.

Method 4 Moisture Determination

Kilns 22 and 23 stack gas moisture content was determined using a Method 4 sampling train. In this technique, stack gas is drawn through a heated probe and filter assembly after which moisture is condensed through a series of four impingers. The first two impingers were charged with approximately 100 mls of deionized, distilled water. Impinger three was left empty and impinger four was charged with clean, dried silica gel. The water volumes of the impinger train were measured and the silica gel was weighed before and after each test run to determine the mass of moisture condensed.

During testing, the sample train was operated in the manner specified in USEPA Method 4. All of the data specified in Method 4 (gas volume, delta H, impinger outlet well temperature, etc.) was recorded on field data sheets included in Appendix F.

Method 25A Total Hydrocarbons (THC) Determination

The Method 25A sampling and measurement system meets the requirements for sampling of THC set forth by the United States Environmental Protection Agency (USEPA). In particular, it meets the requirements of USEPA Reference Method 25A, "Determination of Total Gaseous Organic Concentration Using a Flame Ionization Analyzer," 40CFR60, Appendix A. This method applies to the measurement of total gaseous organic concentration of hydrocarbons. With this method, the gas sample was extracted from the sample location through a heated Teflon sample line to the analyzer.

The flame ionization detectors (FID) used during this program, were Thermo 51i High-Temperature Hydrocarbon Analyzers. They are highly sensitive FIDs that provide a direct reading of organic vapor concentrations with linear ranges of 0-10, 100, 1000, and 10,000 ppm by volume. The instrument was calibrated using ultra-zero air and propane in air EPA Protocol standards for the total hydrocarbon (THC) determination. The calibrations were performed before and after sampling with calibration checks performed between each test run. Sample times and locations were logged simultaneously on data loggers.

The calibration data are found in Appendix G and copies of the calibration gas cylinder certifications are found in Appendix H.

Method 30B Mercury Determination

Per Method 30B sampling, each sample was collected on the paired in-situ sorbent traps. A tube of silica was used to capture remaining moisture prior to the sample reaching the gas metering system.

The sample train used for this test program was designed by APEX, Inc. and meets all requirements for Method 30B sampling. Samples were analyzed onsite utilizing an Ohio Lumex, Inc. analyzer for total gaseous mercury.

Mercury QA/QC data are presented in Appendix I.

Multi Gas Fourier Transform Infrared (FTIR) Detector for Moisture, CO, CO₂, NO_x, and SO₂ Determination

Extractive Fourier transform infrared (FTIR) spectrometry following USEPA Methods 3A, 6C, 7E, 10, and 320 was performed for determination of moisture, CO, CO₂, NO_x, and SO₂ at the Kilns 19, 20, and 21.

FTIR technology works on the principle that most gases absorb infrared light. This is true for all compounds with the exception of homonuclear diatomic molecules and noble gases such as: N₂, O₂, H₂, He, Ne, and Ar. Vibrations, stretches, bends, and rotations within the bonds of a molecule determine the infrared absorption distinctiveness. The absorption creates a "fingerprint" which is unique to each given compound. The quantity of infrared light absorbed is proportional to the gas concentration. Most compounds have absorbencies at different infrared frequencies, thus allowing the simultaneous analysis of multiple compounds at one time. The FTIR software compares each sample spectrum to a user-selected list of calibration references and concentration data is generated.

FTIR data was collected using an MKS MultiGas 2030 FTIR spectrometer. Analyte spiking was performed to assure the ability of the FTIR to quantify analytes in the presence of effluent gas. All analyte spikes were introduced using an instrument grade stainless steel rotometer. All QA/QC procedures were within the acceptance criteria allowance of Method 320.

FTIR QA/QC Procedures						
QA/QC Specification	Purpose	Calibration Gas Analyte	Delivery	Frequency	Acceptance Criteria	Result
M320: Zero	Verify that the FTIR is free of contaminants & zero the FTIR	Nitrogen (zero)	Direct to FTIR	pre/post test	< MDL or Noise	Pass
M320: Calibration Transfer Standard (CTS) Direct	Verify FTIR stability, confirm optical path length	Ethylene	Direct to FTIR	pretest	+/- 5% cert. value	Pass
M320: CTS Response	Verify system stability, recovery, response time	Ethylene	Sampling System	Daily, pre/post test	+/- 5% of Direct Measurement	Pass
M320: Zero Response	Verify system is free of contaminants, system bias	Nitrogen (zero)	Sampling System	pretest	Bias correct data	Pass

FTIR QA/QC Procedures						
QA/QC Specification	Purpose	Calibration Gas Analyte	Delivery	Frequency	Acceptance Criteria	Result
M320: Analyte Spike	Verify system ability to deliver and quantify analyte of interest in the presence of other effluent gases	Acetaldehyde	Dynamic Addition to Sampling System, ~1:10 effluent	pre test	+/- 30% theoretical recovery	Pass

Note: The determined concentrations from direct analyses were used in all system/spike recovery calculations.

Analyte Spiking

Spiking was performed prior to testing to verify the ability of the sampling system to quantitatively deliver a sample containing acetaldehyde and methanol from the base of the probe to the FTIR. Analyte spiking assures the ability of the FTIR sampling system to recover acid gases in the presence of effluent gas.

As part of the spiking procedure, samples were measured to determine native acetaldehyde and methanol concentrations to be used in the spike recovery calculations. The analyte spiking gases contained a low concentration of sulfur hexafluoride (SF_6). The determined SF_6 concentration in the spiked sample was used to calculate the dilution factor of the spike and thus used to calculate the concentration of the spiked HCl. The spike target dilution ratio was 1:10 or less.

The following equation illustrates the percent recovery calculation.

$$DF = \frac{SF_6(spk)}{SF_6(direct)} \quad (\text{Sec. 9.2.3 (3) USEPA Method 320})$$

$$CS = DF * Spike(dir) + Unspike(1 - DF) \quad (\text{Sec. 9.2.3 (4) USEPA Method 320})$$

DF	= Dilution factor of the spike gas
$SF_6(\text{dir})$	= SF_6 concentration measured directly in undiluted spike gas
$SF_6(\text{spk})$	= Diluted SF_6 concentration measured in a spiked sample
$Spike_{\text{dir}}$	= Concentration of the analyte in the spike standard measure by the FTIR directly
CS	= Expected concentration of the spiked samples
Unspike	= Native concentration of analytes in unspiked samples

QA/QC data are found in Appendix H. Copies of gas cylinder certifications are found in Appendix I. All concentration data were recorded on a wet, volume basis. The sample and data collection followed the procedures outlined in Method 320.

3.0 TEST RESULT SUMMARIES

3.1 Kiln 19 RATA Tables

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 19 Date: 9/15/22 Test Method: 3A					
O₂ % (dry) RATA										
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM O₂ % (dry)	CEM O₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)		
0	1	09/15/22	11:12	11:41	9.6	8.4	1.2	1.44		
1	2	09/15/22	11:42	12:11	9.5	8.4	1.1	1.21		
0	3	09/15/22	12:12	12:41	9.6	8.4	1.2	1.44		
1	4	09/15/22	13:25	13:54	9.4	8.4	1.0	1.00		
1	5	09/15/22	13:55	14:24	9.4	8.4	1.0	1.00		
1	6	09/15/22	14:25	14:54	9.4	8.4	1.0	1.00		
1	7	09/15/22	15:35	16:04	9.5	8.4	1.1	1.21		
1	8	09/15/22	16:05	16:34	9.6	8.6	1.0	1.00		
1	9	09/15/22	16:35	17:04	9.2	8.3	0.9	0.81		
0	10	09/15/22	17:25	17:54	9.6	8.4	1.2	1.44		
1	11	09/15/22	17:55	18:24	9.6	8.5	1.1	1.21		
1	12	09/15/22	18:25	18:54	9.5	8.5	1.0	1.00		
n		9								
		t(0.975)		2.306						
Mean Reference Method Value				9.456		RM avg				
Mean CEM Value				8.433		CEM avg				
Sum of Differences				9.200		di				
Mean Difference				1.022		d				
Sum of Differences Squared				9.440		di²				
Standard Deviation				0.067		sd				
Confidence Coefficient 2.5% Error (1-tail)				0.051		cc				
Relative Accuracy				11.35		RA				

I Q

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 19 Date: 9/15/22 Test Method: 3A			
CO₂ % (wet) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ₂ % (wet)	CEM CO ₂ % (wet)	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	09/15/22	11:12	11:41	16.3	17.2	-0.9	0.81
1	2	09/15/22	11:42	12:11	16.3	17.2	-0.9	0.81
0	3	09/15/22	12:12	12:41	16.1	17.1	-1.0	1.00
1	4	09/15/22	13:25	13:54	16.3	17.2	-0.9	0.81
1	5	09/15/22	13:55	14:24	16.5	17.3	-0.8	0.64
1	6	09/15/22	14:25	14:54	16.2	17.1	-0.9	0.81
1	7	09/15/22	15:35	16:04	16.4	17.3	-0.9	0.81
1	8	09/15/22	16:05	16:34	16.0	16.9	-0.9	0.81
1	9	09/15/22	16:35	17:04	16.6	17.5	-0.9	0.81
1	10	09/15/22	17:25	17:54	16.6	17.5	-0.9	0.81
0	11	09/15/22	17:55	18:24	16.1	17.1	-1.0	1.00
0	12	09/15/22	18:25	18:54	16.0	17.0	-1.0	1.00
n					9			
t(0.975)					2.306			
Mean Reference Method Value					16.356	RM avg		
Mean CEM Value					17.244	CEM avg		
Sum of Differences					-8.000	di		
Mean Difference					-0.889	d		
Sum of Differences Squared					7.120	di²		
Standard Deviation					0.033	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.026	cc		
Relative Accuracy					5.59	RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406							Location: Kiln 19	Date: 9/15/22	Test Method: 7E
NO_x ppmvd RATA									
1=accept 0=reject	Test Run	Mw	Test Date	Start Time	End Time	RM NO _x ppmvd	CEM NO _x ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	56.5	09/15/22	11:12	11:41	199.1	215.6	-16.5	272.25
1	2	56.6	09/15/22	11:42	12:11	98.8	106.2	-7.4	54.76
1	3	56.3	09/15/22	12:12	12:41	88.8	80.5	8.3	68.89
1	4	56.3	09/15/22	13:25	13:54	241.3	238.5	2.8	7.84
1	5	56.5	09/15/22	13:55	14:24	244.3	242.1	2.2	4.84
0	6	56.4	09/15/22	14:25	14:54	207.0	223.7	-16.7	278.89
1	7	56.6	09/15/22	15:35	16:04	211.3	214.1	-2.8	7.84
1	8	56.5	09/15/22	16:05	16:34	228.2	238.0	-9.8	96.04
1	9	56.4	09/15/22	16:35	17:04	210.4	205.3	5.1	26.01
0	10	56.4	09/15/22	17:25	17:54	225.7	234.0	-8.3	68.89
1	11	56.4	09/15/22	17:55	18:24	235.5	241.0	-5.5	30.25
1	12	56.6	09/15/22	18:25	18:54	230.4	237.7	-7.3	53.29
n							9		
t(0.975)							2.306		
Mean Reference Method Value							198.778	RM avg	
Mean CEM Value							200.378	CEM avg	
Sum of Differences							-14.400	di	
Mean Difference							-1.600	d	
Sum of Differences Squared							349.760	di ²	
Standard Deviation							6.391	sd	
Confidence Coefficient 2.5% Error (1-tail)							4.912	cc	
Relative Accuracy							3.28	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 19 Date: 9/15/22 Test Method: 7E, 2					
NO_x lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/hr	CEM NO _x lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	09/15/22	11:12	11:41	145.33	158.47	-13.14	172.6596	
1	2	09/15/22	11:42	12:11	69.68	77.95	-8.27	68.3929	
1	3	09/15/22	12:12	12:41	59.51	58.87	0.64	0.4096	
0	4	09/15/22	13:25	13:54	173.36	174.49	-1.13	1.2769	
0	5	09/15/22	13:55	14:24	178.98	178.86	0.12	0.0144	
1	6	09/15/22	14:25	14:54	152.06	165.08	-13.02	169.5204	
1	7	09/15/22	15:35	16:04	152.25	157.80	-5.55	30.8025	
1	8	09/15/22	16:05	16:34	168.33	173.70	-5.37	28.8369	
0	9	09/15/22	16:35	17:04	152.72	149.74	2.98	8.8804	
1	10	09/15/22	17:25	17:54	161.45	172.93	-11.48	131.7904	
1	11	09/15/22	17:55	18:24	171.09	178.65	-7.56	57.1536	
1	12	09/15/22	18:25	18:54	172.24	174.57	-2.33	5.4289	
n					9				
t(0.975)					2.306				
Mean Reference Method Value					139.104	RM avg			
Mean CEM Value					146.447	CEM avg			
Sum of Differences					-66.080	di			
Mean Difference					-7.342	d			
Sum of Differences Squared					664.995	di²			
Standard Deviation					4.741	sd			
Confidence Coefficient 2.5% Error (1-tail)					3.644	cc			
Relative Accuracy					7.90	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 19 Date: 9/15/22 Test Method: 7E, 2							
NO_x lb/ton RATA											
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/ton	CEM NO _x lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)			
1	1	09/15/22	11:12	11:41	2.6	2.8	-0.2	0.04			
1	2	09/15/22	11:42	12:11	1.2	1.4	-0.2	0.03			
0	3	09/15/22	12:12	12:41	1.1	1.0	0.1	0.00			
1	4	09/15/22	13:25	13:54	3.1	3.1	0.0	0.00			
1	5	09/15/22	13:55	14:24	3.2	3.2	0.0	0.00			
1	6	09/15/22	14:25	14:54	2.7	2.9	-0.2	0.05			
1	7	09/15/22	15:35	16:04	2.7	2.8	-0.1	0.01			
1	8	09/15/22	16:05	16:34	3.0	3.1	-0.1	0.01			
0	9	09/15/22	16:35	17:04	2.7	2.7	0.0	0.00			
1	10	09/15/22	17:25	17:54	2.9	3.1	-0.2	0.03			
1	11	09/15/22	17:55	18:24	3.0	3.2	-0.2	0.03			
1	12	09/15/22	18:25	18:54	3.0	3.1	-0.1	0.01			
		n	10								
		t(0.975)	2.262								
Mean Reference Method Value					2.740	RM avg					
Mean CEM Value					2.857	CEM avg					
Sum of Differences					-1.173	di					
Mean Difference					-0.117	d					
Sum of Differences Squared					0.209	di²					
Standard Deviation					0.089	sd					
Confidence Coefficient 2.5% Error (1-tail)					0.064	cc					
Relative Accuracy					6.60	RA					

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406						Location: Kiln 19 Date: 9/15/22 Test Method: 6C			
SO₂ ppmvd RATA									
1=accept 0=reject	Test Run	Mw	Test Date	Start Time	End Time	RM SO ₂ ppmvd	CEM SO ₂ ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	56.5	09/15/22	11:12	11:41	25.7	31.6	-5.9	34.81
1	2	56.6	09/15/22	11:42	12:11	46.2	49.1	-2.9	8.41
1	3	56.3	09/15/22	12:12	12:41	26.2	31.3	-5.1	26.01
1	4	56.3	09/15/22	13:25	13:54	23.4	27.3	-3.9	15.21
0	5	56.5	09/15/22	13:55	14:24	60.0	52.7	7.3	53.29
1	6	56.4	09/15/22	14:25	14:54	70.6	79.1	-8.5	72.25
1	7	56.6	09/15/22	15:35	16:04	45.9	51.2	-5.3	28.09
1	8	56.5	09/15/22	16:05	16:34	14.2	17.5	-3.3	10.89
0	9	56.4	09/15/22	16:35	17:04	79.3	88.8	-9.5	90.25
1	10	56.4	09/15/22	17:25	17:54	21.8	27.4	-5.6	31.36
1	11	56.4	09/15/22	17:55	18:24	22.9	26.1	-3.2	10.24
						n	9		
						t(0.975)	2.306		
						Mean Reference Method Value	32.989	RM avg	
						Mean CEM Value	37.844	CEM avg	
						Sum of Differences	-43.700	di	
						Mean Difference	-4.856	d	
						Sum of Differences Squared	237.270	di²	
						Standard Deviation	1.771	sd	
						Confidence Coefficient 2.5% Error (1-tail)	1.361	cc	
						Relative Accuracy	18.84	RA	

Client: Holcim (US) Inc. Lafarge Alpena	Location: Kiln 19							
Facility: Alpena Cement Plant	Date: 9/15/22							
Project #: M223406	Test Method: 6C, 2							
	Applicable Standard: 136							
SO2 lb/hr RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO ₂ lb/hr	CEM SO ₂ lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	09/15/22	11:12	11:41	27.43	34.28	-6.85	46.9225
1	2	09/15/22	11:42	12:11	47.77	52.89	-5.12	26.2144
0	3	09/15/22	12:12	12:41	25.71	33.82	-8.11	65.7721
1	4	09/15/22	13:25	13:54	24.59	29.36	-4.77	22.7529
0	5	09/15/22	13:55	14:24	64.31	57.17	7.14	50.9796
1	6	09/15/22	14:25	14:54	75.93	85.99	-10.06	101.2036
1	7	09/15/22	15:35	16:04	48.31	55.56	-7.25	52.5625
1	8	09/15/22	16:05	16:34	15.27	18.70	-3.43	11.7649
0	9	09/15/22	16:35	17:04	84.13	95.20	-11.07	122.5449
1	10	09/15/22	17:25	17:54	22.74	29.58	-6.84	46.7856
1	11	09/15/22	17:55	18:24	24.28	28.40	-4.12	16.9744
1	12	09/15/22	18:25	18:54	37.96	41.76	-3.80	14.4400
n		9						
t(0.975)		2.306						
Mean Reference Method Value		36.031		RM avg				
Mean CEM Value		41.836		CEM avg				
Sum of Differences		-52.240		di				
Mean Difference		-5.804		d				
Sum of Differences Squared		339.621		di²				
Standard Deviation		2.133		sd				
Confidence Coefficient 2.5% Error (1-tail)		1.640		cc				
Relative Accuracy - APS		5.47		RA				

Client: Holcim (US) Inc. Lafarge Alpena	Location: Kiln 19							
Facility: Alpena Cement Plant	Date: 9/15/22							
Project #: M223406	Test Method: 6C, 2							
Applicable Standard: 4.07								
SO2 lb/ton RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO ₂ lb/ton	CEM SO ₂ lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	09/15/22	11:12	11:41	0.5	0.6	-0.1	0.01
1	2	09/15/22	11:42	12:11	0.8	0.9	-0.1	0.01
1	3	09/15/22	12:12	12:41	0.5	0.6	-0.1	0.01
1	4	09/15/22	13:25	13:54	0.4	0.5	-0.1	0.01
0	5	09/15/22	13:55	14:24	1.1	1.0	0.1	0.01
1	6	09/15/22	14:25	14:54	1.3	1.5	-0.2	0.04
1	7	09/15/22	15:35	16:04	0.9	1.0	-0.1	0.01
1	8	09/15/22	16:05	16:34	0.3	0.3	0.0	0.00
1	9	09/15/22	16:35	17:04	1.5	1.7	-0.2	0.04
0	10	09/15/22	17:25	17:54	0.4	0.5	-0.1	0.01
1	11	09/15/22	17:55	18:24	0.4	0.5	-0.1	0.01
1	12	09/15/22	18:25	18:54	0.7	0.7	0.0	0.00
		n	9					
		t(0.975)	2.306					
		Mean Reference Method Value		0.756	RM avg			
		Mean CEM Value		0.856	CEM avg			
		Sum of Differences		-0.900	di			
		Mean Difference		-0.100	d			
		Sum of Differences Squared		0.130	di²			
		Standard Deviation		0.071	sd			
		Confidence Coefficient 2.5% Error (1-tail)		0.054	cc			
		Relative Accuracy - APS		3.79	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406						Location: Kiln 19 Date: 9/15/22 Test Method: 10			
CO ppmvd RATA									
1=accept 0=reject	Test Run	Mw	Test Date	Start Time	End Time	RM CO ppmvd	CEM CO ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)
1	1	56.5	09/15/22	11:12	11:41	85.2	90.5	-5.3	28.09
1	2	56.6	09/15/22	11:42	12:11	113.8	117.3	-3.5	12.25
0	3	56.3	09/15/22	12:12	12:41	114.3	123.1	-8.8	77.44
1	4	56.3	09/15/22	13:25	13:54	83.2	88.4	-5.2	27.04
1	5	56.5	09/15/22	13:55	14:24	80.4	85.3	-4.9	24.01
1	6	56.4	09/15/22	14:25	14:54	78.2	80.5	-2.3	5.29
0	7	56.6	09/15/22	15:35	16:04	77.9	83.5	-5.6	31.36
1	8	56.5	09/15/22	16:05	16:34	75.9	77.4	-1.5	2.25
0	9	56.4	09/15/22	16:35	17:04	88.1	96.9	-8.8	77.44
1	10	56.4	09/15/22	17:25	17:54	81.4	81.0	0.4	0.16
1	11	56.4	09/15/22	17:55	18:24	79.2	77.5	1.7	2.89
1	12	56.6	09/15/22	18:25	18:54	78.8	78.2	0.6	0.36
						n	9		
						t(0.975)	2.306		
						Mean Reference Method Value	84.011	RM avg	
						Mean CEM Value	86.233	CEM avg	
						Sum of Differences	-20.000	di	
						Mean Difference	-2.222	d	
						Sum of Differences Squared	102.340	di²	
						Standard Deviation	2.690	sd	
						Confidence Coefficient 2.5% Error (1-tail)	2.068	cc	
						Relative Accuracy	5.11	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 19 Date: 9/15/22 Test Method: 10, 2				
CO lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO lb/hr	CEM CO lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	09/15/22	11:12	11:41	37.82	40.49	-2.67	7.1289	
1	2	09/15/22	11:42	12:11	48.85	52.21	-3.36	11.2896	
0	3	09/15/22	12:12	12:41	46.58	54.85	-8.27	68.3929	
1	4	09/15/22	13:25	13:54	36.37	39.35	-2.98	8.8804	
1	5	09/15/22	13:55	14:24	35.83	38.32	-2.49	6.2001	
1	6	09/15/22	14:25	14:54	34.96	36.13	-1.17	1.3689	
1	7	09/15/22	15:35	16:04	34.15	37.46	-3.31	10.9561	
1	8	09/15/22	16:05	16:34	34.06	34.22	-0.16	0.0256	
0	9	09/15/22	16:35	17:04	38.90	43.02	-4.12	16.9744	
1	10	09/15/22	17:25	17:54	35.44	36.35	-0.91	0.8281	
1	11	09/15/22	17:55	18:24	35.04	34.92	0.12	0.0144	
0	12	09/15/22	18:25	18:54	35.84	34.94	0.90	0.8100	
					n	9			
					t(0.975)	2.306			
					Mean Reference Method Value	36.947	RM avg		
					Mean CEM Value	38.828	CEM avg		
					Sum of Differences	-16.930	di		
					Mean Difference	-1.881	d		
					Sum of Differences Squared	46.692	di²		
					Standard Deviation	1.362	sd		
					Confidence Coefficient 2.5% Error (1-tail)	1.047	cc		
					Relative Accuracy	7.93	RA		


Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 19 Date: 9/15/22 Test Method: 25A, 3A										
Applicable Standard: 24														
THC ppmvd @ 7% O₂ RATA														
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM THC ppmvd @ 7% O ₂	CEM THC ppmvd @ 7% O ₂	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)						
1	1	09/15/22	11:12	11:41	1.7	0.0	1.7	2.89						
0	2	09/15/22	11:42	12:11	2.3	0.0	2.3	5.29						
0	3	09/15/22	12:12	12:41	2.3	0.0	2.3	5.29						
1	4	09/15/22	13:25	13:54	1.4	0.0	1.4	1.96						
1	5	09/15/22	13:55	14:24	1.4	0.0	1.4	1.96						
1	6	09/15/22	14:25	14:54	1.3	0.0	1.3	1.69						
1	7	09/15/22	15:35	16:04	1.3	0.0	1.3	1.69						
1	8	09/15/22	16:05	16:34	1.3	0.0	1.3	1.69						
1	9	09/15/22	16:35	17:04	1.4	0.0	1.4	1.96						
1	10	09/15/22	17:25	17:54	1.2	0.0	1.2	1.44						
1	11	09/15/22	17:55	18:24	1.0	0.0	1.0	1.00						
0	12	09/15/22	18:25	18:54	1.0	0.0	1.0	1.00						
n t(0.975)					9									
Mean Reference Method Value					2.306									
Mean CEM Value					1.333	RM avg								
Sum of Differences					0.000	CEM avg								
Mean Difference					12.000	di								
Sum of Differences Squared					1.333	d								
Standard Deviation					16.280	di ²								
Confidence Coefficient 2.5% Error (1-tail)					0.187	sd								
Relative Accuracy - APS					0.144	cc								
					6.15	RA								

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Test Location: Kiln 19 Test Date: 9/15/2022 Test Method: 2			
Volumetric Flow RATA - Normal Load								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	Reference Method Flow SCFH	CEM Flow SCFH	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	09/15/22	11:12	11:41	6,440,199	6,520,401	-80,202	6,432,357,555
0	2	09/15/22	11:42	12:11	6,231,312	6,501,227	-269,915	72,854,289,936
0	3	09/15/22	12:12	12:41	5,910,806	6,497,145	-586,339	343,793,387,920
1	4	09/15/22	13:25	13:54	6,332,674	6,479,067	-146,393	21,430,987,683
1	5	09/15/22	13:55	14:24	6,451,346	6,534,997	-83,651	6,997,445,120
1	6	09/15/22	14:25	14:54	6,476,480	6,530,793	-54,313	2,949,881,378
1	7	09/15/22	15:35	16:04	6,344,645	6,523,520	-178,875	31,996,237,251
1	8	09/15/22	16:05	16:34	6,496,446	6,438,952	57,494	3,305,560,059
1	9	09/15/22	16:35	17:04	6,384,569	6,455,901	-71,332	5,088,222,251
0	10	09/15/22	17:25	17:54	6,293,911	6,524,488	-230,577	53,165,763,749
1	11	09/15/22	17:55	18:24	6,399,035	6,551,508	-152,473	23,248,140,633
1	12	09/15/22	18:25	18:54	6,584,520	6,503,726	80,793	6,527,574,032
		n	9					
		t(0.025)	2.306					
Mean Reference Method Value			6434434.812			RM avg		
Mean CEM Value			6504318.311			CEM avg		
Sum of Differences			-628951.489			di		
Mean Difference			-69883.499			d		
Sum of Differences Squared			107976405961.291			di²		
Standard Deviation			89458.842			sd		
Confidence Coefficient 2.5% Error (1-tail)			68764.030			cc		
Relative Accuracy			2.15			RA		

Client: Holcim (US) Inc. Lafarge Alpena	Location: Kiln 19							
Plant: Alpena Cement Plant	Date: 9/15/22							
Project #: M223406	Test Method: Sorbent Hg (30B)							
Hg ug/wscm RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM ug/wscm	CMMS ug/wscm	(RM-CMMS) Difference (di)	(RM-CMMS) Difference ² (di ²)
1	1	09/15/22	09:10	09:40	2.9	3.2	-0.3	0.09
1	2	09/15/22	09:45	10:15	2.8	3.1	-0.3	0.09
1	3	09/15/22	10:25	10:55	2.9	3.1	-0.2	0.04
1	4	09/15/22	11:12	11:42	2.9	3.3	-0.4	0.16
1	5	09/15/22	11:49	12:19	2.9	3.3	-0.4	0.16
1	6	09/15/22	12:24	12:54	3.0	3.2	-0.2	0.04
1	7	09/15/22	13:25	13:55	3.0	3.2	-0.2	0.04
1	8	09/15/22	14:05	14:35	3.0	3.1	-0.1	0.01
1	9	09/15/22	14:42	15:12	2.8	3.1	-0.3	0.09
0	10	09/15/22	15:35	16:05	2.8	3.2	-0.4	0.16
n		9						
t(0.025)		2.306						
Mean Reference Method Value		2.911		RM avg				
Mean CMM Value		3.178		CMM avg				
Sum of Differences		-2.400		di				
Mean Difference		-0.267		d				
Sum of Differences Squared		0.720		di ²				
Standard Deviation		0.100		sd				
Confidence Coefficient 2.5% Error (1-tail)		0.077		cc				
Relative Accuracy		11.80		RA				

3.2 Kiln 20 RATA Tables

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 20 Date: 8/31/22 Test Method: 3A				
O₂ % (dry) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM O₂ % (dry)	CEM O₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)
1	1	08/31/22	09:30	09:59	8.7	7.4	1.3	1.69
1	2	08/31/22	10:00	10:29	8.7	7.3	1.4	1.96
1	3	08/31/22	10:30	10:59	8.6	7.3	1.3	1.69
1	4	08/31/22	11:40	12:09	8.6	7.3	1.3	1.69
1	5	08/31/22	12:10	12:39	8.6	7.3	1.3	1.69
0	6	08/31/22	12:40	13:09	8.6	7.2	1.4	1.96
1	7	08/31/22	13:50	14:19	8.5	7.2	1.3	1.69
1	8	08/31/22	14:20	14:49	8.6	7.2	1.4	1.96
1	9	08/31/22	14:50	15:19	8.6	7.3	1.3	1.69
0	10	08/31/22	15:55	16:24	8.8	7.3	1.5	2.25
0	11	08/31/22	16:25	16:54	8.7	7.2	1.5	2.25
1	12	08/31/22	16:55	17:24	8.7	7.3	1.4	1.96
n				9				
t(0.975)				2.306				
Mean Reference Method Value				8.622	RM avg			
Mean CEM Value				7.289	CEM avg			
Sum of Differences				12.000	di			
Mean Difference				1.333	d			
Sum of Differences Squared				16.020	di²			
Standard Deviation				0.050	sd			
Confidence Coefficient 2.5% Error (1-tail)				0.038	cc			
Relative Accuracy				15.91	RA			



Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 20 Date: 8/31/22 Test Method: 3A			
CO₂ % (wet) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ₂ % (wet)	CEM CO ₂ % (wet)	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/31/22	09:30	09:59	17.3	19.5	-2.2	4.84
1	2	08/31/22	10:00	10:29	17.6	19.7	-2.1	4.41
1	3	08/31/22	10:30	10:59	17.7	19.9	-2.2	4.84
0	4	08/31/22	11:40	12:09	17.3	19.6	-2.3	5.29
1	5	08/31/22	12:10	12:39	17.3	19.6	-2.3	5.29
0	6	08/31/22	12:40	13:09	17.4	19.7	-2.3	5.29
1	7	08/31/22	13:50	14:19	17.6	19.8	-2.2	4.84
1	8	08/31/22	14:20	14:49	17.5	19.7	-2.2	4.84
1	9	08/31/22	14:50	15:19	17.4	19.6	-2.2	4.84
1	10	08/31/22	15:55	16:24	17.4	19.6	-2.2	4.84
0	11	08/31/22	16:25	16:54	17.7	20.1	-2.4	5.76
1	12	08/31/22	16:55	17:24	17.7	20.0	-2.3	5.29
n					9			
t(0.025)					2.306			
Mean Reference Method Value					17.500	RM avg		
Mean CEM Value					19.711	CEM avg		
Sum of Differences					-19.900	di		
Mean Difference					-2.211	d		
Sum of Differences Squared					44.030	di²		
Standard Deviation					0.060	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.046	cc		
Relative Accuracy					12.90	RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 20 Date: 8/31/22 Test Method: 7E			
NO_x ppmvd RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x ppmvd	CEM NO _x ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/31/22	09:30	09:59	240.9	281.7	-40.8	1664.64
1	2	08/31/22	10:00	10:29	252.5	279.2	-26.7	712.89
1	3	08/31/22	10:30	10:59	259.2	286.3	-27.1	734.41
1	4	08/31/22	11:40	12:09	254.0	286.1	-32.1	1030.41
1	5	08/31/22	12:10	12:39	252.4	287.2	-34.8	1211.04
0	6	08/31/22	12:40	13:09	242.6	289.3	-46.7	2180.89
0	7	08/31/22	13:50	14:19	244.4	302.3	-57.9	3352.41
1	8	08/31/22	14:20	14:49	254.6	298.7	-44.1	1944.81
0	9	08/31/22	14:50	15:19	249.6	295.4	-45.8	2097.64
1	10	08/31/22	15:55	16:24	246.6	243.7	2.9	8.41
1	11	08/31/22	16:25	16:54	250.4	290.3	-39.9	1592.01
1	12	08/31/22	16:55	17:24	255.7	277.1	-21.4	457.96
					n	9		
					t(0.975)	2.306		
					Mean Reference Method Value	251.811	RM avg	
					Mean CEM Value	281.144	CEM avg	
					Sum of Differences	-264.000	di	
					Mean Difference	-29.333	d	
					Sum of Differences Squared	9356.580	di²	
					Standard Deviation	14.198	sd	
					Confidence Coefficient 2.5% Error (1-tail)	10.913	cc	
					Relative Accuracy	15.98	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 20 Date: 8/31/22 Test Method: 7E, 2					
NO_x lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/hr	CEM NO _x lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	08/31/22	09:30	09:59	133.15	146.16	-13.01	169.2601	
1	2	08/31/22	10:00	10:29	131.90	145.26	-13.36	178.4896	
1	3	08/31/22	10:30	10:59	136.43	150.01	-13.58	184.4164	
1	4	08/31/22	11:40	12:09	136.41	149.78	-13.37	178.7569	
1	5	08/31/22	12:10	12:39	135.70	148.41	-12.71	161.5441	
1	6	08/31/22	12:40	13:09	131.84	151.61	-19.77	390.8529	
0	7	08/31/22	13:50	14:19	132.65	154.47	-21.82	476.1124	
1	8	08/31/22	14:20	14:49	140.11	156.40	-16.29	265.3641	
1	9	08/31/22	14:50	15:19	138.35	152.21	-13.86	192.0996	
0	10	08/31/22	15:55	16:24	133.09	125.33	7.76	60.2176	
0	11	08/31/22	16:25	16:54	135.33	155.28	-19.95	398.0025	
1	12	08/31/22	16:55	17:24	137.89	147.12	-9.23	85.1929	
					n	9			
					t(0.975)	2.306			
					Mean Reference Method Value	135.753	RM avg		
					Mean CEM Value	149.662	CEM avg		
					Sum of Differences	-125.180	di		
					Mean Difference	-13.909	d		
					Sum of Differences Squared	1805.977	di ²		
					Standard Deviation	2.847	sd		
					Confidence Coefficient 2.5% Error (1-tail)	2.189	cc		
					Relative Accuracy	11.86	RA		

Client: Holcim (US) Inc. Lafarge Alpena	Location: Kiln 20							
Facility: Alpena Cement Plant	Date: 8/31/22							
Project #: M223406	Test Method: 7E, 2							
NO_x lb/ton RATA								
CEM Analyzer Information								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/ton	CEM NO _x lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/31/22	09:30	09:59	2.4	2.6	-0.2	0.04
1	2	08/31/22	10:00	10:29	2.3	2.6	-0.3	0.09
1	3	08/31/22	10:30	10:59	2.4	2.6	-0.2	0.04
1	4	08/31/22	11:40	12:09	2.4	2.6	-0.2	0.04
1	5	08/31/22	12:10	12:39	2.4	2.6	-0.2	0.04
0	6	08/31/22	12:40	13:09	2.3	2.6	-0.3	0.09
0	7	08/31/22	13:50	14:19	2.3	2.7	-0.4	0.16
1	8	08/31/22	14:20	14:49	2.5	2.8	-0.3	0.09
1	9	08/31/22	14:50	15:19	2.4	2.7	-0.3	0.09
1	10	08/31/22	15:55	16:24	2.3	2.2	0.1	0.01
0	11	08/31/22	16:25	16:54	2.3	2.7	-0.4	0.16
1	12	08/31/22	16:55	17:24	2.4	2.6	-0.2	0.04
n		9						
		t(0.975)		2.306				
		Mean Reference Method Value		2.389		RM avg		
		Mean CEM Value		2.589		CEM avg		
		Sum of Differences		-1.800		di		
		Mean Difference		-0.200		d		
		Sum of Differences Squared		0.480		di²		
		Standard Deviation		0.122		sd		
		Confidence Coefficient 2.5% Error (1-tail)		0.094		cc		
		Relative Accuracy		12.31		RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406						Location: Kiln 20 Date: 8/31/22 Test Method: 6C			
SO₂ ppmvd RATA									
1=accept 0=reject	Test Run	Mw	Test Date	Start Time	End Time	RM SO ₂ ppmvd	CEM SO ₂ ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	55.96	08/31/22	09:30	09:59	244.4	259.4	-15.0	225.00
1	2	56.62	08/31/22	10:00	10:29	283.2	312.9	-29.7	882.09
1	3	56.99	08/31/22	10:30	10:59	245.9	265.2	-19.3	372.49
0	4	57.7	08/31/22	11:40	12:09	259.1	292.2	-33.1	1095.61
1	5	57.7	08/31/22	12:10	12:39	285.9	297.2	-11.3	127.69
1	6	57.7	08/31/22	12:40	13:09	275.5	284.3	-8.8	77.44
1	7	57.2	08/31/22	13:50	14:19	298.7	319.6	-20.9	436.81
1	8	56.6	08/31/22	14:20	14:49	260.7	271.9	-11.2	125.44
1	9	57	08/31/22	14:50	15:19	237.9	239.8	-1.9	3.61
0	10	57.52	08/31/22	15:55	16:24	250.0	281.1	-31.1	967.21
1	11	57.65	08/31/22	16:25	16:54	261.3	284.6	-23.3	542.89
0	12	57.69	08/31/22	16:55	17:24	228.2	259.8	-31.6	998.56
						n	9		
						t(0.975)	2.306		
						Mean Reference Method Value	265.944	RM avg	
						Mean CEM Value	281.656	CEM avg	
						Sum of Differences	-141.400	di	
						Mean Difference	-15.711	d	
						Sum of Differences Squared	2793.460	di ²	
						Standard Deviation	8.455	sd	
						Confidence Coefficient 2.5% Error (1-tail)	6.499	cc	
						Relative Accuracy	8.35	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 20 Date: 8/31/22 Test Method: 6C, 2			
SO2 lb/hr RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO ₂ lb/hr	CEM SO ₂ lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/31/22	09:30	09:59	187.81	186.70	1.11	1.2321
0	2	08/31/22	10:00	10:29	205.68	226.62	-20.94	438.4836
1	3	08/31/22	10:30	10:59	179.93	192.60	-12.67	160.5289
0	4	08/31/22	11:40	12:09	193.48	212.11	-18.63	347.0769
1	5	08/31/22	12:10	12:39	213.68	213.73	-0.05	0.0025
1	6	08/31/22	12:40	13:09	208.12	207.40	0.72	0.5184
1	7	08/31/22	13:50	14:19	225.40	226.69	-1.29	1.6641
1	8	08/31/22	14:20	14:49	199.50	197.75	1.75	3.0625
1	9	08/31/22	14:50	15:19	183.38	172.07	11.31	127.9161
1	10	08/31/22	15:55	16:24	187.54	201.04	-13.50	182.2500
1	11	08/31/22	16:25	16:54	196.37	211.67	-15.30	234.0900
0	12	08/31/22	16:55	17:24	171.09	191.77	-20.68	427.6624
					n	9		
					t(0.975)	2.306		
					Mean Reference Method Value	197.970	RM avg	
					Mean CEM Value	201.072	CEM avg	
					Sum of Differences	-27.920	di	
					Mean Difference	-3.102	d	
					Sum of Differences Squared	711.265	di²	
					Standard Deviation	8.836	sd	
					Confidence Coefficient 2.5% Error (1-tail)	6.792	cc	
					Relative Accuracy	5.00	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 20 Date: 8/31/22 Test Method: 6C, 2					
SO2 lb/ton RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO₂ lb/ton	CEM SO₂ lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)	
1	1	08/31/22	09:30	09:59	3.4	3.3	0.1	0.01	
0	2	08/31/22	10:00	10:29	3.6	4.0	-0.4	0.16	
1	3	08/31/22	10:30	10:59	3.2	3.4	-0.2	0.04	
0	4	08/31/22	11:40	12:09	3.4	3.7	-0.3	0.09	
1	5	08/31/22	12:10	12:39	3.7	3.7	0.0	0.00	
1	6	08/31/22	12:40	13:09	3.6	3.6	0.0	0.00	
1	7	08/31/22	13:50	14:19	3.9	4.0	-0.1	0.01	
1	8	08/31/22	14:20	14:49	3.5	3.5	0.0	0.00	
1	9	08/31/22	14:50	15:19	3.2	3.0	0.2	0.04	
1	10	08/31/22	15:55	16:24	3.3	3.5	-0.2	0.04	
1	11	08/31/22	16:25	16:54	3.4	3.7	-0.3	0.09	
0	12	08/31/22	16:55	17:24	3.0	3.3	-0.3	0.09	
n					9				
t(0.975)					2.306				
Mean Reference Method Value					3.467	RM avg			
Mean CEM Value					3.522	CEM avg			
Sum of Differences					-0.500	di			
Mean Difference					-0.056	d			
Sum of Differences Squared					0.230	di²			
Standard Deviation					0.159	sd			
Confidence Coefficient 2.5% Error (1-tail)					0.122	cc			
Relative Accuracy					5.13	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 20 Date: 8/31/22 Test Method: 10			
CO ppmvd RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ppmvd	CEM CO ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/31/22	09:30	09:59	92.8	90.4	2.4	5.76
1	2	08/31/22	10:00	10:29	94.8	95.0	-0.2	0.04
1	3	08/31/22	10:30	10:59	96.0	95.0	1.0	1.00
1	4	08/31/22	11:40	12:09	96.2	95.8	0.4	0.16
1	5	08/31/22	12:10	12:39	103.5	99.8	3.7	13.69
0	6	08/31/22	12:40	13:09	94.9	89.0	5.9	34.81
0	7	08/31/22	13:50	14:19	99.3	91.9	7.4	54.76
1	8	08/31/22	14:20	14:49	95.3	90.5	4.8	23.04
0	9	08/31/22	14:50	15:19	90.9	86.1	4.8	23.04
1	10	08/31/22	15:55	16:24	84.5	88.3	-3.8	14.44
1	11	08/31/22	16:25	16:54	83.4	83.0	0.4	0.16
1	12	08/31/22	16:55	17:24	76.2	77.8	-1.6	2.56
					n	9		
					t(0.975)	2.306		
					Mean Reference Method Value	91.411	RM avg	
					Mean CEM Value	90.622	CEM avg	
					Sum of Differences	7.100	di	
					Mean Difference	0.789	d	
					Sum of Differences Squared	60.850	di²	
					Standard Deviation	2.628	sd	
					Confidence Coefficient 2.5% Error (1-tail)	2.020	cc	
					Relative Accuracy	3.07	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 20 Date: 8/31/22 Test Method: 10, 2				
CO lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO lb/hr	CEM CO lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	08/31/22	09:30	09:59	31.23	30.62	0.61	0.3721	
0	2	08/31/22	10:00	10:29	30.12	32.35	-2.23	4.9729	
1	3	08/31/22	10:30	10:59	30.76	32.53	-1.77	3.1329	
1	4	08/31/22	11:40	12:09	31.45	32.76	-1.31	1.7161	
1	5	08/31/22	12:10	12:39	33.85	33.77	0.08	0.0064	
1	6	08/31/22	12:40	13:09	31.36	30.52	0.84	0.7056	
0	7	08/31/22	13:50	14:19	32.78	30.62	2.16	4.6656	
1	8	08/31/22	14:20	14:49	31.91	30.87	1.04	1.0816	
1	9	08/31/22	14:50	15:19	30.66	28.94	1.72	2.9584	
0	10	08/31/22	15:55	16:24	27.74	29.61	-1.87	3.4969	
1	11	08/31/22	16:25	16:54	27.42	28.82	-1.40	1.9600	
1	12	08/31/22	16:55	17:24	25.00	26.80	-1.80	3.2400	
					n	9			
					t(0.975)	2.306			
					Mean Reference Method Value	30.404	RM avg		
					Mean CEM Value	30.626	CEM avg		
					Sum of Differences	-1.990	di		
					Mean Difference	-0.221	d		
					Sum of Differences Squared	15.173	di²		
					Standard Deviation	1.357	sd		
					Confidence Coefficient 2.5% Error (1-tail)	1.043	cc		
					Relative Accuracy	4.16	RA		


Client: Holcim (US) Inc. Lafarge Alpena	Location: Kiln 20							
Facility: Alpena Cement Plant	Date: 8/31/22							
Project #: M223406	Test Method: 25A, 3A							
Applicable Standard: 24								
THC ppmvd @ 7% O₂ RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM THC ppmvd @ 7% O ₂	CEM THC ppmvd @ 7% O ₂	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/31/22	9:30	9:59	2.3	1.5	0.8	0.71
0	2	08/31/22	10:00	10:29	3.3	1.4	1.9	3.76
1	3	08/31/22	10:30	10:59	2.4	1.4	1.0	0.94
1	4	08/31/22	11:40	12:09	2.5	1.5	1.0	1.00
1	5	08/31/22	12:10	12:39	2.4	1.7	0.7	0.55
1	6	08/31/22	12:40	13:09	1.9	1.3	0.6	0.32
1	7	08/31/22	13:50	14:19	1.4	1.4	0.0	0.00
1	8	08/31/22	14:20	14:49	1.6	1.4	0.3	0.06
1	9	08/31/22	14:50	15:19	1.9	1.3	0.6	0.36
1	10	08/31/22	15:55	16:24	2.9	1.3	1.6	2.53
0	11	08/31/22	16:25	16:54	2.8	1.2	1.6	2.53
0	12	08/31/22	16:55	17:24	2.8	1.1	1.7	2.86
n t(0.975)		9						
Mean Reference Method Value		2.306						
Mean CEM Value		2.144				RM avg		
Sum of Differences		1.416				CEM avg		
Sum of Differences Squared		6.560				di		
Mean Difference		0.729				d		
Standard Deviation		6.470				di²		
Confidence Coefficient 2.5% Error (1-tail)		0.459				sd		
Relative Accuracy - APS		0.353				cc		
		4.51				RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Test Location: Kiln 20 Breaching Duct Test Date: 8/31/2022 Test Method: 2			
Volumetric Flow RATA - Normal Load								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	Reference Method Flow SCFH	CEM Flow SCFH	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	08/31/22	9:30	9:59	4,951,634	4,666,300	285,334	81,415,608,207
1	2	08/31/22	10:00	10:31	4,674,697	4,684,638	-9,941	98,816,724
1	3	08/31/22	10:30	10:59	4,710,143	4,713,382	-3,239	10,489,907
1	4	08/31/22	11:40	12:09	4,805,287	4,710,729	94,557	8,941,097,730
1	5	08/31/22	12:10	12:39	4,809,898	4,653,992	155,906	24,306,551,609
1	6	08/31/22	12:40	13:09	4,856,768	4,719,943	136,825	18,721,158,567
0	7	08/31/22	13:50	14:19	4,845,670	4,587,613	258,057	66,593,601,917
1	8	08/31/22	14:20	14:49	4,908,941	4,697,700	211,240	44,622,511,308
0	9	08/31/22	14:50	15:19	4,944,759	4,623,822	320,937	103,000,553,547
1	10	08/31/22	15:55	16:24	4,803,135	4,612,995	190,140	36,153,152,686
1	11	08/31/22	16:25	16:54	4,805,438	4,780,539	24,898	619,930,409
1	12	08/31/22	16:55	17:24	4,790,378	4,739,358	51,021	2,603,099,327
		n	9					
		t(0.025)	2.306					
Mean Reference Method Value			4796076.153				RM avg	
Mean CEM Value			4701475.266				CEM avg	
Sum of Differences			851407.990				di	
Mean Difference			94600.888				d	
Sum of Differences Squared			136076808268.494				di²	
Standard Deviation			83316.307				sd	
Confidence Coefficient 2.5% Error (1-tail)			64042.468				cc	
Relative Accuracy			3.31				RA	

Client: Holcim (US) Inc. Lafarge Alpena Plant: Alpena Cement Plant Project #: M223406					Location: Kiln 20 Stack Date: 8/31/22 Test Method: Sorbent Hg (30B)			
Hg ug/wscm RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM ug/wscm	CMMS ug/wscm	(RM-CMMS) Difference (di)	(RM-CMMS) Difference ² (di ²)
0	1	08/31/22	09:30	10:00	3.1	2.7	0.400	0.160
1	2	08/31/22	10:10	10:40	2.6	2.6	0.000	0.000
1	3	08/31/22	10:45	11:15	2.6	2.7	-0.100	0.010
1	4	08/31/22	11:40	12:10	2.7	2.7	0.000	0.000
1	5	08/31/22	12:15	12:45	2.6	2.8	-0.200	0.040
1	6	08/31/22	12:50	13:20	2.7	2.9	-0.200	0.040
1	7	08/31/22	13:50	14:20	2.8	3.0	-0.200	0.040
1	8	08/31/22	14:25	14:55	3.3	3.1	0.200	0.040
1	9	08/31/22	15:00	15:30	3.0	3.2	-0.200	0.040
1	10	08/31/22	15:55	16:25	3.2	3.2	0.000	0.000
n t(0.025)					9			
Mean Reference Method Value					2.306			
Mean CMM Value					2.833	RM avg		
Sum of Differences					2.911	CMM avg		
Mean Difference					-0.700	di		
Sum of Differences Squared					-0.078	d		
Standard Deviation					0.210	di ²		
Confidence Coefficient 2.5% Error (1-tail)					0.139	sd		
Relative Accuracy					0.107	cc		
					6.53	RA		

3.3 Kiln 21 RATA Tables

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 3A				
O₂ % (dry) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM O₂ % (dry)	CEM O₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)
1	1	09/01/22	08:45	09:14	9.1	8.2	0.9	0.81
1	2	09/01/22	09:15	09:44	8.9	8.0	0.9	0.81
1	3	09/01/22	09:45	10:14	8.9	8.0	0.9	0.81
1	4	09/01/22	10:50	11:19	8.9	8.0	0.9	0.81
0	5	09/01/22	11:20	11:49	8.9	7.9	1.0	1.00
1	6	09/01/22	11:50	12:19	9.0	8.0	1.0	1.00
1	7	09/01/22	13:00	13:29	8.6	7.7	0.9	0.81
1	8	09/01/22	13:30	13:59	8.8	7.8	1.0	1.00
1	9	09/01/22	14:00	14:29	8.7	7.8	0.9	0.81
0	10	09/01/22	15:10	15:39	8.6	7.6	1.0	1.00
0	11	09/01/22	15:40	16:09	8.6	7.6	1.0	1.00
1	12	09/01/22	16:10	16:39	8.7	7.8	0.9	0.81
n				9				
t(0.975)				2.306				
Mean Reference Method Value				8.844	RM avg			
Mean CEM Value				7.922	CEM avg			
Sum of Differences				8.300	di			
Mean Difference				0.922	d			
Sum of Differences Squared				7.670	di²			
Standard Deviation				0.044	sd			
Confidence Coefficient 2.5% Error (1-tail)				0.034	cc			
Relative Accuracy				10.81	RA			



Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 21 Date: 9/1/22 Test Method: 3A			
CO₂ % (wet) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ₂ % (wet)	CEM CO ₂ % (wet)	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	09/01/22	08:45	09:14	15.5	16.4	-0.9	0.81
1	2	09/01/22	09:15	09:44	16.3	17.1	-0.8	0.64
1	3	09/01/22	09:45	10:14	16.5	17.3	-0.8	0.64
1	4	09/01/22	10:50	11:19	16.2	17.1	-0.9	0.81
1	5	09/01/22	11:20	11:49	16.4	17.2	-0.8	0.64
0	6	09/01/22	11:50	12:19	16.1	17.0	-0.9	0.81
1	7	09/01/22	13:00	13:29	17.2	17.5	-0.3	0.09
0	8	09/01/22	13:30	13:59	16.1	17.3	-1.2	1.44
1	9	09/01/22	14:00	14:29	16.4	17.2	-0.8	0.64
1	10	09/01/22	15:10	15:39	16.4	17.3	-0.9	0.81
1	11	09/01/22	15:40	16:09	16.8	17.6	-0.8	0.64
1	12	09/01/22	16:10	16:39	16.7	17.5	-0.8	0.64
n					9			
t(0.975)					2.306			
Mean Reference Method Value					16.544	RM avg		
Mean CEM Value					17.311	CEM avg		
Sum of Differences					-6.900	di		
Mean Difference					-0.767	d		
Sum of Differences Squared					5.550	di ²		
Standard Deviation					0.180	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.139	cc		
Relative Accuracy					5.47	RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 7E					
NO_x ppmvd RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x ppmvd	CEM NO _x ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	09/01/22	08:45	09:14	118.3	136.4	-18.1	327.61	
0	2	09/01/22	09:15	09:44	106.6	135.3	-28.7	823.69	
1	3	09/01/22	09:45	10:14	139.3	151.9	-12.6	158.76	
0	4	09/01/22	10:50	11:19	205.1	178.1	27.0	729.00	
1	5	09/01/22	11:20	11:49	139.8	130.4	9.4	88.36	
1	6	09/01/22	11:50	12:19	162.9	148.3	14.6	213.16	
1	7	09/01/22	13:00	13:29	148.5	144.8	3.7	13.69	
1	8	09/01/22	13:30	13:59	145.1	162.0	-16.9	285.61	
1	9	09/01/22	14:00	14:29	140.1	147.5	-7.4	54.76	
1	10	09/01/22	15:10	15:39	131.0	112.3	18.7	349.69	
1	11	09/01/22	15:40	16:09	137.9	121.2	16.7	278.89	
1	12	09/01/22	16:10	16:39	152.5	160.4	-7.9	62.41	
n					10				
t(0.975)					2.262				
Mean Reference Method Value					141.540	RM avg			
Mean CEM Value					141.520	CEM avg			
Sum of Differences					0.200	di			
Mean Difference					0.020	d			
Sum of Differences Squared					1832.940	di²			
Standard Deviation					14.271	sd			
Confidence Coefficient 2.5% Error (1-tail)					10.208	cc			
Relative Accuracy					7.23	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 7E, 2					
NO_x lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/hr	CEM NO _x lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	09/01/22	08:45	09:14	65.37	74.40	-9.03	81.5409	
0	2	09/01/22	09:15	09:44	59.26	73.04	-13.78	189.8884	
1	3	09/01/22	09:45	10:14	78.01	82.87	-4.86	23.6196	
0	4	09/01/22	10:50	11:19	114.11	96.70	17.41	303.1081	
1	5	09/01/22	11:20	11:49	76.89	72.90	3.99	15.9201	
1	6	09/01/22	11:50	12:19	90.49	81.60	8.89	79.0321	
1	7	09/01/22	13:00	13:29	83.39	79.80	3.59	12.8881	
1	8	09/01/22	13:30	13:59	82.02	90.30	-8.28	68.5584	
1	9	09/01/22	14:00	14:29	76.17	80.80	-4.63	21.4369	
0	10	09/01/22	15:10	15:39	72.21	59.70	12.51	156.5001	
1	11	09/01/22	15:40	16:09	73.94	62.90	11.04	121.8816	
1	12	09/01/22	16:10	16:39	83.43	85.40	-1.97	3.8809	
n					9				
t(0.975)					2.306				
Mean Reference Method Value					78.857	RM avg			
Mean CEM Value					78.997	CEM avg			
Sum of Differences					-1.260	di			
Mean Difference					-0.140	d			
Sum of Differences Squared					428.759	di²			
Standard Deviation					7.319	sd			
Confidence Coefficient 2.5% Error (1-tail)					5.626	cc			
Relative Accuracy					7.31	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 7E, 2							
NOx lb/ton RATA											
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NOx lb/ton	CEM NOx lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)			
1	1	09/01/22	08:45	09:14	1.5	1.7	-0.2	0.04			
0	2	09/01/22	09:15	09:44	1.4	1.7	-0.3	0.09			
1	3	09/01/22	09:45	10:14	1.8	2.0	-0.2	0.04			
0	4	09/01/22	10:50	11:19	2.7	2.3	0.4	0.16			
1	5	09/01/22	11:20	11:49	1.8	1.7	0.1	0.01			
1	6	09/01/22	11:50	12:19	2.1	1.9	0.2	0.04			
1	7	09/01/22	13:00	13:29	1.9	1.8	0.1	0.01			
1	8	09/01/22	13:30	13:59	1.9	2.1	-0.2	0.04			
1	9	09/01/22	14:00	14:29	1.7	1.8	-0.1	0.01			
0	10	09/01/22	15:10	15:39	1.6	1.3	0.3	0.09			
1	11	09/01/22	15:40	16:09	1.7	1.4	0.3	0.09			
1	12	09/01/22	16:10	16:39	2.0	2.0	0.0	0.00			
		n	9								
		t(0.975)	2.306								
Mean Reference Method Value					1.822	RM avg					
Mean CEM Value					1.822	CEM avg					
Sum of Differences					0.000	di					
Mean Difference					0.000	d					
Sum of Differences Squared					0.280	di²					
Standard Deviation					0.187	sd					
Confidence Coefficient 2.5% Error (1-tail)					0.144	cc					
Relative Accuracy					7.89	RA					

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 6C					
SO₂ ppmvd RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO ₂ ppmvd	CEM SO ₂ ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	09/01/22	08:45	09:14	199.9	200.2	-0.3	0.09	
1	2	09/01/22	09:15	09:44	208.2	209.2	-1.0	1.00	
0	3	09/01/22	09:45	10:14	32.1	46.9	-14.8	219.04	
1	4	09/01/22	10:50	11:19	55.5	50.8	4.7	22.09	
1	5	09/01/22	11:20	11:49	150.0	154.1	-4.1	16.81	
1	6	09/01/22	11:50	12:19	164.0	159.4	4.6	21.16	
0	7	09/01/22	13:00	13:29	147.5	155.1	-7.6	57.76	
1	8	09/01/22	13:30	13:59	59.1	61.7	-2.6	6.76	
1	9	09/01/22	14:00	14:29	64.2	62.3	1.9	3.61	
1	10	09/01/22	15:10	15:39	134.2	135.2	-1.0	1.00	
1	11	09/01/22	15:40	16:09	196.0	198.2	-2.2	4.84	
0	12	09/01/22	16:10	16:39	112.7	136.5	-23.8	566.44	
n					9				
t(0.025)					2.306				
Mean Reference Method Value					136.789	RM avg			
Mean CEM Value					136.789	CEM avg			
Sum of Differences					0.000	di			
Mean Difference					0.000	d			
Sum of Differences Squared					77.360	di²			
Standard Deviation					3.110	sd			
Confidence Coefficient 2.5% Error (1-tail)					2.390	cc			
Relative Accuracy					1.75	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 6C, 2					
SO2 lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO₂ lb/hr	CEM SO₂ lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)	
1	1	09/01/22	08:45	09:14	153.55	151.80	1.75	3.0625	
1	2	09/01/22	09:15	09:44	160.89	157.22	3.67	13.4689	
0	3	09/01/22	09:45	10:14	25.03	35.35	-10.32	106.5024	
1	4	09/01/22	10:50	11:19	42.96	38.10	4.86	23.6196	
1	5	09/01/22	11:20	11:49	114.70	118.60	-3.90	15.2100	
0	6	09/01/22	11:50	12:19	126.60	121.50	5.10	26.0100	
1	7	09/01/22	13:00	13:29	115.19	118.90	-3.71	13.7641	
1	8	09/01/22	13:30	13:59	46.39	47.80	-1.41	1.9881	
1	9	09/01/22	14:00	14:29	48.52	47.40	1.12	1.2544	
1	10	09/01/22	15:10	15:39	102.86	98.90	3.96	15.6816	
1	11	09/01/22	15:40	16:09	146.08	143.30	2.78	7.7284	
0	12	09/01/22	16:10	16:39	85.69	101.10	-15.41	237.4681	
n					9				
t(0.975)					2.306				
Mean Reference Method Value					103.460	RM avg			
Mean CEM Value					102.447	CEM avg			
Sum of Differences					9.120	di			
Mean Difference					1.013	d			
Sum of Differences Squared					95.778	di²			
Standard Deviation					3.289	sd			
Confidence Coefficient 2.5% Error (1-tail)					2.528	cc			
Relative Accuracy					3.42	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 6C, 2					
SO₂ lb/ton RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO ₂ lb/ton	CEM SO ₂ lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	09/01/22	08:45	09:14	3.6	3.6	0.0	0.00	
1	2	09/01/22	09:15	09:44	3.8	3.7	0.1	0.01	
0	3	09/01/22	09:45	10:14	0.6	0.8	-0.2	0.04	
0	4	09/01/22	10:50	11:19	1.0	0.9	0.1	0.01	
1	5	09/01/22	11:20	11:49	2.7	2.8	-0.1	0.01	
1	6	09/01/22	11:50	12:19	2.9	2.8	0.1	0.01	
1	7	09/01/22	13:00	13:29	2.6	2.7	-0.1	0.01	
1	8	09/01/22	13:30	13:59	1.1	1.1	0.0	0.00	
1	9	09/01/22	14:00	14:29	1.1	1.1	0.0	0.00	
1	10	09/01/22	15:10	15:39	2.3	2.2	0.1	0.01	
1	11	09/01/22	15:40	16:09	3.3	3.3	0.0	0.00	
0	12	09/01/22	16:10	16:39	2.0	2.4	-0.4	0.16	
n					9				
t(0.975)					2.306				
Mean Reference Method Value					2.600	RM avg			
Mean CEM Value					2.589	CEM avg			
Sum of Differences					0.100	di			
Mean Difference					0.011	d			
Sum of Differences Squared					0.050	di²			
Standard Deviation					0.078	sd			
Confidence Coefficient 2.5% Error (1-tail)					0.060	cc			
Relative Accuracy					2.74	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 21 Date: 9/1/22 Test Method: 10			
CO ppmvd RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ppmvd	CEM CO ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	09/01/22	08:45	09:14	52.4	55.4	-3.0	9.00
1	2	09/01/22	09:15	09:44	56.7	57.4	-0.7	0.49
1	3	09/01/22	09:45	10:14	50.1	52.8	-2.7	7.29
1	4	09/01/22	10:50	11:19	40.7	42.7	-2.0	4.00
1	5	09/01/22	11:20	11:49	53.7	55.3	-1.6	2.56
1	6	09/01/22	11:50	12:19	50.1	50.9	-0.8	0.64
1	7	09/01/22	13:00	13:29	55.3	57.3	-2.0	4.00
0	8	09/01/22	13:30	13:59	47.8	51.6	-3.8	14.44
1	9	09/01/22	14:00	14:29	53.7	55.0	-1.3	1.69
1	10	09/01/22	15:10	15:39	56.2	58.1	-1.9	3.61
1	11	09/01/22	15:40	16:09	54.6	56.8	-2.2	4.84
0	12	09/01/22	16:10	16:39	45.8	48.7	-2.9	8.41
					n	9		
					t(0.975)	2.306		
					Mean Reference Method Value	52.344	RM avg	
					Mean CEM Value	54.033	CEM avg	
					Sum of Differences	-15.200	di	
					Mean Difference	-1.689	d	
					Sum of Differences Squared	29.120	di²	
					Standard Deviation	0.657	sd	
					Confidence Coefficient 2.5% Error (1-tail)	0.505	cc	
					Relative Accuracy	4.19	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 21 Date: 9/1/22 Test Method: 10, 2				
CO lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO lb/hr	CEM CO lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)	
0	1	09/01/22	08:45	09:14	17.60	18.42	-0.82	0.6724	
1	2	09/01/22	09:15	09:44	19.17	18.89	0.28	0.0784	
1	3	09/01/22	09:45	10:14	17.08	17.55	-0.47	0.2209	
1	4	09/01/22	10:50	11:19	13.77	14.20	-0.43	0.1849	
0	5	09/01/22	11:20	11:49	17.96	18.70	-0.74	0.5476	
1	6	09/01/22	11:50	12:19	16.94	17.00	-0.06	0.0036	
1	7	09/01/22	13:00	13:29	18.90	19.30	-0.40	0.1600	
0	8	09/01/22	13:30	13:59	16.43	17.50	-1.07	1.1449	
1	9	09/01/22	14:00	14:29	17.78	18.30	-0.52	0.2704	
1	10	09/01/22	15:10	15:39	18.84	18.60	0.24	0.0576	
1	11	09/01/22	15:40	16:09	17.83	17.90	-0.07	0.0049	
1	12	09/01/22	16:10	16:39	15.24	15.80	-0.56	0.3136	
					n	9			
					t(0.975)	2.306			
					Mean Reference Method Value	17.283	RM avg		
					Mean CEM Value	17.504	CEM avg		
					Sum of Differences	-1.990	di		
					Mean Difference	-0.221	d		
					Sum of Differences Squared	1.294	di²		
					Standard Deviation	0.327	sd		
					Confidence Coefficient 2.5% Error (1-tail)	0.251	cc		
					Relative Accuracy	2.73	RA		


Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 21 Date: 9/1/22 Test Method: 25A, 3A										
Applicable Standard: 24														
THC ppmvd @ 7% O₂ RATA														
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM THC ppmvd @ 7% O ₂	CEM THC ppmvd @ 7% O ₂	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)						
0	1	09/01/22	8:45	9:14	1.4	0.8	0.6	0.41						
0	2	09/01/22	9:15	9:44	1.5	0.7	0.8	0.59						
0	3	09/01/22	9:45	10:14	1.6	0.9	0.7	0.52						
1	4	09/01/22	10:50	11:19	0.7	0.7	0.0	0.00						
1	5	09/01/22	11:20	11:49	0.9	0.8	0.1	0.01						
1	6	09/01/22	11:50	12:19	0.9	0.7	0.2	0.04						
1	7	09/01/22	13:00	13:29	0.7	0.8	-0.1	0.01						
1	8	09/01/22	13:30	13:59	0.9	0.7	0.2	0.04						
1	9	09/01/22	14:00	14:29	0.7	0.8	-0.1	0.01						
1	10	09/01/22	15:10	15:39	0.9	1.0	-0.1	0.01						
1	11	09/01/22	15:40	16:09	0.6	0.8	-0.2	0.04						
1	12	09/01/22	16:10	16:39	0.5	0.7	-0.2	0.04						
n t(0.975)					9									
Mean Reference Method Value					2.306									
Mean CEM Value					0.756	RM avg								
Sum of Differences					0.778	CEM avg								
Mean Difference					-0.200	di								
Sum of Differences Squared					-0.022	d								
Standard Deviation					0.200	di²								
Confidence Coefficient 2.5% Error (1-tail)					0.156	sd								
Relative Accuracy - APS					0.120	cc								
Relative Accuracy - APS					0.59	RA								

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Test Location: Kiln 21 Breaching Duct Test Date: 9/1/2022 Test Method: 2			
Volumetric Flow RATA - Normal Load								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	Reference Method Flow SCFH	CEM Flow SCFH	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	09/01/22	8:45	9:14	4,970,127	4,918,246	51,881	2,691,650,415
0	2	09/01/22	9:15	9:44	4,995,855	4,860,702	135,152	18,266,087,916
1	3	09/01/22	9:45	10:14	5,038,753	4,917,294	121,459	14,752,272,575
1	4	09/01/22	10:50	11:19	5,000,788	4,895,744	105,044	11,034,237,519
1	5	09/01/22	11:20	11:49	4,941,665	4,996,772	-55,108	3,036,849,500
1	6	09/01/22	11:50	12:19	4,990,830	4,940,595	50,235	2,523,585,699
1	7	09/01/22	13:00	13:29	5,029,971	4,970,824	59,147	3,498,402,496
1	8	09/01/22	13:30	13:59	5,072,755	5,027,675	45,080	2,032,188,970
1	9	09/01/22	14:00	14:29	4,900,245	4,942,785	-42,539	1,809,568,691
0	10	09/01/22	15:10	15:39	5,007,474	4,807,864	199,610	39,844,296,112
0	11	09/01/22	15:40	16:09	4,859,735	4,712,626	147,109	21,641,034,959
1	12	09/01/22	16:10	16:39	4,947,960	4,830,124	117,837	13,885,470,907
		n	9					
		t(0.975)	2.306					
Mean Reference Method Value			4988121.636			RM avg		
Mean CEM Value			4937784.256			CEM avg		
Sum of Differences			453036.421			di		
Mean Difference			50337.380			d		
Sum of Differences Squared			55264226772.911			di ²		
Standard Deviation			63698.077			sd		
Confidence Coefficient 2.5% Error (1-tail)			48962.589			cc		
Relative Accuracy			1.99			RA		

Client: Holcim (US) Inc. Lafarge Alpena Plant: Alpena Cement Plant Project #: M223406			Location: Kiln 21 Stack Date: 9/1/22 Test Method: Sorbent Hg (30B)					
Hg ug/wscm RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM ug/wscm	CMMS ug/wscm	(RM-CMMS) Difference (di)	(RM-CMMS) Difference ² (di ²)
0	1	09/01/22	08:45	09:15	2.7	2.4	0.3	0.09
0	2	09/01/22	09:20	09:50	2.6	2.3	0.3	0.09
0	3	09/01/22	09:55	10:25	2.2	1.9	0.3	0.09
1	4	09/01/22	10:50	11:20	2.5	2.4	0.1	0.01
1	5	09/01/22	11:25	11:55	2.6	2.5	0.1	0.01
1	6	09/01/22	12:00	12:30	2.4	2.5	-0.1	0.01
1	7	09/01/22	13:00	13:30	2.6	2.6	0.0	0.00
1	8	09/01/22	13:35	14:05	2.7	2.6	0.1	0.01
1	9	09/01/22	14:10	14:40	2.7	2.6	0.1	0.01
1	10	09/01/22	15:10	15:40	2.9	2.7	0.2	0.04
			n	7				
			t(0.025)	2.447				
			Mean Reference Method Value	2.629	RM avg			
			Mean CMM Value	2.557	CMM avg			
			Sum of Differences	0.500	di			
			Mean Difference	0.071	d			
			Sum of Differences Squared	0.090	di ²			
			Standard Deviation	0.095	sd			
			Confidence Coefficient 2.5% Error (1-tail)	0.088	cc			
			Relative Accuracy	6.06	RA			

3.4 Kiln 22 RATA Tables

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 22 Baghouse Outlet Date: 8/30/22 Test Method: 3A			
O₂ % (dry) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM O ₂ % (dry)	CEM O ₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/30/22	08:45	09:05	8.1	7.9	0.2	0.04
1	2	08/30/22	09:06	09:26	8.4	8.1	0.3	0.09
1	3	08/30/22	09:27	09:47	8.5	8.3	0.2	0.04
1	4	08/30/22	10:10	10:30	8.8	8.5	0.3	0.09
1	5	08/30/22	10:31	10:51	8.8	8.6	0.2	0.04
1	6	08/30/22	10:52	11:12	8.8	8.5	0.3	0.09
1	7	08/30/22	11:35	11:55	8.4	8.2	0.2	0.04
0	8	08/30/22	11:56	12:16	8.8	8.5	0.3	0.09
0	9	08/30/22	12:17	12:37	11.1	10.9	0.2	0.04
1	10	08/30/22	13:10	13:30	8.9	8.7	0.2	0.04
1	11	08/30/22	13:31	13:51	8.3	8.1	0.2	0.04
0	12	08/30/22	13:52	14:12	8.4	8.1	0.3	0.09
n					9			
t(0.975)					2.306			
Mean Reference Method Value					8.556	RM avg		
Mean CEM Value					8.322	CEM avg		
Sum of Differences					2.100	di		
Mean Difference					0.233	d		
Sum of Differences Squared					0.510	di²		
Standard Deviation					0.050	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.038	cc		
Relative Accuracy					3.18	RA		



Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 22 Baghouse Outlet Date: 8/30/22 Test Method: 3A			
CO₂ % (dry) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ₂ % (dry)	CEM CO ₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/30/22	08:45	09:05	19.1	19.1	0.0	0.00
1	2	08/30/22	09:06	09:26	18.2	18.3	-0.1	0.01
1	3	08/30/22	09:27	09:47	18.1	18.0	0.1	0.01
1	4	08/30/22	10:10	10:30	17.4	18.0	-0.6	0.36
1	5	08/30/22	10:31	10:51	17.6	18.0	-0.4	0.16
1	6	08/30/22	10:52	11:12	17.7	18.3	-0.6	0.36
1	7	08/30/22	11:35	11:55	17.9	18.7	-0.8	0.64
0	8	08/30/22	11:56	12:16	17.2	18.1	-0.9	0.81
0	9	08/30/22	12:17	12:37	13.5	13.6	-0.1	0.01
1	10	08/30/22	13:10	13:30	14.3	14.9	-0.6	0.36
1	11	08/30/22	13:31	13:51	16.8	17.3	-0.5	0.25
0	12	08/30/22	13:52	14:12	17.5	18.4	-0.9	0.81
n					9			
t(0.975)					2.306			
Mean Reference Method Value					17.456	RM avg		
Mean CEM Value					17.844	CEM avg		
Sum of Differences					-3.500	di		
Mean Difference					-0.389	d		
Sum of Differences Squared					2.150	di²		
Standard Deviation					0.314	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.241	cc		
Relative Accuracy					3.61	RA		

Client: Holcim (US) Inc. Lafarge Alpena		Location: Kiln 22 Baghouse Outlet						
Facility: Alpena Cement Plant		Date: 8/30/22						
Project #: M223406		Test Method: 7E						
NO_x ppmvd RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x ppmvd	CEM NO _x ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/30/22	08:45	09:05	326.3	371.5	-45.2	2043.04
1	2	08/30/22	09:06	09:26	403.3	450.5	-47.2	2227.84
1	3	08/30/22	09:27	09:47	424.3	489.0	-64.7	4186.09
1	4	08/30/22	10:10	10:30	471.5	536.8	-65.3	4264.09
1	5	08/30/22	10:31	10:51	422.2	488.8	-66.6	4435.56
1	6	08/30/22	10:52	11:12	307.5	355.7	-48.2	2323.24
1	7	08/30/22	11:35	11:55	223.1	247.9	-24.8	615.04
0	8	08/30/22	11:56	12:16	316.9	354.6	-37.7	1421.29
0	9	08/30/22	12:17	12:37	187.2	179.0	8.2	67.24
1	10	08/30/22	13:10	13:30	822.5	890.8	-68.3	4664.89
0	11	08/30/22	13:31	13:51	596.4	692.7	-96.3	9273.69
1	12	08/30/22	13:52	14:12	574.4	626.8	-52.4	2745.76
		n	9					
		t(0.975)	2.306					
		Mean Reference Method Value		441.678	RM avg			
		Mean CEM Value		495.311	CEM avg			
		Sum of Differences		-482.700	di			
		Mean Difference		-53.633	d			
		Sum of Differences Squared		27505.550	di²			
		Standard Deviation		14.216	sd			
		Confidence Coefficient 2.5% Error (1-tail)		10.927	cc			
		Relative Accuracy		14.62	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406						Location: Kiln 22 Baghouse Outlet Date: 8/30/22 Test Method: 7E, 2			
NO_x lb/hr RATA									
1=accept 0=reject	Test Run	Mw	Test Date	Start Time	End Time	RM NO _x lb/hr	CEM NO _x lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	62.9	08/30/22	08:45	09:05	262.16	306.20	-44.04	1939.5216
1	2	63.4	08/30/22	09:06	09:26	326.45	365.80	-39.35	1548.4225
1	3	62.9	08/30/22	09:27	09:47	349.21	398.00	-48.79	2380.4641
1	4	65.25	08/30/22	10:10	10:30	391.47	436.40	-44.93	2018.7049
0	5	65.16	08/30/22	10:31	10:51	348.84	401.22	-52.38	2743.6644
1	6	65.67	08/30/22	10:52	11:12	255.49	294.51	-39.02	1522.5604
1	7	66.24	08/30/22	11:35	11:55	178.70	207.92	-29.22	853.8084
0	8	28.98	08/30/22	11:56	12:16	261.06	293.98	-32.92	1083.7264
0	9	18.17	08/30/22	12:17	12:37	155.51	121.97	33.54	1124.9316
1	10	62.33	08/30/22	13:10	13:30	688.83	608.97	79.86	6377.6196
1	11	63	08/30/22	13:31	13:51	474.45	484.68	-10.23	104.6529
1	12	63.08	08/30/22	13:52	14:12	458.65	475.89	-17.24	297.2176
n						9			
t(0.975)						2.306			
Mean Reference Method Value						376.157	RM avg		
Mean CEM Value						397.597	CEM avg		
Sum of Differences						-192.960	di		
Mean Difference						-21.440	d		
Sum of Differences Squared						17042.972	di²		
Standard Deviation						40.165	sd		
Confidence Coefficient 2.5% Error (1-tail)						30.874	cc		
Relative Accuracy						13.91	RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 22 Baghouse Outlet Date: 8/30/22 Test Method: 7E, 2			
NO_x lb/ton RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/ton	CEM NO _x lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	08/30/22	08:45	09:05	4.20	4.90	-0.70	0.4900
1	2	08/30/22	09:06	09:26	5.10	5.80	-0.70	0.4900
1	3	08/30/22	09:27	09:47	5.60	6.30	-0.70	0.4900
1	4	08/30/22	10:10	10:30	6.00	6.70	-0.70	0.4900
1	5	08/30/22	10:31	10:51	5.40	6.20	-0.80	0.6400
1	6	08/30/22	10:52	11:12	3.90	4.50	-0.60	0.3600
1	7	08/30/22	11:35	11:55	2.70	3.20	-0.50	0.2500
0	8	08/30/22	11:56	12:16	9.00	32.80	-23.80	566.4400
0	9	08/30/22	12:17	12:37	8.60	18.50	-9.90	98.0100
1	10	08/30/22	13:10	13:30	11.10	9.80	1.30	1.6900
1	11	08/30/22	13:31	13:51	7.50	7.70	-0.20	0.0400
1	12	08/30/22	13:52	14:12	7.30	7.60	-0.30	0.0900
					n	9		
					t(0.975)	2.306		
					Mean Reference Method Value	6.067	RM avg	
					Mean CEM Value	6.422	CEM avg	
					Sum of Differences	-3.200	di	
					Mean Difference	-0.356	d	
					Sum of Differences Squared	4.540	di²	
					Standard Deviation	0.652	sd	
					Confidence Coefficient 2.5% Error (1-tail)	0.501	cc	
					Relative Accuracy	14.12	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 22 Baghouse Outlet Date: 8/30/22 Test Method: 10			
CO ppmvd RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ppmvd	CEM CO ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/30/22	08:45	09:05	56.2	61.3	-5.1	26.01
1	2	08/30/22	09:06	09:26	36.5	42.6	-6.1	37.21
1	3	08/30/22	09:27	09:47	30.1	35.1	-5.0	25.00
1	4	08/30/22	10:10	10:30	32.7	33.5	-0.8	0.64
1	5	08/30/22	10:31	10:51	33.9	34.0	-0.1	0.01
1	6	08/30/22	10:52	11:12	39.0	41.8	-2.8	7.84
1	7	08/30/22	11:35	11:55	51.9	56.0	-4.1	16.81
0	8	08/30/22	11:56	12:16	31.3	37.8	-6.5	42.25
0	9	08/30/22	12:17	12:37	50.8	44.9	5.9	34.81
1	10	08/30/22	13:10	13:30	33.4	33.0	0.4	0.16
1	11	08/30/22	13:31	13:51	70.4	68.4	2.0	4.00
0	12	08/30/22	13:52	14:12	51.7	57.9	-6.2	38.44
					n	9		
					t(0.975)	2.306		
					Mean Reference Method Value	42.678	RM avg	
					Mean CEM Value	45.078	CEM avg	
					Sum of Differences	-21.600	di	
					Mean Difference	-2.400	d	
					Sum of Differences Squared	117.680	di²	
					Standard Deviation	2.869	sd	
					Confidence Coefficient 2.5% Error (1-tail)	2.205	cc	
					Relative Accuracy - APS	4.61	ppm + cc difference^A	


^A Relative accuracy based upon alternate performance standard of +/- 5 ppm CO plus the confidence coefficient.

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406						Location: Kiln 22 Baghouse Outlet Date: 8/30/22 Test Method: 10, 2 Applicable Standard: 122.6			
CO lb/hr RATA CEM Analyzer Information									
1=accept 0=reject	Test Run	Mw	Test Date	Start Time	End Time	RM CO lb/hr	CEM CO lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	62.9	08/30/22	08:45	09:05	27.48	30.59	-3.11	9.6721
1	2	63.4	08/30/22	09:06	09:26	17.96	21.09	-3.13	9.7969
1	3	62.9	08/30/22	09:27	09:47	15.08	17.39	-2.31	5.3361
1	4	65.25	08/30/22	10:10	10:30	16.50	16.56	-0.06	0.0036
1	5	65.16	08/30/22	10:31	10:51	17.02	16.99	0.03	0.0009
1	6	65.67	08/30/22	10:52	11:12	19.71	21.12	-1.41	1.9881
0	7	66.24	08/30/22	11:35	11:55	25.29	28.61	-3.32	11.0224
0	8	28.98	08/30/22	11:56	12:16	15.69	19.26	-3.57	12.7449
0	9	18.17	08/30/22	12:17	12:37	25.65	18.78	6.87	47.1969
1	10	62.33	08/30/22	13:10	13:30	17.02	13.75	3.27	10.6929
1	11	63	08/30/22	13:31	13:51	34.07	29.17	4.90	24.0100
1	12	63.08	08/30/22	13:52	14:12	25.10	26.40	-1.30	1.6900
						n	9		
						t(0.975)	2.306		
						Mean Reference Method Value	21.104	RM avg	
						Mean CEM Value	21.451	CEM avg	
						Sum of Differences	-3.120	di	
						Mean Difference	-0.347	d	
						Sum of Differences Squared	63.191	di²	
						Standard Deviation	2.786	sd	
						Confidence Coefficient 2.5% Error (1-tail)	2.142	cc	
						Relative Accuracy - APS	2.03	RA	

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Test Location: Kiln 22 Baghouse Outlet Test Date: 8/30/2022 Test Method: 2			
Volumetric Flow RATA - Normal Load								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	Reference Method Flow SCFH	CEM Flow SCFH	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/30/22	8:45	9:05	7,127,364	7,237,389	-110,025	12,105,420,452
1	2	08/30/22	9:06	9:26	7,181,652	7,158,305	23,347	545,062,493
1	3	08/30/22	9:27	9:47	7,302,396	7,169,302	133,094	17,714,083,427
1	4	08/30/22	10:10	10:30	7,342,163	7,160,486	181,677	33,006,638,505
1	5	08/30/22	10:31	10:51	7,307,497	7,235,334	72,163	5,207,489,391
1	6	08/30/22	10:52	11:12	7,347,936	7,300,685	47,251	2,232,678,258
1	7	08/30/22	11:35	11:55	7,285,127	7,390,110	-104,983	11,021,408,639
0	8	08/30/22	11:56	12:16	7,250,002	7,320,023	-70,021	4,902,891,443
0	9	08/30/22	12:17	12:37	5,335,542	5,746,791	-411,249	169,125,562,828
0	10	08/30/22	13:10	13:30	7,474,748	6,019,413	1,455,335	2,117,999,199,693
1	11	08/30/22	13:31	13:51	7,099,624	6,161,372	938,252	880,316,064,466
1	12	08/30/22	13:52	14:12	7,127,081	6,652,487	474,594	225,239,861,926
		n	9					
		t(0.025)	2.306					
Mean Reference Method Value			7235648.975				RM avg	
Mean CEM Value			7051718.889				CEM avg	
Sum of Differences			1655370.778				di	
Mean Difference			183930.086				d	
Sum of Differences Squared			1187388707557.520				di²	
Standard Deviation			332211.570				sd	
Confidence Coefficient 2.5% Error (1-tail)			255359.960				cc	
Relative Accuracy			6.07				RA	

3.5 Kiln 23 RATA Tables

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 23 Baghouse Outlet Date: 9/13/22 Test Method: 3A				
O₂ % (dry) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM O₂ % (dry)	CEM O₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)
1	1	09/13/22	08:15	08:35	6.7	6.8	-0.1	0.01
1	2	09/13/22	08:36	08:56	6.6	6.6	0.0	0.00
1	3	09/13/22	08:57	09:17	6.5	6.5	0.0	0.00
1	4	09/13/22	09:45	10:05	6.8	6.8	0.0	0.00
1	5	09/13/22	10:06	10:26	6.9	7.0	-0.1	0.01
0	6	09/13/22	10:27	10:47	6.9	7.1	-0.2	0.04
1	7	09/13/22	11:45	12:05	8.1	8.2	-0.1	0.01
1	8	09/13/22	12:06	12:26	8.0	8.2	-0.2	0.04
1	9	09/13/22	12:27	12:47	8.1	8.3	-0.2	0.04
0	10	09/13/22	13:10	13:30	8.0	8.3	-0.3	0.09
0	11	09/13/22	13:31	13:51	7.6	7.8	-0.2	0.04
1	12	09/13/22	13:52	14:12	7.9	8.1	-0.2	0.04
				n	9			
				t(0.975)	2.306			
				Mean Reference Method Value	7.289	RM avg		
				Mean CEM Value	7.389	CEM avg		
				Sum of Differences	-0.900	di		
				Mean Difference	-0.100	d		
				Sum of Differences Squared	0.150	di²		
				Standard Deviation	0.087	sd		
				Confidence Coefficient 2.5% Error (1-tail)	0.067	cc		
				Relative Accuracy	2.29	RA		



Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 23 Baghouse Outlet Date: 9/13/22 Test Method: 3A			
CO₂ % (dry) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ₂ % (dry)	CEM CO ₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	09/13/22	08:15	08:35	21.0	21.4	-0.4	0.16
1	2	09/13/22	08:36	08:56	21.6	21.9	-0.3	0.09
1	3	09/13/22	08:57	09:17	21.6	21.9	-0.3	0.09
0	4	09/13/22	09:45	10:05	21.0	21.6	-0.6	0.36
1	5	09/13/22	10:06	10:26	20.7	21.1	-0.4	0.16
1	6	09/13/22	10:27	10:47	20.7	21.2	-0.5	0.25
1	7	09/13/22	11:45	12:05	19.5	20.0	-0.5	0.25
1	8	09/13/22	12:06	12:26	19.5	20.0	-0.5	0.25
0	9	09/13/22	12:27	12:47	19.0	19.5	-0.5	0.25
0	10	09/13/22	13:10	13:30	19.2	19.7	-0.5	0.25
1	11	09/13/22	13:31	13:51	20.1	20.6	-0.5	0.25
1	12	09/13/22	13:52	14:12	19.8	20.2	-0.4	0.16
n					9			
t(0.975)					2.306			
Mean Reference Method Value					20.500	RM avg		
Mean CEM Value					20.922	CEM avg		
Sum of Differences					-3.800	di		
Mean Difference					-0.422	d		
Sum of Differences Squared					1.660	di²		
Standard Deviation					0.083	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.064	cc		
Relative Accuracy					2.37	RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 23 Baghouse Outlet Date: 9/13/22 Test Method: 7E				
NO_x ppmvd RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x ppmvd	CEM NO _x ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	09/13/22	08:15	08:35	673.4	687.1	-13.7	187.69
1	2	09/13/22	08:36	08:56	509.6	527.4	-17.8	316.84
1	3	09/13/22	08:57	09:17	521.5	529.1	-7.6	57.76
1	4	09/13/22	09:45	10:05	789.9	817.6	-27.7	767.29
0	5	09/13/22	10:06	10:26	697.0	737.4	-40.4	1632.16
0	6	09/13/22	10:27	10:47	679.6	710.9	-31.3	979.69
1	7	09/13/22	11:45	12:05	307.3	289.8	17.5	306.25
1	8	09/13/22	12:06	12:26	266.8	247.0	19.8	392.04
0	9	09/13/22	12:27	12:47	453.9	427.4	26.5	702.25
1	10	09/13/22	13:10	13:30	263.8	246.0	17.8	316.84
1	11	09/13/22	13:31	13:51	93.0	87.1	5.9	34.81
1	12	09/13/22	13:52	14:12	140.3	127.7	12.6	158.76
				n	9			
				t(0.975)	2.306			
				Mean Reference Method Value	396.178	RM avg		
				Mean CEM Value	395.422	CEM avg		
				Sum of Differences	6.800	di		
				Mean Difference	0.756	d		
				Sum of Differences Squared	2538.280	di²		
				Standard Deviation	17.794	sd		
				Confidence Coefficient 2.5% Error (1-tail)	13.678	cc		
				Relative Accuracy	3.64	RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Kiln 23 Baghouse Outlet Date: 9/13/22 Test Method: 7E, 2					
NO_x lb/hr RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/hr	CEM NO _x lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
0	1	09/13/22	08:15	08:35	520.96	476.74	44.22	1955.4084	
1	2	09/13/22	08:36	08:56	375.14	362.45	12.69	161.0361	
1	3	09/13/22	08:57	09:17	394.56	367.35	27.21	740.3841	
1	4	09/13/22	09:45	10:05	610.76	586.08	24.68	609.1024	
1	5	09/13/22	10:06	10:26	560.12	528.16	31.96	1021.4416	
1	6	09/13/22	10:27	10:47	525.59	499.59	26.00	676.0000	
1	7	09/13/22	11:45	12:05	236.90	224.65	12.25	150.0625	
1	8	09/13/22	12:06	12:26	217.56	187.60	29.96	897.6016	
0	9	09/13/22	12:27	12:47	379.49	327.27	52.22	2726.9284	
0	10	09/13/22	13:10	13:30	216.50	184.73	31.77	1009.3329	
1	11	09/13/22	13:31	13:51	76.40	63.44	12.96	167.9616	
1	12	09/13/22	13:52	14:12	109.19	96.48	12.71	161.5441	
n					9				
t(0.975)					2.306				
Mean Reference Method Value					345.136	RM avg			
Mean CEM Value					323.978	CEM avg			
Sum of Differences					190.420	di			
Mean Difference					21.158	d			
Sum of Differences Squared					4585.134	di²			
Standard Deviation					8.339	sd			
Confidence Coefficient 2.5% Error (1-tail)					6.410	cc			
Relative Accuracy					7.99	RA			

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 23 Baghouse Outlet Date: 9/13/22 Test Method: 7E, 2			
NO_x lb/ton RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM NO _x lb/ton	CEM NO _x lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	09/13/22	08:15	08:35	7.9	7.2	0.7	0.49
1	2	09/13/22	08:36	08:56	5.7	5.5	0.2	0.04
1	3	09/13/22	08:57	09:17	6.0	5.6	0.4	0.16
1	4	09/13/22	09:45	10:05	9.2	8.9	0.3	0.09
1	5	09/13/22	10:06	10:26	7.9	7.4	0.5	0.25
1	6	09/13/22	10:27	10:47	7.9	7.5	0.4	0.16
1	7	09/13/22	11:45	12:05	3.6	3.4	0.2	0.04
1	8	09/13/22	12:06	12:26	3.2	2.8	0.4	0.16
0	9	09/13/22	12:27	12:47	5.7	5.0	0.7	0.49
0	10	09/13/22	13:10	13:30	3.2	2.7	0.5	0.25
1	11	09/13/22	13:31	13:51	1.1	0.9	0.2	0.04
1	12	09/13/22	13:52	14:12	1.6	1.4	0.2	0.04
n					9			
t(0.975)					2.306			
Mean Reference Method Value					5.133	RM avg		
Mean CEM Value					4.822	CEM avg		
Sum of Differences					2.800	di		
Mean Difference					0.311	d		
Sum of Differences Squared					0.980	di²		
Standard Deviation					0.117	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.090	cc		
Relative Accuracy					7.81	RA		


Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Kiln 23 Baghouse Outlet Date: 9/13/22 Test Method: 10			
CO ppmvd RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM CO ppmvd	CEM CO ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	09/13/22	08:15	08:35	86.1	77.3	8.8	77.44
0	2	09/13/22	08:36	08:56	102.2	92.4	9.8	96.04
0	3	09/13/22	08:57	09:17	108.3	99.0	9.3	86.49
1	4	09/13/22	09:45	10:05	65.4	68.3	-2.9	8.41
1	5	09/13/22	10:06	10:26	56.2	58.8	-2.6	6.76
1	6	09/13/22	10:27	10:47	54.6	58.4	-3.8	14.44
1	7	09/13/22	11:45	12:05	49.6	54.8	-5.2	27.04
1	8	09/13/22	12:06	12:26	55.0	59.4	-4.4	19.36
1	9	09/13/22	12:27	12:47	40.6	44.4	-3.8	14.44
1	10	09/13/22	13:10	13:30	50.2	53.0	-2.8	7.84
1	11	09/13/22	13:31	13:51	127.9	128.8	-0.9	0.81
1	12	09/13/22	13:52	14:12	73.3	77.0	-3.7	13.69
n					9			
t(0.975)					2.306			
Mean Reference Method Value					63.644	RM avg		
Mean CEM Value					66.989	CEM avg		
Sum of Differences					-30.100	di		
Mean Difference					-3.344	d		
Sum of Differences Squared					112.790	di²		
Standard Deviation					1.231	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.946	cc		
Relative Accuracy					6.74	RA		

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406							Location: Kiln 23 Baghouse Outlet Date: 9/13/22 Test Method: 10, 2		
CO lb/hr RATA									
1=accept 0=reject	Test Run	Mw	Test Date	Start Time	End Time	RM CO lb/hr	CEM CO lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)
0	1	65.8	09/13/22	08:15	08:35	40.54	32.64	7.90	62.4100
0	2	65.8	09/13/22	08:36	08:56	45.78	38.64	7.14	50.9796
0	3	65.9	09/13/22	08:57	09:17	49.88	41.83	8.05	64.8025
1	4	66.2	09/13/22	09:45	10:05	30.79	29.79	1.00	1.0000
1	5	70.9	09/13/22	10:06	10:26	27.50	25.63	1.87	3.4969
1	6	66.6	09/13/22	10:27	10:47	25.70	24.98	0.72	0.5184
1	7	66.6	09/13/22	11:45	12:05	23.27	25.85	-2.58	6.6564
1	8	67	09/13/22	12:06	12:26	27.29	27.45	-0.16	0.0256
1	9	66	09/13/22	12:27	12:47	20.67	20.69	-0.02	0.0004
1	10	67.8	09/13/22	13:10	13:30	25.06	24.22	0.84	0.7056
1	11	68.6	09/13/22	13:31	13:51	63.94	57.09	6.85	46.9225
1	12	68.1	09/13/22	13:52	14:12	34.73	35.40	-0.67	0.4489
							n	9	
							t(0.975)	2.306	
							Mean Reference Method Value	30.994	RM avg
							Mean CEM Value	30.122	CEM avg
							Sum of Differences	7.850	di
							Mean Difference	0.872	d
							Sum of Differences Squared	59.775	di²
							Standard Deviation	2.572	sd
							Confidence Coefficient 2.5% Error (1-tail)	1.977	cc
							Relative Accuracy	9.19	RA

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Test Location: Kiln 23 Baghouse Outlet Test Date: 9/13/2022 Test Method: 2			
Volumetric Flow RATA - Normal Load								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	Reference Method Flow SCFH	CEM Flow SCFH	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
0	1	09/13/22	8:15	8:35	6,907,716	6,116,883	790,833	625,417,464,450
1	2	09/13/22	8:36	8:56	6,572,934	6,058,669	514,265	264,468,454,229
1	3	09/13/22	8:57	9:17	6,755,111	6,120,895	634,216	402,230,070,616
1	4	09/13/22	9:45	10:05	6,903,825	6,319,542	584,283	341,387,095,730
0	5	09/13/22	10:06	10:26	7,175,496	6,314,381	861,115	741,519,365,815
1	6	09/13/22	10:27	10:57	6,905,207	6,195,538	709,669	503,629,409,034
1	7	09/13/22	11:45	12:05	6,912,887	6,834,217	78,671	6,189,108,958
1	8	09/13/22	12:06	12:26	7,313,334	6,695,962	617,372	381,147,766,521
1	9	09/13/22	12:27	12:47	7,496,831	6,750,617	746,214	556,835,305,932
1	10	09/13/22	13:10	13:30	6,874,696	6,620,161	254,535	64,787,909,949
0	11	09/13/22	13:31	13:51	7,313,712	6,421,510	892,202	796,023,710,554
1	12	09/13/22	13:52	14:12	6,925,475	6,660,988	264,487	69,953,252,541
		n	9					
		t(0.025)	2.306					
Mean Reference Method Value			6962255.684			RM avg		
Mean CEM Value			6472954.463			CEM avg		
Sum of Differences			4403710.993			di		
Mean Difference			489301.221			d		
Sum of Differences Squared			2590628373509.790			di²		
Standard Deviation			233422.151			sd		
Confidence Coefficient 2.5% Error (1-tail)			179423.827			cc		
Relative Accuracy			9.61			RA		

3.6 Wet Gas Scrubber RATA Tables

Client: Holcim (US) Inc. Facility: Alpena Cement Plant Project #: M223406					Location: Wet Gas Scrubber Date: 8/29/22 Test Method: 3A			
O₂ % (dry) RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM O ₂ % (dry)	CEM O ₂ % (dry)	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/29/22	09:04	09:33	11.8	11.7	0.1	0.01
0	2	08/29/22	09:34	10:03	11.7	11.6	0.1	0.01
0	3	08/29/22	10:04	10:33	11.5	11.4	0.1	0.01
1	4	08/29/22	14:40	15:09	11.3	11.3	0.0	0.00
1	5	08/29/22	15:10	15:39	11.5	11.5	0.0	0.00
1	6	08/29/22	15:40	16:09	11.6	11.6	0.0	0.00
1	7	08/29/22	16:43	17:12	11.8	11.8	0.0	0.00
1	8	08/29/22	17:13	17:42	12.0	12.0	0.0	0.00
1	9	08/29/22	17:43	18:12	12.0	12.0	0.0	0.00
1	10	08/29/22	18:50	19:19	12.7	12.6	0.1	0.01
1	11	08/29/22	19:20	19:49	13.0	12.9	0.1	0.01
0	12	08/29/22	19:50	20:19	13.1	12.9	0.2	0.04
n					9			
t(0.975)					2.306			
Mean Reference Method Value					11.967	RM avg		
Mean CEM Value					11.933	CEM avg		
Sum of Differences					0.300	di		
Mean Difference					0.033	d		
Sum of Differences Squared					0.030	di²		
Standard Deviation					0.050	sd		
Confidence Coefficient 2.5% Error (1-tail)					0.038	cc		
Relative Accuracy					0.60	RA		



Client: Holcim (US) Inc. Facility: Alpena Cement Plant Project #: M223406					Location: Wet Gas Scrubber Date: 8/29/22 Test Method: 6C				
SO2 ppmvd RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO2 ppmvd	CEM SO2 ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)	
1	1	08/29/22	09:04	09:33	38.4	37.4	1.0	0.91	
0	2	08/29/22	09:34	10:03	64.0	56.4	7.6	57.67	
1	3	08/29/22	10:04	10:33	50.9	48.6	2.3	5.46	
0	4	08/29/22	14:40	15:09	88.3	81.1	7.2	51.30	
1	5	08/29/22	15:10	15:39	104.3	99.3	5.0	24.97	
1	6	08/29/22	15:40	16:09	73.8	74.0	-0.2	0.04	
1	7	08/29/22	16:43	17:12	35.6	38.4	-2.8	7.66	
1	8	08/29/22	17:13	17:42	37.0	37.2	-0.2	0.02	
1	9	08/29/22	17:43	18:12	55.2	51.0	4.2	17.94	
1	10	08/29/22	18:50	19:19	15.0	18.2	-3.2	10.24	
1	11	08/29/22	19:20	19:49	19.0	21.4	-2.4	5.76	
1	12	08/29/22	19:50	20:19	27.7	29.8	-2.1	4.41	
					n	10			
					t(0.025)	2.262			
					Mean Reference Method Value	45.701	RM avg		
					Mean CEM Value	45.530	CEM avg		
					Sum of Differences	1.707	di		
					Mean Difference	0.171	d		
					Sum of Differences Squared	77.409	di²		
					Standard Deviation	2.927	sd		
					Confidence Coefficient 2.5% Error (1-tail)	2.094	cc		
					Relative Accuracy	4.96	RA		

Client: Holcim (US) Inc. Facility: Alpena Cement Plant Project #: M223406					Location: Wet Gas Scrubber Date: 8/29/22 Test Method: 6C, 2			
SO₂ lb/hr RATA								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO₂ lb/hr	CEM SO₂ lb/hr	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)
1	1	08/29/22	09:04	09:33	146.72	141.00	5.72	32.7184
0	2	08/29/22	09:34	10:03	241.36	212.60	28.76	827.1376
1	3	08/29/22	10:04	10:33	194.52	182.30	12.22	149.3284
0	4	08/29/22	14:40	15:09	336.50	302.20	34.30	1176.4900
0	5	08/29/22	15:10	15:39	395.35	370.20	25.15	632.5225
1	6	08/29/22	15:40	16:09	280.27	274.90	5.37	28.8369
1	7	08/29/22	16:43	17:12	134.61	142.70	-8.09	65.4481
1	8	08/29/22	17:13	17:42	141.21	138.60	2.61	6.8121
1	9	08/29/22	17:43	18:12	210.38	190.10	20.28	411.2784
1	10	08/29/22	18:50	19:19	57.79	67.90	-10.11	102.2121
1	11	08/29/22	19:20	19:49	72.2	80.50	-8.28	68.5584
1	12	08/29/22	19:50	20:19	105.2	111.80	-6.59	43.4281
					n	9		
					t(0.975)	2.306		
					Mean Reference Method Value	149.214	RM avg	
					Mean CEM Value	147.756	CEM avg	
					Sum of Differences	13.130	di	
					Mean Difference	1.459	d	
					Sum of Differences Squared	908.621	di²	
					Standard Deviation	10.544	sd	
					Confidence Coefficient 2.5% Error (1-tail)	8.105	cc	
					Relative Accuracy	6.41	RA	

Client: Holcim (US) Inc. Facility: Alpena Cement Plant Project #: M223406					Location: Wet Gas Scrubber Date: 8/29/22 Test Method: 6C, 2				
SO2 lb/ton RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM SO₂ lb/ton	CEM SO₂ lb/ton	(RM-CEM) Difference (di)	(RM-CEM) Difference² (di²)	
1	1	08/29/22	09:04	09:33	1.2	1.1	0.1	0.01	
0	2	08/29/22	09:34	10:03	1.9	1.7	0.2	0.04	
1	3	08/29/22	10:04	10:33	1.6	1.5	0.1	0.01	
1	4	08/29/22	14:40	15:09	2.6	2.4	0.2	0.04	
1	5	08/29/22	15:10	15:39	3.1	2.9	0.2	0.04	
1	6	08/29/22	15:40	16:09	2.2	2.1	0.1	0.01	
1	7	08/29/22	16:43	17:12	1.1	1.1	0.0	0.00	
1	8	08/29/22	17:13	17:42	1.1	1.5	-0.4	0.16	
0	9	08/29/22	17:43	18:12	1.7	1.1	0.6	0.36	
1	10	08/29/22	18:50	19:19	0.5	0.6	-0.1	0.01	
1	11	08/29/22	19:20	19:49	0.7	0.7	0.0	0.00	
1	12	08/29/22	19:50	20:19	1.0	1.1	-0.1	0.01	
					n	10			
					t(0.975)	2.262			
					Mean Reference Method Value	1.510	RM avg		
					Mean CEM Value	1.500	CEM avg		
					Sum of Differences	0.100	di		
					Mean Difference	0.010	d		
					Sum of Differences Squared	0.290	di²		
					Standard Deviation	0.179	sd		
					Confidence Coefficient 2.5% Error (1-tail)	0.128	cc		
					Relative Accuracy	9.15	RA		

Client: Holcim (US) Inc. Facility: Alpena Cement Plant Project #: M223406					Location: Wet Gas Scrubber Date: 8/29/22 Test Method: 25A, 3A				
THC ppmvd @ 7%O2 RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM THC ppmvd @ 7% O2	CEM THC ppmvd @ 7% O2	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
0	1	08/29/22	9:04	9:33	0.5	1.0	-0.5	0.25	
0	2	08/29/22	9:34	10:03	0.5	1.1	-0.6	0.36	
1	3	08/29/22	10:04	10:33	1.0	1.2	-0.2	0.04	
1	4	08/29/22	14:40	15:09	1.4	1.3	0.1	0.01	
1	5	08/29/22	15:10	15:39	1.7	1.7	0.0	0.00	
1	6	08/29/22	15:40	16:09	1.6	1.4	0.2	0.04	
1	7	08/29/22	16:43	17:12	1.3	1.2	0.1	0.01	
1	8	08/29/22	17:13	17:42	1.8	1.7	0.1	0.01	
0	9	08/29/22	17:43	18:12	2.7	2.2	0.5	0.25	
1	10	08/29/22	18:50	19:19	1.2	1.2	0.0	0.00	
1	11	08/29/22	19:20	19:49	1.4	1.2	0.2	0.04	
1	12	08/29/22	19:50	20:19	1.0	1.2	-0.2	0.04	
n t(0.975) Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					9				
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					2.306				
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					1.378	RM avg			
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					1.344	CEM avg			
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					0.300	di			
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					0.033	d			
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					0.190	di ²			
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					0.150	sd			
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					0.115	cc			
Mean Reference Method Value Mean CEM Value Sum of Differences Mean Difference Sum of Differences Squared Standard Deviation Confidence Coefficient 2.5% Error (1-tail) Relative Accuracy					10.79	RA			

Client: Holcim (US) Inc. Lafarge Alpena			Test Location: Wet Scrubber Stack					
Facility: Alpena Cement Plant			Test Date: 8/29/2022					
Project #: M223406			Test Method: 2F					
Volumetric Flow RATA - Normal Load								
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	Reference Method Flow SCFH	CEM Flow SCFH	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)
1	1	08/29/22	9:04	9:33	26,216,634	26,367,091	-150,457	14,742,743,548
0	2	08/29/22	9:34	10:03	25,877,978	26,374,039	-496,061	85,044,557,376
1	3	08/29/22	10:04	10:33	26,141,972	26,353,486	-211,514	27,441,446,501
1	4	08/29/22	14:40	15:09	26,009,901	26,345,185	-335,284	22,637,429,215
0	5	08/29/22	15:10	15:39	25,860,700	26,330,209	-469,509	246,076,317,297
1	6	08/29/22	15:40	16:09	25,876,650	26,318,047	-441,397	44,737,960,682
0	7	08/29/22	16:43	17:12	25,831,737	26,306,003	-474,266	112,415,494,770
1	8	08/29/22	17:13	17:42	26,066,734	26,308,909	-242,175	220,438,513,277
1	9	08/29/22	17:43	18:12	26,102,718	26,311,195	-208,477	194,831,046,771
1	10	08/29/22	18:50	19:19	26,377,439	26,256,020	121,420	224,927,764,490
1	11	08/29/22	19:20	19:49	25,989,582	26,281,206	-291,624	58,648,633,755
1	12	08/29/22	19:50	20:19	26,041,276	26,206,931	-165,655	43,462,617,834
n		9						
t(0.975)		2.306						
Mean Reference Method Value		26091434.144				RM avg		
Mean CEM Value		26305341.078				CEM avg		
Sum of Differences		-1925162.400				di		
Mean Difference		-213906.933				d		
Sum of Differences Squared		851868156073.489				di²		
Standard Deviation		234537.463				sd		
Confidence Coefficient 2.5% Error (1-tail)		180281.130				cc		
Relative Accuracy		1.51				RA		

Client: Holcim (US) Inc. Lafarge Alpena Plant: Alpena Cement Plant Project #: M223406				Location: Wet Gas Scrubber Stack Date: 8/29/22 Test Method: Sorbent Hg (30B)					
Hg ug/wscm RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM ug/wscm	CMMS ug/wscm	(RM-CMMS) Difference (di)	(RM-CMMS) Difference ² (di ²)	
1	1	08/29/22	08:50	09:20	0.42	0.34	0.08	0.0064	
1	2	08/29/22	09:40	10:10	0.45	0.39	0.06	0.0036	
1	3	08/29/22	10:24	10:54	0.50	0.40	0.10	0.0100	
1	4	08/29/22	13:25	13:55	0.53	0.45	0.08	0.0064	
1	5	08/29/22	14:14	14:44	0.47	0.40	0.07	0.0049	
1	6	08/29/22	15:06	15:36	0.48	0.40	0.08	0.0064	
1	7	08/29/22	15:50	16:20	0.44	0.40	0.04	0.0016	
1	8	08/29/22	16:34	17:04	0.53	0.43	0.10	0.0100	
1	9	08/29/22	17:16	17:46	0.48	0.40	0.08	0.0064	
0	10	08/29/22	17:56	18:26	0.43	0.04	0.39	0.1521	
		n		9					
		t(0.025)		2.306					
		Mean Reference Method Value		0.478		RM avg			
		Mean CMM Value		0.401		CMM avg			
		Sum of Differences		0.690		di			
		Mean Difference		0.077		d			
		Sum of Differences Squared		0.056		di²			
		Standard Deviation		0.019		sd			
		Confidence Coefficient 2.5% Error (1-tail)		0.014		cc			
		Relative Accuracy		19.06		RA			

3.7 Raw Mill RATA Tables

Client: Holcim (US) Inc.Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406				Location: Raw Mill 14 Exhaust Date: 8/24/22 Test Method: 25A, 320					
THC ppmvd RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM THC ppmvd	CEM THC ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	08/24/22	08:10	08:30	6.5	6.7	-0.2	0.04	
1	2	08/24/22	08:31	08:51	6.0	6.0	0.0	0.00	
1	3	08/24/22	08:52	09:12	5.3	5.5	-0.2	0.04	
1	4	08/24/22	09:55	10:15	6.5	6.2	0.3	0.09	
0	5	08/24/22	10:16	10:36	7.8	7.0	0.8	0.64	
0	6	08/24/22	10:37	10:57	7.8	6.8	1.0	1.00	
1	7	08/24/22	13:20	13:40	6.6	6.8	-0.2	0.04	
1	8	08/24/22	13:41	14:01	6.0	6.2	-0.2	0.04	
1	9	08/24/22	14:02	14:22	6.2	6.0	0.2	0.04	
1	10	08/24/22	14:48	15:08	6.0	5.9	0.1	0.01	
1	11	08/24/22	15:09	15:29	8.5	8.3	0.2	0.04	
1	12	08/24/22	15:30	15:50	7.6	7.6	0.0	0.00	
10									
$t(0.975)$									
Mean Reference Method Value									
6.520									
Mean CEM Value									
6.520									
Sum of Differences									
0.000									
Mean Difference									
0.000									
Sum of Differences Squared									
0.340									
Standard Deviation									
0.194									
Confidence Coefficient 2.5% Error (1-tail)									
0.139									
Relative Accuracy									
2.13									
RA									

11

Client: Holcim (US) Inc. Lafarge Alpena Facility: Alpena Cement Plant Project #: M223406					Location: Raw Mill 15 Exhaust Date: 8/23/22 Test Method: 25A, 320				
THC ppmvd RATA									
1=accept 0=reject	Test Run	Test Date	Start Time	End Time	RM THC ppmvd	CEM THC ppmvd	(RM-CEM) Difference (di)	(RM-CEM) Difference ² (di ²)	
1	1	08/23/22	10:25	10:45	6.8	7.1	-0.3	0.09	
1	2	08/23/22	10:46	11:06	7.0	6.7	0.3	0.09	
1	3	08/23/22	11:07	11:27	7.1	6.8	0.3	0.09	
0	4	08/23/22	11:56	12:16	7.0	6.6	0.4	0.16	
1	5	08/23/22	12:17	12:37	6.6	6.7	-0.1	0.01	
1	6	08/23/22	12:38	12:58	6.3	6.7	-0.4	0.16	
1	7	08/23/22	13:34	13:54	6.2	6.4	-0.2	0.04	
1	8	08/23/22	13:55	14:15	6.4	6.4	0.0	0.00	
1	9	08/23/22	14:16	14:36	6.6	6.5	0.1	0.01	
0	10	08/23/22	15:08	15:28	6.6	6.0	0.6	0.36	
1	11	08/23/22	15:29	15:49	7.1	7.0	0.1	0.01	
1	12	08/23/22	15:50	16:10	6.7	6.6	0.1	0.01	
n					10				
t(0.975)					2.262				
Mean Reference Method Value					6.680	RM avg			
Mean CEM Value					6.690	CEM avg			
Sum of Differences					-0.100	di			
Mean Difference					-0.010	d			
Sum of Differences Squared					0.510	di²			
Standard Deviation					0.238	sd			
Confidence Coefficient 2.5% Error (1-tail)					0.170	cc			
Relative Accuracy					2.70	RA			


15

4.0 CERTIFICATION

Mostardi Platt is pleased to have been of service to Holcim (US) Inc. If you have any questions regarding this test report, please do not hesitate to contact us at 630-993-2100.

As the program manager, I hereby certify that this test report represents a true and accurate summary of emissions test results and the methodologies employed to obtain those results. The test program was performed in accordance with the test methods and the Mostardi Platt Quality Manual, as applicable.

MOSTARDI PLATT



Project Manager

Stuart T. Sands



Quality Assurance


Eric Ehlers

APPENDICES

Appendix A - Test Section Diagrams

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(Gaseous)



Job: Holcim (US) Inc.
Alpena Cement Plant
Alpena, Michigan

Test Date: September 15, 2022

Area: 79.33 square feet

Test Location: Kiln 19 Breaching Duct

No. Test Ports: 1

Length: 8.0 Feet

Test Points per Port: 3

Width: 9.917 Feet

Upstream: 0.73 Diameters


Downstream: 0.79 Diameters

Equivalent Diameter: 8.856 Feet

Port Length: 12.0 Inches

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(Volumetric Flow Rate)



Job: Holcim (US) Inc.
Alpena Plant
Alpena, Michigan

Test Dates: September 15, 2022

Area: 79.33 square feet

Test Location: Kiln 19 Breaching Duct

No. Test Ports: 3

Length: 8.0 Feet

Test Points per Port: 14

Width: 9.917 Feet

Upstream: 0.730 Diameters


Downstream: 0.790 Diameters

Equivalent Diameter: 8.856 Feet

Port Length: 3.25 Inches

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(Gaseous)



Job: Holcim (US) Inc.
Alpena Cement Plant
Alpena, Michigan

Test Dates: August 31, 2022

Area: 70.00 square feet

Test Location: Kiln 20 Breaching Duct

No. Test Ports: 1

Length: 8.0 Feet

Test Points per Port: 3

Width: 8.75 Feet

Upstream: 0.47 Diameters


Downstream: 1.11 Diameters

Equivalent Diameter: 8.358 Feet

Port Length: 3.25 Inches

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(Volumetric Flow Rate)



Job: Holcim (US) Inc.
Alpena Plant
Alpena, Michigan

Test Dates: August 31, 2022

Area: 70.00 square feet

Test Location: Kiln 20 Breaching Duct

No. Test Ports: 3

Length: 8.0 Feet

Test Points per Port: 14

Width: 8.75 Feet

Upstream: 0.47 Diameters


Downstream: 1.11 Diameters

Equivalent Diameter: 8.358 Feet

Port Length: 3.25 Inches

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(Gaseous)



Job: Holcim (US) Inc.
Alpena Cement Plant
Alpena, Michigan

Test Dates: September 1, 2022

Area: 69.36 square

Test Location: Kiln 21 Breaching Ducts

feet No. Test Ports: 1

Length: 8.0 Feet

Test Points per Port: 3

Width: 8.67 Feet

Upstream: 0.470 Diameters


Downstream: 1.110 Diameters

Equivalent Diameter: 8.322 Feet

Port Length 9.0 Inches

EQUAL AREA TRAVERSE FOR RECTANGULAR DUCTS

(Volumetric Flow Rate)



Job: Holcim (US) Inc.
Alpena Plant
Alpena, Michigan

Test Dates: September 1, 2022

Area: 69.36 square feet

Test Location: Kiln 21 Breaching Ducts

No. Test Ports: 3

Length: 8 Feet

Test Points per Port: 14

Width: 8.67 Feet


Upstream: 0.470 Diameters

Downstream: 1.110 Diameters

Equivalent Diameter: 8.322 Feet

Port Length: 9.0 Inches

GASEOUS TRAVERSE FOR ROUND DUCTS



Job: Holcim (US) Inc.
Alpena Cement Plant
Alpena, Michigan

Test Dates: August 30 and September 13, 2022

Test Location: Kiln 22 and 23 Baghouse
Outlets

Duct Diameter: 10 Feet

Duct Area: 78.54 Square Feet


Upstream
Disturbance: 0.19 diameters

Downstream
Disturbance: 1.46 diameters

No. Sample Points: 3

Port Length: 8.0 Inches

VOLUMETRIC FLOW RATE TRAVERSE FOR ROUND DUCTS



Job: Holcim (US) Inc.
Alpena Cement Plant
Alpena, Michigan

Test Date: August 30 and September 13, 2022

Test Location: Kiln 22 and 23 Baghouse
Outlets

Duct Diameter: 10 Feet

Duct Area: 78.54 Square Feet


Upstream
Disturbance: 0.19 diameters

Downstream
Disturbance: 1.46 diameters

No. Sample Points: 16

Port Length: 8.0 Inches

GASEOUS TRAVERSE FOR ROUND DUCTS



Job: Holcim (US) Inc.
Alpena Cement Plant
Alpena, Michigan

Test Date: August 23 and 24, 2022

Test Location: Raw Mill 14 and 15 Stacks

Stack Diameter: 5.46 Feet


Stack Area: 23.40 Square Feet

Upstream
Disturbance: >2.0 diameters

Downstream
Disturbance: ~4.0 diameters

No. Sample Points: 3

GASEOUS TRAVERSE FOR ROUND DUCTS



Job: Holcim (US) Inc.
Alpena Plant
Alpena, Michigan

Date: August 29, 2022

Test Location: Wet Gas Scrubber Stack

Stack Diameter: 12 Feet


Stack Area: 113.097 Square Feet

Upstream
Disturbance: 6.0 diameters

Downstream
Disturbance: 4.5 diameters

No. Sample Points: 3

VOLUMETRIC FLOW RATE TRAVERSE FOR ROUND DUCTS



Job: Holcim (US) Inc.
Alpena Cement Plant
Alpena, Michigan

Date: August 29, 2022

Test Location: West Gas Scrubber Stack

Stack Diameter (Feet): 12

Stack Area (Square Feet): 113.097


No. Sample Points Across Diameter: 8

No. of Ports: 2


Port Length (Inches): 5

Appendix B - Sample Train Diagrams


USEPA Method 2 – Type S Pitot Tube Manometer Assembly




USEPA Method 3A Extractive Gaseous Sampling Diagram




USEPA Method 25A – Total Gaseous Organic Compound Sample Train



USEPA Method 320 – Vapor Phase Organic and Inorganic Emissions by Extractive Fourier Transform Infrared (FTIR) Spectroscopy Sample Train Diagram



USEPA Method 30B- Mercury Sorbent Trap Sampling Train



USEPA Method 4- Moisture Content Sample Train Diagram

