

COMPLIANCE TEST REPORT

for

TOTAL PARTICULATE MATTER (PM)

EU-BOILER2-SC, EU-BOILER3-SC

St. Clair Power Plant
St. Clair, Michigan

July 13-14, 2021

July 27, 2021

RECEIVED
SEP 09 2021
AIR QUALITY DIVISION

Prepared By
Environmental Management & Safety
Ecology, Monitoring, and Remediation Group
DTE Corporate Services, LLC
7940 Livernois G4-S
Detroit, MI 48210

DTE

CONTENTS

<u>Section</u>	<u>Page</u>
EXECUTIVE SUMMARY	III
1. 0 INTRODUCTION	1
2.0 SOURCE DESCRIPTION	1
3.0 SAMPLING AND ANALYTICAL PROCEDURES	2
3.1 STACK GAS VELOCITY AND FLOWRATES (USEPA METHODS 1-2)	2
3.1.1 Sampling Method	2
3.1.2 Method 2 Sampling Equipment	3
3.2 OXYGEN AND CARBON DIOXIDE (USEPA METHOD 3A)	3
3.2.1 Sampling Method	3
3.2.2 O ₂ / CO ₂ Sampling Train	3
3.2.3 Sampling Train Calibration	3
3.3 MOISTURE DETERMINATION (USEPA METHOD 4)	3
3.3.1 Sampling Method	3
3.4 PARTICULATE MATTER (USEPA METHOD 5B)	4
3.4.1 Filterable Particulate Sampling Method	4
3.4.2 Quality Control and Assurance	5
3.4.3 Data Reduction	5
4.0 OPERATING PARAMETERS	5
5.0 DISCUSSION OF RESULTS	5
6.0 CERTIFICATION STATEMENT	6

RESULTS TABLES


Table No. 1:	Particulate Emission Testing Summary – EU-BOILER2-SC
Table No. 2:	Particulate Emission Testing Summary – EU-BOILER3-SC

FIGURES

- 1 Sampling Location
- 2 USEPA Method 5B Sampling Train

APPENDICES

- A EPA Test Plan and Approval Letter
- B Field Sampling Data
- C Analytical Data
- D Equipment and Analyzer Calibration Data
- E Example Calculations
- F Process Operational Data and Coal Analysis



EXECUTIVE SUMMARY


DTE Energy's Environmental Management and Safety (EM&S) Ecology, Monitoring, and Remediation Group performed particulate emissions testing on the exhausts of EU-BOILER2-SC and EU-BOILER3-SC at the St. Clair Power Plant, located in St. Clair, Michigan. The testing was required by the Michigan Department of Environment, Great Lakes, and Energy (EGLE) Michigan Renewable Operating Permit MI-ROP-B2796-2015c to document total filterable particulate matter (PM). Testing was conducted on EU-BOILER3-SC on July 13-14, 2021 and EU-BOILER2-SC on July 27, 2021.

A summary of the emission test results are shown below:

Emissions Testing Summary St. Clair Power Plant EU-BOILER2-SC, EU-BOILER3-SC

Source	Date	Load (MW)	Filterable PM (lbs/1000 lbs @ 50% EA) ⁽¹⁾
EU-BOILER2-SC	July 27, 2021	122	0.0097
EU-BOILER3-SC	July 13-14, 2021	121	0.0061

(1) Permit Limit 0.17 lb/1000lbs @ 50% EA



1.0 INTRODUCTION

DTE Energy's Environmental Management and Safety (EM&S) Ecology, Monitoring, and Remediation Group performed particulate emissions testing on the exhausts of EU-BOILER2-SC and EU-BOILER3-SC at the St. Clair Power Plant, located St. Clair, Michigan. Testing was required by the Michigan Department of Environment, Great Lakes, and Energy (EGLE) Michigan Renewable Operating Permit MI-ROP-B2796-2015c to document total filterable particulate matter (PM) on each Unit. Testing was conducted on EU-BOILER3-SC on July 13-14, 2021 and EU-BOILER2-SC on July 27, 2021.

Testing was performed pursuant to Title 40, *Code of Federal Regulations*, Part 60, Appendix A (40 CFR §60 App. A), Methods 1, 3, 4, 5B, 201A and 202.

The fieldwork was performed in accordance with EPA Reference Methods and DTE Energy Intent to Test, which was approved in a letter by Mr. Mark Dziadosz from the Michigan Department of Environment, Great Lakes, and Energy (EGLE), dated February 2, 2021¹. The following DTE Energy personnel participated in the testing program: Mr. Jason Logan, Environmental Specialist, Mr. Mark Westerberg, Senior Environmental Specialist, and Mr. Kenneth St. Amant, Senior Environmental Technician tested Boiler 2; and Mr. Thomas Snyder, Senior Environmental Specialist, Mr. Mark Grigereit, Principal Engineer, and Mr. Fred Meinecke, Senior Environmental Technician tested Boiler 3. Mr. Logan was the project leader. Mr. Dominic Vendittelli, Environmental Specialist, provided process coordination for the testing program.

2.0 SOURCE DESCRIPTION

The St Clair Power Plant (SCPP) located at 4901 Pointe Drive in St. Clair, Michigan, employs the use of four (4) coal-fired boilers (Units 2-3, 6, and 7). Units 2-3 each have Babcock and Wilcox boilers capable of producing 1,070,000 pounds per hour of steam. Units 2 and 3 have Allis Chalmers turbine generators each with a nominally rated capability of 150 MW.

Units 6 and 7 have Combustion Engineering boilers capable of producing 2,100,000 and 3,580,000 pounds of steam per hour respectively. The turbine generators on each unit were manufactured by Westinghouse and have a nominally rated capability of 325 and 500 megawatts respectively. Full load capability for Units 6 and 7 while firing coal only is approximately 315 MW and 470 MW respectively.

The air pollution control equipment on Units 2-3 consists of Wheelabrator Frye electrostatic precipitators on each unit that have design collection efficiencies of 99.6%. Each exhaust stack is 599 feet tall with an internal diameter of 13.3 feet. The air

¹ MDEQ, Approval Letter, dated February 2, 2021. (Attached-Appendix A)

pollution control equipment on Unit 6 consists of Research Corporation electrostatic precipitators that have design collection efficiencies of 99.6%. The exhaust stack is 425 feet tall with an internal diameter of 19.0 feet. The air pollution control equipment on Unit 7 consists of an American Standard electrostatic precipitator that has design collection efficiency of 99.6%. The exhaust stack is 600 feet tall with an internal diameter of 16.0 feet

Testing occurred on EU-BOILER2-SC and EU-BOILER3-SC at greater than 80% of normal full load capability in accordance with the Approval Letter.

3.0 SAMPLING AND ANALYTICAL PROCEDURES

DTE Energy obtained emissions measurements in accordance with procedures specified in the USEPA *Standards of Performance for New Stationary Sources* or listed as an approved "Other Test Method". The sampling and analytical methods used in the testing program are indicated in the table below:

Sampling Method	Parameter	Analysis
USEPA Methods 1-2	Exhaust Gas Flow Rates	Field data analysis and reduction
USEPA Method 3A	Oxygen & CO2	Instrumental Analyzer Method
USEPA Method 4	Moisture Content	Gravimetric Analysis
USEPA Method 5B	Filterable Particulate Matter (Non-Sulfuric Acid)	Gravimetric Analysis

3.1 STACK GAS VELOCITY AND FLOWRATES (USEPA Methods 1-2)

3.1.1 Sampling Method

Stack gas velocity traverses were conducted in accordance with the procedures outlined in USEPA Method 1, "Sample and Velocity Traverses for Stationary Sources," and Method 2, "Determination of Stack Gas Velocity and Volumetric Flowrate." Four (4) sampling ports were utilized, sampling at three (3) points per port for a total of twelve (12) sampling points. See Figure 1 for a diagram of the traverse/sampling points used.

A cyclonic flow check was performed during Unit 2's initial flow monitor certification RATA. Testing at the sampling location demonstrated that no cyclonic flow was present. No changes to the stack have occurred since the cyclonic flow check was performed. Additionally, static pressure checks performed each day confirmed that the null angles were at 0°.

3.1.2 Method 2 Sampling Equipment

The EPA Method 2 sampling equipment consisted of a 0-10" incline manometer, calibrated S-type pitot tubes ($C_p = 0.84$ & 0.798) and a type-K calibrated thermocouple.

3.2 OXYGEN AND CARBON DIOXIDE (USEPA Method 3A)

3.2.1 Sampling Method

Stack gas oxygen (O_2) and carbon dioxide (CO_2) emissions were evaluated using USEPA Method 3A, "Determination of Oxygen and Carbon Dioxide Concentrations in Emissions from Stationary Sources (Instrumental Analyzer Procedure)". Upon field setup for Unit 2, it was discovered the CO_2 portion of the Servomex 1400 instrument was not working correctly. CO_2 data was collected from the facility CEMS and corrected to dry conditions to calculate exhaust molecular weight for Unit 2 only.

3.2.2 O_2 / CO_2 Sampling Train

The Method 3A sampling system consisted of continuously collecting a gas sample from the exhaust of the dry gas meter during each test. The sample was drawn through a Teflon® line into a Universal™ gas conditioner and into a Servomex™ 1400 gas analyzer.

3.2.3 Sampling Train Calibration

The analyzer was calibrated according to procedures outlined in USEPA Method 7E. Zero, span, and mid-range calibration gases were introduced directly into the analyzer to verify the instruments linearity. Upscale and downscale gases were introduced after every test period to determine instrument drift. CO_2 and O_2 concentrations are recorded on the field data sheets.

3.3 MOISTURE DETERMINATION (USEPA Method 4)

3.3.1 Sampling Method

Determination of the moisture content of the exhaust gas was performed using the method described in USEPA Method 4, "Determination of Moisture Content in Stack Gases". The moisture was collected in glass impingers as a component of the PM sampling train, and the percentage of moisture was then derived from calculations outlined in USEPA Method 4.

3.4 PARTICULATE MATTER (USEPA Method 5B)

3.4.1 Filterable Particulate Sampling Method

USEPA Method 5B, "Determination of Non-Sulfuric Acid Particulate Emissions from Stationary Sources" was used to measure the filterable (front-half) particulate emissions (see Figure 3 for a schematic of the sampling train). Triplicate, 60-minute test runs were conducted.

The Method 5B modular isokinetic stack sampling system consisted of the following:

- (1) PTFE coated stainless-steel button-hook nozzle
- (2) Heated glass-lined probe
- (3) Heated 3" glass filter holder with a quartz filter (maintained at a temperature of 320 ± 25 °F)
- (4) Set of impingers for the collection of condensate for moisture determination
- (5) Length of sample line
- (6) Environmental Supply[®] control case equipped with a pump, dry gas meter, and calibrated orifice.

The quartz filters used in the sampling were initially baked for 3 hours at 320 °F, desiccated for 24 hours and weighed to a constant weight as described in Method 5B to obtain the initial tare weight.

After completion of the final leak test for each test run, the filter was recovered, and the probe, nozzle and the front half of the filter holder assembly were brushed and rinsed with acetone. The acetone rinses were collected in a pre-cleaned sample container. The container was labeled with the test number, test location, test date, and the level of liquid marked on the outside of the container. Immediately after recovery, the sample containers were placed in a cooler for storage.

At the laboratory the acetone rinses were transferred to clean pre-weighed beakers, and evaporated to dryness at ambient temperature and pressure. The beakers and filters were baked for 6 hours at 320 °F, desiccated for 24 hours and weighed to a constant weight (within 0.5 mg). The data sheets containing the initial and final weights on the filters and beakers can be found in Appendix C.

Collected field blanks consisted of a blank filter and acetone solution blank. The acetone blank was collected from the rinse bottle used in sample recovery. The blank filter and acetone were collected and analyzed following the same procedures



used to recover and analyze the field samples. Field data sheets for the Method 5B sampling can be found in Appendix B.

3.4.2 Quality Control and Assurance

All sampling and analytical equipment was calibrated according to the guidelines referenced in EPA Method 5B. All Method 1-4, and 5B calibration data is located in Appendix D.

Test 2 on Unit 3 was discarded due to a leak in the sample train. A fourth test was performed on July 14, 2021.

3.4.3 Data Reduction

The filterable PM emissions data collected during the testing was calculated and reported as lb/1000lbs @ 50% excess air for comparison to the permitted emission limits.

4.0 OPERATING PARAMETERS

The test program included the collection of boiler load and stack CEMs monitoring during each test run. Parameters recorded included gross Megawatts (MW), CO₂, and opacity.

Electrostatic Precipitator data was also collected including total power, sparks per minute, primary amps, primary voltage, secondary amps, secondary voltage, spark rate, and firing angle.


Operational data and results of the fuel analysis can be referred to in Appendix F.

5.0 DISCUSSION OF RESULTS


Tables 1 and 2 present the Particulate Emission testing results from EU-BOILER2-SC and EU-BOILER3-SC, respectively. Total Filterable PM emissions are presented in pounds per 1000 pounds @ 50% excess air for comparison to the permitted emission limit. Additional test data presented for each test includes the Unit load in gross megawatts (GMW), stack temperature in degrees Fahrenheit (°F), stack gas velocity in feet per minute (ft/min), and stack gas flow rate in actual cubic feet per minute (ACFM), standard cubic feet per minute (SCFM) and dry standard cubic feet per minute (DSCFM). The average filterable PM emissions from Unit 2 and Unit 3 were 0.0096 and 0.0061 lbs/1000lbs @ 50% excess air, respectively, which is less than the permit limit of 0.17 lbs/1000lbs excess air.

6.0 CERTIFICATION STATEMENT

"I certify that I believe the information provided in this document is true, accurate, and complete. Results of testing are based on the good faith application of sound professional judgment, using techniques, factors, or standards approved by the Local, State, or Federal Governing body, or generally accepted in the trade."



Mr. Jason Logan, QSTI

This report prepared by: 

Mr. Jason Logan, QSTI
Environmental Specialist, Ecology, Monitoring, and Remediation
Environmental Management and Safety
DTE Energy Corporate Services, LLC

This report reviewed by: 

Mr. Mark Grigereit, QSTI
Principal Engineer, Ecology, Monitoring, & Remediation
Environmental Management & Safety
DTE Energy Corporate Services, LLC

DTE

RESULTS TABLE



Table No. 1
PARTICULATE EMISSION TESTING SUMMARY
St. Clair Power Plant - EU-BOILER2-SC
July 27, 2021

Unit 2 - Total Filterable PM

Test	Test Date	Test Time (EST)	Unit Load (GMW)	Stack Temperature (°F)	Stack Velocity (ft/min)	Exhaust Gas Flowrates			PM Emissions		
						(ACFM)	(SCFM)	(DSCFM)	(grains/dscf)	(lbs/hr)	(lbs/1000lbs @ 50% EA) ⁽¹⁾
PM-1	27-Jul-21	7:50-8:54	122	288	5,437	759,143	522,893	484,495	0.0026	10.8	0.0071
PM-2	27-Jul-21	9:23-10:28	122	292	5,339	745,525	511,008	472,663	0.0037	14.8	0.0098
PM-3	27-Jul-21	11:18-12:22	<u>122</u>	<u>294</u>	<u>4,911</u>	<u>685,692</u>	<u>468,802</u>	<u>434,008</u>	<u>0.0046</u>	<u>17.0</u>	<u>0.0121</u>
<i>Average:</i>			<i>122</i>	<i>291</i>	<i>5,229</i>	<i>730,120</i>	<i>500,901</i>	<i>463,722</i>	<i>0.0036</i>	<i>14.2</i>	<i>0.0097</i>

(1) Permit Limit = 0.17 lbs/1000 lbs @ 50% excess air



Table No. 2
PARTICULATE EMISSION TESTING SUMMARY
St. Clair Power Plant - EU-BOILER3-SC
July 13-14, 2021

Unit 3 - Total Filterable PM

Test	Test Date	Test Time (EST)	Unit Load (GMW)	Stack Temperature (°F)	Stack Velocity (ft/min)	Exhaust Gas Flowrates			PM Emissions		
						(ACFM)	(SCFM)	(DSCFM)	(grains/dscf)	(lbs/hr)	(lbs/1000lbs @ 50% EA) ⁽¹⁾
PM-1	13-Jul-21	6:50-7:56	121	294	4,414	616,340	428,706	394,415	0.0037	12.6	0.0080
PM-3 ⁽²⁾	13-Jul-21	11:04-12:10	122	302	4,640	647,869	445,808	402,969	0.0021	7.1	0.0044
PM-4	14-Jul-21	8:47-9:50	<u>122</u>	<u>281</u>	<u>4,552</u>	<u>635,633</u>	<u>451,793</u>	<u>409,795</u>	<u>0.0026</u>	<u>9.3</u>	<u>0.0058</u>
<i>Average:</i>			<i>121</i>	<i>292</i>	<i>4,535</i>	<i>633,281</i>	<i>442,102</i>	<i>402,393</i>	<i>0.0028</i>	<i>9.7</i>	<i>0.0061</i>

(1) Permit Limit = 0.17 lbs/1000 lbs @ 50% excess air

(2) PM-2 was discarded due to sample train leak

DTE

FIGURES

RECEIVED

SEP 09 2021

AIR QUALITY DIVISION




Figure 1 – Sampling Location & Traverse Points
St Clair Power Plant – Units 2-3




Figure 2 – Sampling Location & Traverse Points
St Clair Power Plant – Unit 6




Figure 3 – Sampling Location & Traverse Points
St Clair Power Plant – Unit 7





Figure 4 – EPA Method 5B
Calendar Year 2021



DTE

APPENDIX A

TEST PLAN APPROVAL LETTER