

---

**COMPLIANCE TEST REPORT  
ANR PIPELINE-GOODWELL COMPRESSOR STATION  
COMBUSTION EUGDS TURBINE NO.6  
COMBUSTION EUGDS TURBINE NO.7**

---

Prepared for:



TC Energy's ANR Pipeline Company  
White Cloud, MI

March 22, 2022

Prepared by:



Environmental Quality Management, Inc.  
1280 Arrowhead Court  
Suite 2  
Crown Point, IN 46307  
(219) 661-9900  
[www.eqm.com](http://www.eqm.com)

PN: 050812.0007

April 2022

---



**PREFACE**

I, Karl Mast, do hereby certify that the source emissions testing conducted at TC Energy in White Cloud, MI was performed in accordance with the procedures set forth by the United States Environmental Protection Agency, and that the data and results submitted within this report are an exact representation of the testing.



Karl Mast  
Test Supervisor

I, Karl Mast, do hereby attest that all work on this project was performed under my direct supervision, and that this report accurately and authentically presents the source emissions testing conducted at ANR Pipeline's Goodwell Compressor Station in White Cloud, MI.



Karl Mast  
Test Supervisor



**SUMMARY**

The compliance testing was performed on the Combustion Turbine No. 6 and Combustion Turbine No. 7 systems in accordance with the requirements of the Title 40, Code of Federal Regulations, Part 60 (40 CFR 60.4320(a)). The results of the testing are detailed in the following tables.

| <b>NO<sub>x</sub> Emission Test Results</b>   |             |              |              |              |                |              |
|---|-------------|--------------|--------------|--------------|----------------|--------------|
| <b>Parameter</b>                              | <b>Unit</b> | <b>Run 1</b> | <b>Run 2</b> | <b>Run 3</b> | <b>Average</b> | <b>Limit</b> |
| NO <sub>x</sub> ppmvd @<br>15% O <sub>2</sub> | No. 6       | 4.9269       | 4.4276       | 3.9095       | 4.4213         | 25           |
| NO <sub>x</sub> ppmvd @<br>15% O <sub>2</sub> | No. 7       | 2.3930       | 2.1640       | 1.8851       | 2.1474         | 25           |

**CONTENTS**

Preface..... ii

Summary ..... iii

1 Introduction.....1

2 Test Results Summary .....3

3 Facility and Process Conditions.....8

4 Test Procedures .....12

5 Quality Assurance Procedures .....15

6 Conclusions .....16

**TABLES**

1 NOx Test Results Summary.....3

2 Turbine 6-Operating Parameters/Ambient Conditions .....4

3 Turbine 6- Emissions Concentrations, Calculated Mass Emissions, & Calculated Flows ..5

4 Turbine 7-Operating Parameters/Ambient Conditions .....6

5 Turbine 7- Emissions Concentrations, Calculated Mass Emissions, & Calculated Flows ..7

6 Horsepower Recorded Data .....8

7 CT Rotations Per Minute Recorded Data .....8

8 Unit 6 General Information.....9

9 Unit 7 General Information.....10

**FIGURES**

1 Turbine 6 & 7 Flow Schematic.....11

**APPENDICES**

- A – Field Test Data
- B – Process Operating Data
- C – Gas Certifications
- D – Correspondence
- E – Sample Calculations

## 1. INTRODUCTION

This report presents the results of the source emissions testing conducted by Environmental Quality Management, Inc. (EQM) for TC Energy's ANR Pipeline (ANR) at Goodwell compressor station, near White Cloud, MI, which is located in Newaygo County.

The primary purpose of this testing program was to conduct emissions testing to determine compliance with operating permit No. MI-ROP-N5576-2021 for Combustion EUGDS Turbine No. 6 and Combustion EUGDS Turbine No. 7 at ANR Pipeline's gas compressor facility.

EQM's responsibility was to conduct the compliance testing for the O<sub>2</sub> and NO<sub>x</sub> emissions rates and perform data reduction for conformance evaluation. ANR Pipeline's responsibility was to maintain process operating parameters and to assist in providing process operating data per compliance test requirements.

The following report provides information pertaining to TC Energy's process operations, and Compliance testing. The Compliance testing conducted on the Combustion Turbine No. 6 was performed on March 22, 2022, from 8:50 A.M. to 9:52 A.M. The Compliance testing conducted on the Combustion Turbine No. 7 was performed on March 22, 2022, from 10:47 A.M. to 11:49 A.M.

The following requirements were specific for the testing program:

1. Equipment calibrations performed and calibration data provided.
2. Three (3) twenty-one (21) -minute, minimum, O<sub>2</sub> and NO<sub>x</sub> test runs performed at the Combustion Turbine No. 6 and Combustion Turbine No. 7 at maximum achievable load and speed according to pipeline conditions pursuant to EPA, Title 40, Code of Federal Regulations, Part 60, Appendix A.
3. Process manufacturing operations maintained at 100% of capacities and production and fuel consumption rates recorded during the emissions testing periods.
4. All testing and analyses performed in accordance with current EPA test methodologies and analytical procedures for O<sub>2</sub> and NO<sub>x</sub> emissions determinations.
5. Stratification was found to be less than 0.77% in both turbine exhausts.
6. Diluent corrected stratification test was performed in accordance with Subpart KKKK.

The testing program was approved by and/or coordinated with Tyrah Lydia, TC Energy's ANR Pipeline Company. The emission testing was managed by Karl Mast, Manager, Emission Measurement and Project Manager, EQM. The testing was completed by Zach Hill, Field Activities Lead, EQM. The emission testing was observed Chris Robinson, MEGLE.

---

April 2022

2

RECEIVED

MAY 23 2022

AIR QUALITY DIVISION

## 2. TEST RESULTS SUMMARY

The compliance testing was performed on the Combustion Turbine No. 6 and Combustion Turbine No. 7 systems in accordance with the requirements of the Title 40, Code of Federal Regulations, Part 60 (40 CFR 60, Appendix A) A summary of the test results is given below:

| Table 1. NO <sub>x</sub> Emission Test Results |       |        |        |        |         |       |
|--|-------|--------|--------|--------|---------|-------|
| Parameter                                      | Unit  | Run 1  | Run 2  | Run 3  | Average | Limit |
| NO <sub>x</sub> ppmvd @<br>15% O <sub>2</sub>  | No. 6 | 4.9269 | 4.4276 | 3.9095 | 4.4213  | 25    |
| NO <sub>x</sub> ppmvd @<br>15% O <sub>2</sub>  | No. 7 | 2.3930 | 2.1640 | 1.8851 | 2.1474  | 25    |

Based on the information provided above, the Combustion Turbine No. 6 and Combustion Turbine No. 7 met the acceptance criteria during the course of the testing. A complete list of performance parameters for each test run that was performed at the stack sampling locations can be found in Table 2-9.

Additional testing information may be found in Appendix A.



**Table 2. Operating Parameters and Ambient Conditions-Turbine No. 6**

| Run                                   | 1           | 2           | 3           |             |
|---------------------------------------|-------------|-------------|-------------|-------------|
| Date                                  | 03/22/22    | 03/22/22    | 03/22/22    |             |
| Time                                  | 8:50        | 9:11        | 9:32        |             |
| <b>Engine Operating Conditions</b>    | High        | High        | High        | Averages    |
| Unit Horsepower from Control Panel    | 3,599.0     | 4,621.0     | 5,239.0     | 4,486.3     |
| % Load                                | 45.8        | 58.8        | 66.6        | 57.0        |
| Unit Speed (rpm) CT/GG/GP/Jet         | 14,830.0    | 14,810.0    | 14,796.0    | 14,812.0    |
| % CT Speed                            | 98.9        | 98.7        | 98.6        | 98.7        |
| Gas Compressor Speed (rpm) PT/Booster | 12,386.0    | 12,296.0    | 12,276.0    | 12,319.3    |
| % PT Speed                            | 86.6        | 86.0        | 85.8        | 86.1        |
| Turbine Exhaust Temp T5               | 1,402.0     | 1,400.0     | 1,399.0     | 1,400.3     |
| Compressor Suction Pressure (PSIG)    | 275.0       | 276.0       | 276.0       | 275.7       |
| Compressor Suction Temperature (°F)   | 36.0        | 36.0        | 36.0        | 36.0        |
| Compressor Discharge Pressure (PSIG)  | 593.0       | 624.0       | 627.0       | 614.7       |
| Compressor Discharge Temperature (°F) | 106.0       | 128.0       | 140.0       | 124.7       |
| Compressor Flow (MMSCFD)              | 145.0       | 141.0       | 140.0       | 142.0       |
| Heat Rate (BTU(LHV)/HP-hr)            | 17,236.7155 | 13,424.5702 | 11,840.9885 | 14,167.4247 |
| <b>Ambient Conditions</b>             |             |             |             |             |
| Ambient Temperature (°F)              | 36.00       | 36.00       | 37.00       | 36.33       |
| Barometric Pressure (psi)             | 14.17       | 14.18       | 14.18       | 14.18       |
| Ambient Relative Humidity (%)         | 61.00       | 61.00       | 59.00       | 60.33       |
| Absolute Humidity (grains/LB)         | 19.64       | 19.64       | 19.75       | 19.68       |



**Table 3. Emissions Concentrations, Calculated Mass Emissions, & Calculated Flows- Turbine No. 6**

| Run   | 1           | 2           | 3           |             |
|---|-------------|-------------|-------------|-------------|
| Date  | 03/22/22    | 03/22/22    | 03/22/22    |             |
| Time  | 8:50        | 9:11        | 9:32        |             |
| <b>Emissions Concentrations &amp; Calculated Mass Emissions</b> |             |             |             |             |
| NO <sub>x</sub> ppm (BIAS Corrected)                            | 4.810       | 4.330       | 3.830       | 4.3233      |
| NO <sub>x</sub> LB/HR   | 1.2455      | 1.1193      | 0.9883      | 1.1177      |
| NO <sub>x</sub> (ppm @ 15% O <sub>2</sub> )                     | 4.9269      | 4.4276      | 3.9095      | 4.4213      |
| NO <sub>x</sub> (ppm @ 15% O <sub>2</sub> , ISO)                | 5.0247      | 4.5152      | 3.9746      | 4.5048      |
| NO <sub>x</sub> LB/MMBTU  | 0.0182      | 0.0163      | 0.0144      | 0.0163      |
| NO <sub>x</sub> Tons/Year                                       | 5.4553      | 4.9024      | 4.3288      | 4.8955      |
| NO <sub>x</sub> LB/SCF Fuel                                     | 1.92E-05    | 1.73E-05    | 1.52E-05    | 1.72E-05    |
| NO <sub>x</sub> LB/MMSCF Fuel                                   | 19.2004     | 17.2544     | 15.2355     | 17.2301     |
| % O <sub>2</sub> (BIAS Corrected)                               | 15.140      | 15.130      | 15.120      | 15.1300     |
| <b>Calculated Flows</b>   |             |             |             |             |
| Fuel Flow - (SCFM)  | 1083.3333   | 1083.3333   | 1083.3333   | 1083.3333   |
| Fuel Flow - (SCFH)  | 65000.00    | 65000.00    | 65000.00    | 65000.00    |
| Exhaust Flow (LB/HR)  | 142502.2533 | 142271.6066 | 141905.7377 | 142226.5325 |
| Exhaust Flow (SCFM)   | 37084.7524  | 37032.5088  | 36980.4443  | 37032.5685  |
| Air Flow (SCFM)   | 34718.0865  | 34658.4880  | 34599.0939  | 34658.5561  |
| Exhaust Flow Method 19 (scfm)                                   | 36071.6844  | 36009.1685  | 35946.8689  | 36009.2406  |
| Exhaust Flow Method 19 (lbm/min)                                | 1660.0385   | 1657.1613   | 1654.3077   | 1657.1692   |
| Exhaust Flow Carbon Balance (lbm/min)                           | 2771.8685   | 2767.2532   | 2762.6536   | 2767.2584   |
| Air flow Beshouri (scfm)  | 36062.4696  | 36002.4230  | 35942.5823  | 36002.4916  |
| BSAC, #/BHP-hr  | 43.9643     | 34.1822     | 30.0984     | 36.0816     |
| <b>Fuel Flow Measurements</b>                                   |             |             |             |             |
| Fuel Flow From Screen(MSCFH)                                    | 65.00       | 65.00       | 65.00       | 65.00       |
| <b>** BASED ON FUEL SPECIFIC DRY F-FACTOR CALCULATION</b>       | Run 1       | Run 2       | Run 3       |             |
| <b>* BASED ON CARBON BALANCE (STOICH. + O2)</b>                 |             |             |             |             |
| <b>- A/F IS TOTAL MASS RATIO</b>                                |             |             |             |             |



**Table 4. Operating Parameters and Ambient Conditions-Turbine No. 7**

| Run                                   | 1           | 2           | 3           |                 |
|---------------------------------------|-------------|-------------|-------------|-----------------|
| Date                                  | 03/22/22    | 03/22/22    | 03/22/22    |                 |
| Time                                  | 10:47       | 11:08       | 11:29       |                 |
| <b>Engine Operating Conditions</b>    | <b>High</b> | <b>High</b> | <b>High</b> | <b>Averages</b> |
| Unit Horsepower from Control Panel    | 6,922.0     | 6,960.0     | 6,945.0     | 6,942.3         |
| % Load                                | 88.0        | 88.5        | 88.3        | 88.3            |
| Unit Speed (rpm) CT/GG/GP/Jet         | 14,945.0    | 14,945.0    | 14,945.0    | 14,945.0        |
| % CT Speed                            | 99.6        | 99.6        | 99.6        | 99.6            |
| Gas Compressor Speed (rpm) PT/Booster | 12,236.0    | 12,235.0    | 12,221.0    | 12,230.7        |
| % PT Speed                            | 85.6        | 85.6        | 85.5        | 85.5            |
| Turbine Exhaust Temp T5               | 1,384.0     | 1,385.0     | 1,388.0     | 1,385.7         |
| Compressor Suction Pressure (PSIG)    | 275.0       | 275.0       | 276.0       | 275.3           |
| Compressor Suction Temperature (°F)   | 37.0        | 37.0        | 38.0        | 37.3            |
| Compressor Discharge Pressure (PSIG)  | 630.0       | 638.0       | 641.0       | 636.3           |
| Compressor Discharge Temperature (°F) | 174.0       | 176.0       | 177.0       | 175.7           |
| Compressor Flow (MMSCFD)              | 138.0       | 137.0       | 136.0       | 137.0           |
| Heat Rate (BTU(LHV)/HP-hr)            | 8,686.2426  | 8,501.6937  | 8,520.0559  | 8,569.3307      |
| <b>Ambient Conditions</b>             |             |             |             |                 |
| Ambient Temperature (°F)              | 37.00       | 38.00       | 39.00       | 38.00           |
| Barometric Pressure (psi)             | 14.20       | 14.19       | 14.20       | 14.20           |
| Ambient Relative Humidity (%)         | 58.00       | 62.00       | 54.00       | 58.00           |
| Absolute Humidity (grains/LB)         | 19.39       | 21.58       | 19.53       | 20.17           |



**Table 5. Emissions Concentrations, Calculated Mass Emissions, & Calculated Flows-  
Turbine No. 7**

| Run   | 1            | 2            | 3            |              |
|---|--------------|--------------|--------------|--------------|
| Date  | 03/22/22     | 03/22/22     | 03/22/22     |              |
| Time  | 10:47        | 11:08        | 11:29        |              |
| <b>Emissions Concentrations &amp; Calculated Mass Emissions</b> |              |              |              |              |
| NO <sub>x</sub> ppm (BIAS Corrected)                            | 2.320        | 2.120        | 1.850        | 2.0967       |
| NO <sub>x</sub> LB/HR   | 0.5863       | 0.5218       | 0.4546       | 0.5209       |
| NO <sub>x</sub> (ppm @ 15% O <sub>2</sub> )                     | 2.3930       | 2.1640       | 1.8851       | 2.1474       |
| NO <sub>x</sub> (ppm @ 15% O <sub>2</sub> , ISO)                | 2.4294       | 2.2035       | 1.9028       | 2.1786       |
| NO <sub>x</sub> LB/MMBTU  | 0.0088       | 0.0080       | 0.0069       | 0.0079       |
| NO <sub>x</sub> Tons/Year                                       | 2.5681       | 2.2855       | 1.9910       | 2.2815       |
| NO <sub>x</sub> LB/SCF Fuel                                     | 9.33E-06     | 8.43E-06     | 7.35E-06     | 8.37E-06     |
| NO <sub>x</sub> LB/MMSCF Fuel                                   | 9.3256       | 8.4332       | 7.3465       | 8.3685       |
| % O <sub>2</sub> (BIAS Corrected)                               | 15.180       | 15.120       | 15.110       | 15.137       |
| <b>Calculated Flows</b>   |              |              |              |              |
| Fuel Flow - (SCFM)  | 1050.00      | 1033.33      | 1033.33      | 1038.8889    |
| Fuel Flow - (SCFH)  | 63,000       | 62,000       | 62,000       | 62,333.3333  |
| Exhaust Flow (LB/HR)  | 138,855.8377 | 135,466.2200 | 134,856.0183 | 136,392.6920 |
| Exhaust Flow (SCFM)   | 36,177.9189  | 35,303.1159  | 35,253.6245  | 35,578.2198  |
| Air Flow (SCFM)   | 33,882.8984  | 33,002.2126  | 32,945.7538  | 33,276.9549  |
| Exhaust Flow Method 19 (scfm)                                   | 35,206.2745  | 34,287.7827  | 34,228.5637  | 34,574.2069  |
| Exhaust Flow Method 19 (lbm/min)                                | 1,620.1774   | 1,578.1675   | 1,575.1996   | 1,591.1815   |
| Exhaust Flow Carbon Balance (lbm/min)                           | 2,704.6287   | 2,635.1465   | 2,630.7743   | 2,656.8498   |
| Air flow Beshouri (scfm)  | 35,187.6681  | 34,283.6939  | 34,226.8106  | 34,566.0575  |
| BSAC, #/BHP-hr  | 22.3088      | 21.6103      | 21.6199      | 21.8463      |
| <b>Fuel Flow Measurements</b>                                   |              |              |              |              |
| Fuel Flow From Screen(MSCFH)                                    | 63.00        | 62.00        | 62.00        | 62.33        |
| ** BASED ON FUEL SPECIFIC DRY F-FACTOR CALCULATION              | Run 1        | Run 2        | Run 3        |              |
| * BASED ON CARBON BALANCE (STOICH. + O <sub>2</sub> )           |              |              |              |              |
| - A/F IS TOTAL MASS RATIO                                       |              |              |              |              |

### 3. PROCESS DESCRIPTION

TC Energy's ANR Goodwell Compressor Station is located in White Cloud, Michigan and operates two Solar Centaur 60, 7,865 hp and 15,000 rpm, natural gas fired turbines with low NO<sub>x</sub> burner for NO<sub>x</sub> control labeled EUGDS Turbine 6 (aka 6.1) and EUGDS Turbine 7 (aka 7.2). The plant is located at 6759 East Five Mile Road, White Cloud, MI

The Solar Centaur 60 gas turbine is a simple cycle, natural gas fired, split-shaft turbine. In a simple cycle turbine, filtered atmosphere air is first compressed by the axial flow compressor. The hot compressed air is then fired with natural gas in the combustor. The hot exhaust gases expand through two turbine stages. The gas producer (G.P.) turbine drives the axial flow air while the power turbine (P.T.) drives the centrifugal pipeline compressor. The pipeline gas compressor moves natural gas through the pipeline by compressing it from an initial "suction" state to a more compressed "discharge" state.

The following tables provide a summary of the production rates for the Turbines No. 6 and No. 7 during the test:

| <b>Table 6. Turbine No. 6 and No. 7 Brake Horsepower (BHP)</b> |                      |                      |
|--|----------------------|----------------------|
| <b>Run No.</b>   | <b>Turbine No. 6</b> | <b>Turbine No. 7</b> |
| 1  | 3,599.0              | 6,922.0              |
| 2  | 4,621.0              | 6,960.0              |
| 3  | 5,239.0              | 6,945.0              |
| Average  | 4,486.3              | 6,942.3              |
| Rated BHP  | 7,865                | 7,865                |

| <b>Table 7. Turbine No. 6 and No. 7 CT RPM</b> |                      |                      |
|--|----------------------|----------------------|
| <b>Run No.</b>                                 | <b>Turbine No. 6</b> | <b>Turbine No. 7</b> |
| 1  | 14,830.0             | 14,945.0             |
| 2  | 14,810.0             | 14,945.0             |
| 3  | 14,796.0             | 14,945.0             |
| Average  | 14,812.0             | 14,945.0             |
| Rated CT RPM                                   | 15,000               | 15,000               |

**Table 8. Unit 6 General Information**

| General Information |                  |
|---------------------|------------------|
| Date:               | 22-Mar-22        |
| Company:            | TC Energy        |
| Station:            | Goodwell MI      |
| Unit:               | 6.1              |
| Engine Type:        | Solar Centaur 60 |
| CT Rated RPM:       | 15000 RPM        |
| PT Rated RPM:       | 14300 RPM        |
| Rated BHP:          | 7865 BHP         |

| Permit Limits |         |          |       |     |
|---------------|---------|----------|-------|-----|
|               | ppm@15% | g/Bhp-Hr | lb/hr | TPY |
| NOx:          | 25      |          |       |     |
| CO:           |         |          |       |     |
| VOC:          |         |          |       |     |
| H2CO:         |         |          |       |     |

*Limits are actually listed as average values*

| Fuel Gas Analysis |               |
|-------------------|---------------|
| Constituent       | Mole Percent  |
| Nitrogen          | 1.123         |
| Carbon Dioxide    | 0.457         |
| Methane           | 91.112        |
| Ethane            | 6.905         |
| Propane           | 0.363         |
| I-Butane          | 0.015         |
| N-Butane          | 0.020         |
| I-Pentane         | 0.000         |
| N-Pentane         | 0.000         |
| Hexane +          | 0.004         |
| <b>Total</b>      | <b>100.00</b> |


  

| Fuel Meter Type                          |       |
|--|-------|
| Enter Type from List Below               |       |
| Orifice Meter (upstream pressure tap):   | 1     |
| Orifice Meter (downstream pressure tap): | 2     |
| Electronic Flow Meter (EFM):             | 3     |
| Venturi (Nozzle) Meter:                  | 4     |
| Roots Meter w/ Accumulator:              | 5     |
| Pipe ID.:                                | 3.068 |
| Orifice ID.:                             | 1.5   |

**Table 9. Unit 7 General Information**

| General Information                                 |                  | Permit Limits                            |          |       |     |
|---|------------------|--|----------|-------|-----|
| Date:   | 22-Mar-22        | ppm @15%                                 | g/Bhp-Hr | lb/yr | TPY |
| Company:  | TC Energy        | NOx:                                     | 25       |       |     |
| Station:  | Goodwell MI      | CO:                                      |          |       |     |
| Unit:   | 7.2              | VOC:                                     |          |       |     |
| Engine Type:  | Solar Centaur 60 | H2CO:                                    |          |       |     |
| <i>Limits are actually listed as average values</i> |                  |  |          |       |     |
| CT Rated RPM:                                       | 15000            | RPM                                      |          |       |     |
| PT Rated RPM:                                       | 14300            | RPM                                      |          |       |     |
| Rated BHP:  | 7865             | BHP                                      |          |       |     |
| Fuel Gas Analysis                                   |                  | Fuel Meter Type                          |          |       |     |
| Constituent   | Mole Percent     | Enter Type from List Below               |          |       |     |
| Nitrogen  | 1.123            | 2  |          |       |     |
| Carbon Dioxide                                      | 0.457            | Orifice Meter (upstream pressure tap):   | 1        |       |     |
| Methane   | 91.112           | Orifice Meter (downstream pressure tap): | 2        |       |     |
| Ethane  | 6.905            | Electronic Flow Meter (EFM):             | 3        |       |     |
| Propane   | 0.363            | Venturi (Nozzle) Meter:                  | 4        |       |     |
| I-Butane  | 0.015            | Roots Meter w/ Accumulator:              | 5        |       |     |
| N-Butane  | 0.020            | Pipe ID.:                                | 3.068    |       |     |
| I-Pentane   | 0.0004           | Orifice ID.:                             | 1.5      |       |     |
| N-Pentane   | 0.000            |  |          |       |     |
| Hexane +  | 0.004            |  |          |       |     |
| Total   | 100.00           |  |          |       |     |

**Figure 1. Flow Schematic**



Additional Information pertaining to the Fuel Flows may be found in Appendix B.



#### 4. TEST PROCEDURES

EQM and EQM's affiliates and subcontractors use current U.S. EPA accepted testing methodologies in their Air Quality Programs as listed in the U.S. Code of Federal Regulations, Title 40, Part 60, Appendix A. For this testing program, the following specific methodologies were utilized:

- U.S. EPA Method 3A – Determination of Oxygen and Carbon Dioxide Concentrations in Emissions From Stationary Sources (Instrumental Analyzer Procedure)
- U.S. EPA Method 7E – Determination of Nitrogen Oxides Emissions From Stationary Sources (Instrumental Analyzer Procedure)
- U.S. EPA Method 19– Determination of Volumetric Flow Rate From Stationary Sources

USEPA Methods 3A and 7E were performed at the Exhaust Stack sampling location by continuously extracting a gas sample from the stack through a single point stainless steel sample probe. The extracted sample was pulled through a series of filters to remove any particulate matter. Directly after the probe, the sample was conditioned by a series of refrigeration dryers to remove moisture from the gas stream. After the refrigeration dryers, the sample was transported through a Teflon® line to the analyzers. The flow of the stack gas sample was regulated at a constant rate to minimize drift.

At the start of the day, each monitor was checked for calibration error by introducing zero, mid-range and high-range EPA Protocol 1 gases to the measurement system at a point upstream of the analyzers. In this report, the calibration error test is referred to as instrument calibration. The gas was injected into the sampling valve located at the outlet of the sampling probe. The bias test was conducted before and after each consecutive test run by introducing zero and upscale calibration gases for each monitor. The upscale calibration gases used for each monitor were the high calibration gases.

Measurement System Performance Specifications were as follows:

- Analyzer Calibration Error - Less than +/- 2% of the span of the zero, mid-range and high-range calibration gases.
- Sampling System Bias - Less than +/-5% of the span for the zero, mid-range and high-range calibration gases.
- Zero Drift - Less than +/-3% of the span over the period of each test run.
- Calibration Drift - Less than +/-3% of the span over the period of each set of runs.

Calculations that were used in this testing event for the Units No. 6 and No. 7 are as follows:

Calibration Correction

$$C_{GAS} = (C_R - C_O) \frac{C_{MA}}{C_M - C_O}$$

Where:

- $C_{GAS}$ : Corrected flue gas concentration (ppmvd)
- $C_R$ : Flue gas concentration (ppmvd)
- $C_O$ : Average of initial and final zero checks (ppmvd)
- $C_M$ : Average of initial and final span checks (ppmvd)
- $C_{MA}$ : Actual concentration of span gas (ppmvd)

EPA F-Factor

$$F_d = \frac{[(3.64 \cdot H_{Wt\%} \cdot 100) + (1.53 \cdot C_{Wt\%} \cdot 100)]}{GCV} \cdot 10^6$$

$$+ \frac{\left[ \frac{\rho_{FuelGas}}{GCV} \cdot [(0.14 \cdot N_{2Wt\%} \cdot 100) - (0.46 \cdot O_{2Wt\%} \cdot 100)] \right]}{\rho_{FuelGas}} \cdot 10^6$$

Where:

- $F_d$ : Fuel specific F-factor, dscf/MMBtu
- $H_{Wt\%}$ : Hydrogen weight percent
- $C_{Wt\%}$ : Carbon weight percent
- $N_{2Wt\%}$ : Nitrogen weight percent
- $O_{2Wt\%}$ : Oxygen weight percent
- $GCV$ : Heating value of the fuel, BTU/dscf
- $\rho_{Fuel Gas}$ : Density of the fuel gas, lb/scf

NO<sub>x</sub> Corrected to 15% O<sub>2</sub>

$$Em = NO_x \left( \frac{5.9}{20.9 - \%O_2} \right)$$



**Where:**

Em: Pollutant concentration corrected to 15% O<sub>2</sub>, ppm  
NO<sub>x</sub>: Pollutant concentration, ppm  
%O<sub>2</sub>: Oxygen concentration in percent, measured on a dry basis



## 5. QUALITY ASSURANCE PROCEDURES

Each reference method presented in the U.S. Code of Federal Regulations details the instrument calibration requirements, sample recovery and analysis, data reduction and verification, types of equipment required, and the appropriate sampling and analytical procedures to ensure maximum performance and accuracy. EQM and EQM's affiliates and subcontractors adhere to the guidelines for quality control set forth by the United States Environmental Protection Agency. These procedures are outlined in the following documents:

- Code of Federal Regulations, Title 40, Part 51
- Code of Federal Regulations, Title 40, Part 60
- Quality Assurance Handbook, Volume 1, EPA 600/9-76-005
- Quality Assurance Handbook, Volume 2, EPA 600/4-77-027a
- Quality Assurance Handbook, Volume 3, EPA 600/4-77-027b

## 6. CONCLUSIONS

An Emissions Test was conducted on the Turbine 6 and Turbine 7 at TC Energy's ANR Pipeline Company's Goodwell Compressor Station located in White Cloud, MI. The testing was conducted on March 22, 2022.

During the course of the testing, the Turbine 6 and Turbine 7 conformed to the requirements of Code of Federal Regulations, Title 40, Part 60, Appendix A.

The usefulness and/or significance of the emissions values presented in this document as they relate to the compliance status of the Turbine 6 and Turbine 7 emissions shall be determined by others.

For additional information pertaining to the testing program see Appendix E of this report.

**A. FIELD TEST DATA**