

MICHIGAN DEPARTMENT OF ENVIRONMENT, GREAT LAKES, AND ENERGY
AIR QUALITY DIVISION

June 13, 2022

PERMIT TO INSTALL
75-22

ISSUED TO
Asphalt Paving, Inc.

LOCATED AT
45 South Getty Street
Muskegon, Michigan 49444

IN THE COUNTY OF
Muskegon

STATE REGISTRATION NUMBER
P1209

The Air Quality Division has approved this Permit to Install, pursuant to the delegation of authority from the Michigan Department of Environment, Great Lakes, and Energy. This permit is hereby issued in accordance with and subject to Section 5505(1) of Article II, Chapter I, Part 55, Air Pollution Control, of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended. Pursuant to Air Pollution Control Rule 336.1201(1), this permit constitutes the permittee's authority to install the identified emission unit(s) in accordance with all administrative rules of the Department and the attached conditions. Operation of the emission unit(s) identified in this Permit to Install is allowed pursuant to Rule 336.1201(6).

DATE OF RECEIPT OF ALL INFORMATION REQUIRED BY RULE 203: March 21, 2022	
DATE PERMIT TO INSTALL APPROVED: June 13, 2022	SIGNATURE: <i>MaryAnn Dolehanty</i>
DATE PERMIT VOIDED:	SIGNATURE:
DATE PERMIT REVOKED:	SIGNATURE:

PERMIT TO INSTALL

Table of Contents

COMMON ACRONYMS	2
POLLUTANT / MEASUREMENT ABBREVIATIONS.....	3
GENERAL CONDITIONS	4
EMISSION UNIT SPECIAL CONDITIONS.....	6
EMISSION UNIT SUMMARY TABLE	6
EUHMAPLANT	7
EUYARD.....	15
EUACTANKS	17
EUSILOS	18
APPENDIX A.....	20
APPENDIX B.....	21
APPENDIX C.....	23

COMMON ACRONYMS

AQD	Air Quality Division
BACT	Best Available Control Technology
CAA	Clean Air Act
CAM	Compliance Assurance Monitoring
CEMS	Continuous Emission Monitoring System
CFR	Code of Federal Regulations
COMS	Continuous Opacity Monitoring System
Department/department/EGLE	Michigan Department of Environment, Great Lakes, and Energy
EU	Emission Unit
FG	Flexible Group
GACS	Gallons of Applied Coating Solids
GC	General Condition
GHGs	Greenhouse Gases
HVLP	High Volume Low Pressure
ID	Identification
IRSL	Initial Risk Screening Level
ITSL	Initial Threshold Screening Level
LAER	Lowest Achievable Emission Rate
MACT	Maximum Achievable Control Technology
MAERS	Michigan Air Emissions Reporting System
MAP	Malfuction Abatement Plan
MSDS	Material Safety Data Sheet
NA	Not Applicable
NAAQS	National Ambient Air Quality Standards
NESHAP	National Emission Standard for Hazardous Air Pollutants
NSPS	New Source Performance Standards
NSR	New Source Review
PS	Performance Specification
PSD	Prevention of Significant Deterioration
PTE	Permanent Total Enclosure
PTI	Permit to Install
RACT	Reasonable Available Control Technology
ROP	Renewable Operating Permit
SC	Special Condition
SCR	Selective Catalytic Reduction
SNCR	Selective Non-Catalytic Reduction
SRN	State Registration Number
TBD	To Be Determined
TEQ	Toxicity Equivalence Quotient
USEPA/EPA	United States Environmental Protection Agency
VE	Visible Emissions

*For HVLP applicators, the pressure measured at the gun air cap shall not exceed 10 psig.

POLLUTANT / MEASUREMENT ABBREVIATIONS

acfm	Actual cubic feet per minute
BTU	British Thermal Unit
°C	Degrees Celsius
CO	Carbon Monoxide
CO ₂ e	Carbon Dioxide Equivalent
dscf	Dry standard cubic foot
dscm	Dry standard cubic meter
°F	Degrees Fahrenheit
gr	Grains
HAP	Hazardous Air Pollutant
Hg	Mercury
hr	Hour
HP	Horsepower
H ₂ S	Hydrogen Sulfide
kW	Kilowatt
lb	Pound
m	Meter
mg	Milligram
mm	Millimeter
MM	Million
MW	Megawatts
NMOC	Non-Methane Organic Compounds
NO _x	Oxides of Nitrogen
ng	Nanogram
PM	Particulate Matter
PM10	Particulate Matter equal to or less than 10 microns in diameter
PM2.5	Particulate Matter equal to or less than 2.5 microns in diameter
pph	Pounds per hour
ppm	Parts per million
ppmv	Parts per million by volume
ppmw	Parts per million by weight
psia	Pounds per square inch absolute
psig	Pounds per square inch gauge
scf	Standard cubic feet
sec	Seconds
SO ₂	Sulfur Dioxide
TAC	Toxic Air Contaminant
Temp	Temperature
THC	Total Hydrocarbons
tpy	Tons per year
µg	Microgram
µm	Micrometer or Micron
VOC	Volatile Organic Compounds
yr	Year

GENERAL CONDITIONS

1. The process or process equipment covered by this permit shall not be reconstructed, relocated, or modified, unless a Permit to Install authorizing such action is issued by the Department, except to the extent such action is exempt from the Permit to Install requirements by any applicable rule. **(R 336.1201(1))**
2. If the installation, construction, reconstruction, relocation, or modification of the equipment for which this permit has been approved has not commenced within 18 months, or has been interrupted for 18 months, this permit shall become void unless otherwise authorized by the Department. Furthermore, the permittee or the designated authorized agent shall notify the Department via the Supervisor, Permit Section, Air Quality Division, Michigan Department of Environment, Great Lakes, and Energy, P.O. Box 30260, Lansing, Michigan 48909-7760, if it is decided not to pursue the installation, construction, reconstruction, relocation, or modification of the equipment allowed by this Permit to Install. **(R 336.1201(4))**
3. If this Permit to Install is issued for a process or process equipment located at a stationary source that is not subject to the Renewable Operating Permit program requirements pursuant to Rule 210 (R 336.1210), operation of the process or process equipment is allowed by this permit if the equipment performs in accordance with the terms and conditions of this Permit to Install. **(R 336.1201(6)(b))**
4. The Department may, after notice and opportunity for a hearing, revoke this Permit to Install if evidence indicates the process or process equipment is not performing in accordance with the terms and conditions of this permit or is violating the Department's rules or the Clean Air Act. **(R 336.1201(8), Section 5510 of Act 451, PA 1994)**
5. The terms and conditions of this Permit to Install shall apply to any person or legal entity that now or hereafter owns or operates the process or process equipment at the location authorized by this Permit to Install. If the new owner or operator submits a written request to the Department pursuant to Rule 219 and the Department approves the request, this permit will be amended to reflect the change of ownership or operational control. The request must include all of the information required by subrules (1)(a), (b), and (c) of Rule 219 and shall be sent to the District Supervisor, Air Quality Division, Michigan Department of Environment, Great Lakes and Energy. **(R 336.1219)**
6. Operation of this equipment shall not result in the emission of an air contaminant which causes injurious effects to human health or safety, animal life, plant life of significant economic value, or property, or which causes unreasonable interference with the comfortable enjoyment of life and property. **(R 336.1901)**
7. The permittee shall provide notice of an abnormal condition, start-up, shutdown, or malfunction that results in emissions of a hazardous or toxic air pollutant which continue for more than one hour in excess of any applicable standard or limitation, or emissions of any air contaminant continuing for more than two hours in excess of an applicable standard or limitation, as required in Rule 912, to the Department. The notice shall be provided not later than two business days after start-up, shutdown, or discovery of the abnormal condition or malfunction. Written reports, if required, must be filed with the Department within 10 days after the start-up or shutdown occurred, within 10 days after the abnormal condition or malfunction has been corrected, or within 30 days of discovery of the abnormal condition or malfunction, whichever is first. The written reports shall include all of the information required in Rule 912(5). **(R 336.1912)**
8. Approval of this permit does not exempt the permittee from complying with any future applicable requirements which may be promulgated under Part 55 of 1994 PA 451, as amended or the Federal Clean Air Act.
9. Approval of this permit does not obviate the necessity of obtaining such permits or approvals from other units of government as required by law.
10. Operation of this equipment may be subject to other requirements of Part 55 of 1994 PA 451, as amended and the rules promulgated thereunder.

11. Except as provided in subrules (2) and (3) or unless the special conditions of the Permit to Install include an alternate opacity limit established pursuant to subrule (4) of Rule 301, the permittee shall not cause or permit to be discharged into the outer air from a process or process equipment a visible emission of density greater than the most stringent of the following. The grading of visible emissions shall be determined in accordance with Rule 303 (R 336.1303). **(R 336.1301)**
 - a) A six-minute average of 20 percent opacity, except for one six-minute average per hour of not more than 27 percent opacity.
 - b) A visible emission limit specified by an applicable federal new source performance standard.
 - c) A visible emission limit specified as a condition of this Permit to Install.
12. Collected air contaminants shall be removed as necessary to maintain the equipment at the required operating efficiency. The collection and disposal of air contaminants shall be performed in a manner so as to minimize the introduction of contaminants to the outer air. Transport of collected air contaminants in Priority I and II areas requires the use of material handling methods specified in Rule 370(2). **(R 336.1370)**
13. The Department may require the permittee to conduct acceptable performance tests, at the permittee's expense, in accordance with Rule 1001 and Rule 1003, under any of the conditions listed in Rule 1001. **(R 336.2001)**

EMISSION UNIT SPECIAL CONDITIONS

EMISSION UNIT SUMMARY TABLE

The descriptions provided below are for informational purposes and do not constitute enforceable conditions.

Emission Unit ID	Emission Unit Description (Including Process Equipment & Control Device(s))	Flexible Group ID
EUHMAPLANT	Hot mix asphalt (HMA) facility including: aggregate conveyors, cold feed aggregate bins, and a 310 tph counter-flow drum equipped with a burner rated at 75 MMBtu/hr heat input and a 55,407 cfm baghouse.	NA
EUYARD	Fugitive dust sources including: plant roadways, plant yard, material storage piles, material handling operations (excluding cold feed aggregate bins).	NA
EUACTIONKANS	Two 20,000 gallon liquid asphalt cement storage tanks and a Hot Oil Heater (HOH) with a total heat capacity of 3 MMBtu/hr.	NA
EUSILOS	Three 200 ton capacity hot mix asphalt (HMA) paving material product storage silos.	NA

Changes to the equipment described in this table are subject to the requirements of R 336.1201, except as allowed by R 336.1278 to R 336.1291.

**EUHMAPLANT
 EMISSION UNIT CONDITIONS**

DESCRIPTION

Hot mix asphalt (HMA) facility including: aggregate conveyors, cold feed aggregate bins, and a 310 tph counter-flow drum with a 75 MMBtu/hr heat input.

Flexible Group ID: NA

POLLUTION CONTROL EQUIPMENT

A 55,407 cfm fabric filter bag system (baghouse)

I. EMISSION LIMIT(S)

Pollutant	Limit	Time Period / Operating Scenario	Equipment	Monitoring / Testing Method	Underlying Applicable Requirements
1. PM	0.04 gr/dscf	Hourly	EUHMAPLANT	SC V.5, SC VI.4	40 CFR 60.92
2. PM	0.03 lb per ton ^b	Hourly	EUHMAPLANT	SC V.3	R 336.1205(1)(a),
3. PM	4.5 tpy ^a	12-month rolling time period as determined at the end of each calendar month	EUHMAPLANT	SC VI.8	R 336.1205(1)(a)
4. PM10	0.03 lb per ton ^b	Hourly	EUHMAPLANT	SC V.3	R 336.1205(1)(a), R 336.1205(3), 40 CFR 52.21(c) & (d)
5. PM10	4.5 tpy ^a	12-month rolling time period as determined at the end of each calendar month	EUHMAPLANT	SC VI.8	R 336.1205(1)(a), R 336.1205(3)
6. PM2.5	0.03 lb per ton ^b	Hourly	EUHMAPLANT	SC V.3	R 336.1205(1)(a), R 336.1205(3), 40 CFR 52.21(c) & (d)
7. PM2.5	4.5 tpy ^a	12-month rolling time period as determined at the end of each calendar month	EUHMAPLANT	SC VI.8	R 336.1205(1)(a), R 336.1205(3)
8. CO	0.2 lb per ton ^b	Hourly	EUHMAPLANT	SC V.3	R 336.1205(1)(a), R 336.1205(3)
9. CO	30.0 tpy ^a	12-month rolling time period as determined at the end of each calendar month	EUHMAPLANT	SC VI.8	R 336.1205(1)(a), R 336.1205(3)
10. SO ₂	0.004 lb per ton ^b	Hourly	EUHMAPLANT	SC V.2	R 336.1205(1)(a), R 336.1205(3)

Pollutant	Limit	Time Period / Operating Scenario	Equipment	Monitoring / Testing Method	Underlying Applicable Requirements
11. SO ₂	0.6 tpy ^a	12-month rolling time period as determined at the end of each calendar month	EUHMAPLANT	SC VI.8	R 336.1205(1)(a), R 336.1205(3)
12. NO _x	0.07 lb per ton ^b	Hourly	EUHMAPLANT	SC V.3	R 336.1205(1)(a), R 336.1205(3)
13. NO _x	10.5 tpy ^a	12-month rolling time period as determined at the end of each calendar month	EUHMAPLANT	SC VI.8	R 336.1205(1)(a), R 336.1205(3)
14. Lead	1.5 x 10 ⁻⁵ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	40 CFR 52.21(c) & (d)
15. Benzene	7.5 x 10 ⁻⁴ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	R 336.1224, R 336.1225
16. Toluene	3.0 x 10 ⁻³ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	R 336.1224, R 336.1225
17. Ethylbenzene	1.0 x 10 ⁻³ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	R 336.1224, R 336.1225
18. Xylene	1.0 x 10 ⁻³ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	R 336.1224, R 336.1225
19. Naphthalene	7.8 x 10 ⁻⁴ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2, SC V.4	R 336.1224, R 336.1225
20. Formaldehyde	5.4 x 10 ⁻³ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	R 336.1224, R 336.1225
21. Arsenic	2.0 x 10 ⁻⁶ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	R 336.1224, R 336.1225
22. Nickel	7.6 x 10 ⁻⁵ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2, SC V.4	R 336.1224, R 336.1225
23. Manganese	3.5 x 10 ⁻⁴ lb per ton ^{b,1}	Hourly	EUHMAPLANT	SC V.2	R 336.1224, R 336.1225

Pollutant	Limit	Time Period / Operating Scenario	Equipment	Monitoring / Testing Method	Underlying Applicable Requirements
24. Opacity	20%	6 minute average	Drum dryer; systems for screening, handling, storing, and weighing hot aggregate; systems for loading, transferring, and storing (piles) of mineral filler, systems for mixing HMA; and the loading, transfer, and storage systems associated with emission control systems	SC V.5	40 CFR 60.92
<p>^a Annual limits based on 300,000 tons HMA paving material production.</p> <p>^b Pound pollutant per ton of HMA paving material produced.</p>					

II. MATERIAL LIMIT(S)

1. The permittee shall not burn any fuel other than natural gas in EUHMAPLANT. **(R 336.1224, R 336.1225, R 336.1702)**
2. The permittee shall not use any asbestos tailings or waste materials containing asbestos in EUHMAPLANT pursuant to the National Emission Standards for Hazardous Air Pollutants, 40 CFR Part 61, Subpart M. **(R 336.1225, 40 CFR Part 61 Subparts A & M)**
3. The permittee shall limit the asphalt mixture produced in EUHMAPLANT to a maximum of 50 percent RAP material based on a monthly average. **(R 336.1224, R 336.1225, R 336.1702)**
4. The permittee shall not produce more than 300,000 tons of HMA paving materials in EUHMAPLANT per 12-month rolling time period as determined at the end of each calendar month. **(R 336.1205(1)(a), R 336.1205(3))**
5. The permittee shall not produce more than 310 tons of HMA paving materials per hour averaged over each operating hour per calendar day in EUHMAPLANT. **(R 336.1224, R 336.1225, R 336.1702, 40 CFR 52.21(c) & (d))**

III. PROCESS/OPERATIONAL RESTRICTION(S)

1. The permittee shall not operate EUHMAPLANT unless the Fugitive Dust Control Plan for EUYARD specified in Appendix A has been implemented and is maintained. **(R 336.1371, R 336.1372, Act 451 324.5524)**
2. The permittee shall not operate EUHMAPLANT unless the Preventative Maintenance Program specified in Appendix B has been implemented and is maintained. **(R 336.1910, R 336.1911)**
3. The permittee shall not operate EUHMAPLANT unless the Emission Abatement Plan for Startup, Shutdown and Malfunctions specified in Appendix C has been implemented and is maintained. **(R 336.1911, R 336.1912)**

4. The permittee shall maintain the efficiency of the EUHMAPLANT drum mix burners, to control CO emissions, by fine tuning the burners for proper burner operation and performance. The permittee shall fine tune the burners at the startup of the drum mix fuel burners; upon each paving season; after every 500 hours of operation thereafter or upon a malfunction of EUHMAPLANT as shown by the CO emission monitoring data, whichever occurs first. **(R 336.1205, R 336.1224, R 336.1225, R 336.170240, 40 CFR 52.21(c) & (d))**
5. The permittee shall install and operate the asphalt plant as reviewed in the permit application APP-2021-0149 except as allowed under Rules 201 and Rule 278(1)(b). **(R 336.1201(1), R 336.1205, R 336.1224, R 336.1225, 40 CFR 52.21(c) & (d))**

IV. DESIGN/EQUIPMENT PARAMETER(S)

1. The permittee shall install, maintain, and operate the fabric filter dust collector, associated parameter monitoring, recording system, and associated alarm systems for EUHMAPLANT in a satisfactory manner. The baghouse shall be equipped with a bag leak detection system and alarm. The bag leak alarm system shall be calibrated and fully operational within 180 days of startup Satisfactory operation of the fabric filter dust collector requires a pressure drop range between 2 and 10 inches of water column during operation. The minimum pressure drop shall not be less than 2 inches water gauge during operation, except when a large number of filter bags have been replaced or other reason acceptable to the AQD. **(R 336.1910, 40 CFR 52.21(c) & (d))**
2. The permittee shall install, calibrate, maintain and operate in a satisfactory manner, a device to monitor the virgin aggregate feed rate and the RAP feed rate to EUHMAPLANT on a continuous basis. **(R 336.1224, R 336.1225, R 336.1702)**

V. TESTING/SAMPLING

Records shall be maintained on file for a period of five years. **(R 336.1201(3))**

1. The verification and quantification of odor emissions from EUHMAPLANT, by testing at owner's expense, in accordance with Department requirements may be required for continued operation. Within 60 days upon notification from the AQD District Supervisor, the permittee shall submit to the AQD Technical Programs Unit and District Office, a complete stack sampling and odor threshold analysis plan using the Dynamic Dilution Method. The stack sampling plan shall include provisions for various fuel usages, plant operating conditions, and odor neutralizer system operation (if any). The AQD must approve the final plan prior to testing. The permittee must submit a complete report of the test results to the AQD Technical Programs Unit and District Office within 120 days from notification from the AQD District Supervisor. **(R 336.1901, R 336.2001, R 336.2003, R 336.2004)**
2. Within 180 days after a request by the Department, the permittee shall verify any requested emission rates from EUHMAPLANT by testing at the owner's expense, in accordance with Department requirements. Testing shall be performed using an approved EPA Method listed in the table below.

Pollutant	Test Method Reference
PM	40 CFR Part 60, Appendix A; Part 10 of the Michigan Air Pollution Control Rules
PM10 / PM2.5	40 CFR Part 51, Appendix M
NO _x	40 CFR Part 60, Appendix A
SO ₂	40 CFR Part 60, Appendix A
CO	40 CFR Part 60, Appendix A
VOCs	40 CFR Part 60, Appendix A
Metals	40 CFR Part 60, Appendix A; 40 CFR Part 61, Appendix B; 40 CFR Part 63, Appendix A
HAPs	40 CFR Part 63, Appendix A

An alternate method, or a modification to the approved EPA Method, may be specified in an AQD approved Test Protocol and must meet the requirements of the federal Clean Air Act, all applicable state and federal rules and regulations, and be with the authority of the AQD to make the change. No less than 30 days prior

to testing, the permittee shall submit a complete test plan to the AQD Technical Programs Unit and District Office. The AQD must approve the final plan prior to testing, including any modifications to the method in the test protocol that are proposed after initial submittal. The permittee must submit a complete report of the test results to the AQD Technical Programs Unit and District Office within 60 days following the last date of the test. **(R 336.1225, R 336.2001, R 336.2003, R 336.2004)**

3. Within 60 days after achieving the maximum production rate, but not later than 180 days after commencement of trial operation, the permittee shall verify PM, PM10, PM2.5, NOx, CO, and VOCs from EUHMAPLANT by testing at the owner's expense, in accordance with Department requirements. Subsequently, testing for these pollutants shall be performed once every five (5) years thereafter. Testing shall be performed using an approved EPA Method listed in the table below.

Pollutant	Test Method Reference
PM	40 CFR Part 60, Appendix A; Part 10 of the Michigan Air Pollution Control Rules
PM10 / PM2.5	40 CFR Part 51, Appendix M
NO _x	40 CFR Part 60, Appendix A
CO	40 CFR Part 60, Appendix A
VOCs	40 CFR Part 60, Appendix A

An alternate method, or a modification to the approved EPA Method, may be specified in an AQD approved Test Protocol and must meet the requirements of the federal Clean Air Act, all applicable state and federal rules and regulations, and be with the authority of the AQD to make the change. No less than 30 days prior to testing, the permittee shall submit a complete test plan to the AQD Technical Programs Unit and District Office. The AQD must approve the final plan prior to testing, including any modifications to the method in the test protocol that are proposed after initial submittal. The permittee must submit a complete report of the test results to the AQD Technical Programs Unit and District Office within 60 days following the last date of the test. **(R 336.1205(1)(a), R 336.1205(3), R 336.2001, R 336.2003, R 336.2004, 40 CFR 52.21(c) & (d))**

4. Within 60 days after achieving the maximum production rate, but not later than 180 days after commencement of trial operation, the permittee shall verify formaldehyde and nickel from EUHMAPLANT by initial performance testing at the owner's expense, in accordance with Department requirements. Testing shall be performed using an approved EPA Method listed in the table below.

Pollutant	Test Method Reference
Metals	40 CFR Part 60, Appendix A; 40 CFR Part 61, Appendix B; 40 CFR Part 63, Appendix A
HAPs	40 CFR Part 63, Appendix A

An alternate method, or a modification to the approved EPA Method, may be specified in an AQD approved Test Protocol and must meet the requirements of the federal Clean Air Act, all applicable state and federal rules and regulations, and be with the authority of the AQD to make the change. No less than 30 days prior to testing, the permittee shall submit a complete test plan to the AQD Technical Programs Unit and District Office. The AQD must approve the final plan prior to testing, including any modifications to the method in the test protocol that are proposed after initial submittal. The permittee must submit a complete report of the test results to the AQD Technical Programs Unit and District Office within 60 days following the last date of the test. **(R 336.1205(1)(a), R 336.1205(3), R 336.2001, R 336.2003, R 336.2004, 40 CFR 52.21(c) & (d))**

5. Within 60 days after achieving the maximum production rate, but not later than 180 days after commencement of trial operation, the permittee shall verify particulate emission (PM) rates from EUHMAPLANT, as required by federal Standards of Performance for New Stationary Sources, by testing at owner's expense, in accordance with 40 CFR Part 60 Subparts A and I. The permittee shall notify the AQD District Supervisor in writing within 15 days of the date of commencement of trial operation in accordance with 40 CFR 60.7(a)(3). Stack testing procedures and the location of stack testing ports shall be in accordance with the applicable federal Reference Methods, 40 CFR Part 60 Appendix A. No less than 30 days prior to testing, the permittee shall submit a complete test plan to the AQD Technical Programs Unit and District Office. The AQD must approve the final plan prior to testing. The permittee must submit a complete report of the test results to the AQD Technical Programs Unit and District Office within 60 days following the last date of the test. **(40 CFR Part 60 Subparts A & I))**

6. Upon start-up of plant operations, the permittee shall perform observations for the presence of visible emission around the site which shall include the drum dryer; systems for screening, handling, storing, and weighing hot aggregate; systems for loading, transferring, and storing (including piles) mineral filler/aggregate; and the loading, transfer, and storage systems associated with emission control systems. The observations shall be conducted at least once per day of operation when EUHMAPLANT is operating during daylight hours, using a method acceptable to the AQD. If the permittee observes visible emissions, the permittee shall do one of the following:
 - a) Determine the cause of the visible emission and initiate corrective action; or
 - b) Perform a Method 9 for visible emissions evaluation. If, after performing a Method 9 visible emissions evaluation, the permittee determines that the opacity of visible emissions from an emission point exceeds 20% opacity or 5% opacity (as specified in Appendix A, the Fugitive Dust Control Plan), the permittee shall immediately initiate an investigation to determine the cause of the visible emissions and initiate prompt corrective action.

Records for visible emissions observations shall be maintained and shall include a description of the emission point observed, the date and time of day each visible emissions observation was conducted, whether visible emissions were observed, whether Method 9 was conducted for any emission point and the result of the Method 9 evaluation, the corrective action taken if necessary, and the date and time the corrective action was completed. During each calendar week of the first paving season, a minimum of one Method 9 evaluation is required for each potential fugitive emission source. During the second paving season, if the weekly Method 9 evaluations demonstrate that there have been no visible emissions exceeding the opacity limits established in this permit, the periodic Method 9 evaluations may be reduced to a minimum of one evaluation during each calendar month for each potential fugitive emission source. Upon conclusion of the second paving season, the permittee may apply to the Grand Rapids District Office to request exemption from the monthly Method 9 evaluations and/or recording the daily observations. The request for the exemption must include copies of all records associated with the visible emissions observations and evaluations, and an explanation why the permittee believes it is no longer necessary to conduct periodic Method 9 evaluations. **(40 CFR 60.92, R 336.2001, R 336.2003, R 336.2004)**

VI. MONITORING/RECORDKEEPING

Records shall be maintained on file for a period of five years. **(R 336.1201(3))**

1. The permittee shall complete all required calculations in a format acceptable to the AQD District Supervisor by the 15th day of the calendar month, for the previous calendar month, unless otherwise specified in any monitoring/recordkeeping special condition. **(R 336.1205(1)(a))**
2. The permittee shall monitor and record, in a satisfactory manner, the virgin aggregate feed rate and the RAP feed rate to EUHMAPLANT on a continuous basis during operation. **(R 336.1224, R 336.1225, R 336.1702)**
3. The permittee shall monitor, with a handheld CO monitor, the CO emissions from EUHMAPLANT and the production data associated with the time the emissions data were collected. The CO emissions should be less than 500 ppmv to ensure EUHMAPLANT is operating properly. One data set shall be recorded for each of the following occurrences:
 - a) Upon start-up of each paving season.
 - b) Upon a malfunction of the drum dryer or its associated burner.
 - c) After every 500 hours of operation.

A data set shall consist of at least eight separate CO readings and shall be taken over a total time period of 30 minutes or longer. The permittee shall submit any request for an alternate monitoring schedule in writing to the AQD District Supervisor for review and approval. Data collected by this method shall be used for determining proper burner operation. **(R 336.1205(1)(a), R 336.1205(3), R 336.1224, R 336.1225, R 336.1702)**

4. The permittee shall monitor emissions and operating information in accordance with the federal Standards of Performance for New Stationary Sources as specified in 40 CFR Part 60 Subparts A and I for EUHMAPLANT. The permittee shall keep records of all source emissions data and operating information on file at the facility and make them available to the Department upon request. **(40 CFR Part 60 Subparts A & I)**

5. The permittee shall conduct all necessary maintenance and make all necessary attempts to keep all drum mixer/burner and fabric filter dust collector components of EUHMAPLANT maintained and operating in a satisfactory manner. The owner or operator shall maintain a log of all significant maintenance activities conducted and all significant repairs made to EUHMAPLANT. Maintenance records for the fabric filter dust collector shall be consistent with the Preventative Maintenance Program specified in Appendix B. The permittee shall keep all records on file and make them available to the Department upon request. **(R 336.1910, R 336.1911, 40 CFR 52.21(c) & (d))**
6. The permittee shall keep a record of the tons of hot mix asphalt containing RAP produced, including the average percent of RAP per ton of hot mix asphalt produced containing RAP records for each calendar month that EUHMAPLANT is operated. The permittee shall keep all records on file and make them available to the Department upon request. **(R 336.1205(1)(a), R 336.1205(3), R 336.1224, R 336.1225, R 336.1402, R 336.1702)**
7. The permittee shall keep daily records of the following production information for EUHMAPLANT, updated upon the start of each new blend:
 - a) The virgin aggregate feed rate.
 - b) The RAP feed rate.
 - c) The asphalt paving material product temperature.
 - d) Information sufficient to identify all ingredients of the asphalt paving material mixture.

Upon start-up, the permittee shall record the initial mix design and time. When a new mix design is activated after start-up, the permittee shall record the time and new mix design. The permittee shall keep all records on file until the end of the paving season in which they were recorded and make them available to the Department upon request. **(R 336.1205(1)(a), R 336.1205(3), R 336.1224, R 336.1225, R 336.1702)**
8. The permittee shall keep in a satisfactory manner, monthly and 12-month rolling time period emission calculation records of all criteria pollutants listed in the Emission Limit Table for EUHMAPLANT. If stack test results for EUHMAPLANT exist for any of the pollutants, the permittee may use those stack test results to estimate pollutant emissions subject to the approval of the AQD. In the event that stack test results do not exist for a specific pollutant, the permittee shall use the applicable emission factor listed in the Emission Limit Table to estimate the emissions of a pollutant from EUHMAPLANT. The permittee shall keep all records on file and make them available to the Department upon request. **(R 336.1205(1)(a), R 336.1205(3), R 336.1225, R 336.1702)**
9. The permittee shall keep records, as described in SC VI.3, of all CO emissions and related production data including the dates and times emissions were monitored. This data shall be used to ensure proper operation of the drum dryer or associated burner. The permittee shall keep all records on file and make them available to the Department upon request. **(R 336.1205(1)(a), R 336.1205(3), R 336.1224, R 336.1225, R 336.1702)**
10. The permittee shall keep, in a satisfactory manner, daily, monthly, and 12-month rolling time period records of the amount of HMA paving materials produced from EUHMAPLANT. The permittee shall keep all records on file and make them available to the Department upon request. **(R 336.1205(1)(a), R 336.1205(3))**
11. The permittee shall keep, in a satisfactory manner, daily records of the hours of operation of EUHMAPLANT. The permittee shall keep all records on file and make them available to the Department upon request. **(R 336.1205(1)(a), R 336.1205(3))**
12. The permittee shall record, in a satisfactory manner, the pressure drop for the fabric filter controlling EUHMAPLANT emissions once per day during operation. **(R 336.1224, R 336.1225, R 336.1910)**
13. The permittee shall record all parameter alarm instances for the EUHMAPLANT fabric filter system including the reason the alarm was activated and the actions taken. **(R 336.1224, R 336.1225, R 336.1910)**
14. The permittee shall keep monthly records of the average percent of RAP per ton of hot mix asphalt containing RAP produced. **(R 336.1224, R 336.1225, R 336.1702)**

15. The permittee shall keep daily records of the following production information for EUHMAPLANT:
- a) Hours of operation
 - b) Total production in tons
 - c) Average ton/hour production rate for based on the total throughput for the day and hours of operation
- The permittee shall keep all records on file until the end of the paving season in which they were recorded and make them available to the Department upon request. **(R 336.1205(1)(a), R 336.1205(3), R 336.1224, R 336.1225, R 336.1702)**

VII. REPORTING

1. Within 30 days after completion of the installation, construction, reconstruction, relocation, or modification authorized by this Permit to Install, the permittee or the authorized agent pursuant to Rule 204, shall notify the AQD District Supervisor, in writing, of the completion of the activity. Completion of the installation, construction, reconstruction, relocation, or modification is considered to occur not later than commencement of trial operation of EUHMAPLANT. **(R 336.1201(7)(a))**

VIII. STACK/VENT RESTRICTION(S)

The exhaust gases from the stacks listed in the table below shall be discharged unobstructed vertically upwards to the ambient air unless otherwise noted:

Stack & Vent ID	Maximum Exhaust Diameter / Dimensions (inches)	Minimum Height Above Ground (feet)	Underlying Applicable Requirements
1. SVHMADRUM	42	60	R 336.1225, 40 CFR 52.21(c) & (d)

IX. OTHER REQUIREMENT(S)

NA

Footnotes:

¹ This condition is state only enforceable and was established pursuant to Rule 201(1)(b).

EUYARD EMISSION UNIT CONDITIONS

DESCRIPTION

Fugitive dust sources including: plant roadways, plant yard, material storage piles, material handling operations (excluding cold feed aggregate bins).

Flexible Group ID: NA

POLLUTION CONTROL EQUIPMENT

Controls as specified in the Fugitive Dust Control Plan in Appendix A

I. EMISSION LIMIT(S)

1. During the operating season, the permittee shall control the emissions from all storage piles, roads and unpaved travel surfaces by the application of water, sweeping, vacuuming, or other acceptable dust control method on a frequency sufficient to meet the visible emission opacity standard of five (5) percent opacity on a continuous basis. **(40 CFR 52.21(c) & (d), Section 5524 of Article II, Chapter 1, Part 55, Air Pollution Control, of the Natural Resources and Environmental Protection Act, 1994 PA 451)**

II. MATERIAL LIMIT(S)

NA

III. PROCESS/OPERATIONAL RESTRICTION(S)

1. The permittee shall not operate EUYARD unless the fugitive dust control plan specified in Appendix A has been implemented and is maintained. The permittee shall submit modifications to this fugitive dust control plan if it does not adequately control the emissions upon request of the District Supervisor. Any changes made to the fugitive dust plan must be pre-approved in writing from the district prior to implementation. **(R 336.1371, R 336.1372, Act 451 324.5524, 40 CFR 52.21(c) & (d))**

IV. DESIGN/EQUIPMENT PARAMETER(S)

1. The permittee shall maintain a 3-sided, roofed structure onsite to store up to three aggregate stockpiles within in the structure including the aggregate material with the highest silt content. **(40 CFR 52.21(c) & (d))**

V. TESTING/SAMPLING

NA

VI. MONITORING/RECORDKEEPING

Records shall be maintained on file for a period of five years. **(R 336.1201(3))**

1. The permittee shall complete all required calculations in a format acceptable to the AQD District Supervisor by the 15th day of the calendar month, for the previous calendar month, unless otherwise specified in any monitoring/recordkeeping special condition. **(R 336.1371, R 336.1372)**
2. The permittee shall calculate, in a satisfactory manner, the annual fugitive dust emissions for EUYARD for each reporting year, using emission factors approved by the Department such as those used in the current U.S. EPA Compilation of Air Pollutant Emission Factors (AP-42, MAERS, WebFIRE or an approved PTI application). **(R 336.1371, R 336.1372)**

3. The permittee shall maintain a record of all activities required by the fugitive dust plan in Appendix A. **(R 336.1371, R 336.1372)**
4. The permittee shall make available upon request by the Department the silt content for each aggregate stored onsite based on the percent by weight passing the #200 sieve. **(40 CFR 52.21(c) & (d))**

VII. REPORTING

1. The permittee shall report the actual emission levels for EUYARD to the AQD through the annual emission reporting required under Section 5503(k) of Article II, Chapter 1, Part 55, Air Pollution Control, of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended (Act 451). **(R 336.1371, R 336.1372)**

VIII. STACK/VENT RESTRICTION(S)

NA

IX. OTHER REQUIREMENT(S)

NA

EUACTANKS EMISSION UNIT CONDITIONS

DESCRIPTION

Two 20,000 gallon liquid asphalt cement storage tanks and a Hot Oil Heater (HOH) with a total heat capacity of 3 MMBtu/hr

Flexible Group ID: NA

POLLUTION CONTROL EQUIPMENT

Vapor condensation and recovery system

I. EMISSION LIMIT(S)

NA

II. MATERIAL LIMIT(S)

NA

III. PROCESS/OPERATIONAL RESTRICTION(S)

1. The permittee shall not operate EUACTANKS unless the vapor condensation and recovery system is installed, maintained, and operated consistent with manufacturers recommendations.. **(R 336.1224, R 336.1702, R 336.1910)**

IV. DESIGN/EQUIPMENT PARAMETER(S)

NA

V. TESTING/SAMPLING

NA

VI. MONITORING/RECORDKEEPING

Records shall be maintained on file for a period of five years. **(R 336.1201(3))**

1. The permittee shall maintain records for maintenance activities on EUACTANKS consistent with the manufacturers recommendations to determine that the vapor condensation and recovery system is operating properly. All records shall be kept on file and made available to the Department upon request. **(R 336.1224, R 336.1702, R 336.1910)**

VIII. STACK/VENT RESTRICTION(S)

NA

IX. OTHER REQUIREMENT(S)

NA

EUSILOS EMISSION UNIT CONDITIONS

DESCRIPTION

Three 200 ton capacity hot mix asphalt (HMA) paving material product storage silos.

Flexible Group ID: NA

POLLUTION CONTROL EQUIPMENT

Top of silo emission controls and loadout controls

I. EMISSION LIMIT(S)

NA

II. MATERIAL LIMIT(S)

NA

III. PROCESS/OPERATIONAL RESTRICTION(S)

1. The permittee shall not operate EUSILOS unless the emission capture system for the top of each storage silo is installed, maintained, and operated in a satisfactory manner. **(R 336.1224, R 336.1702, R 336.1910)**
2. The permittee shall not operate EUSILOS unless emissions from the load-out area are properly captured and controlled. Unless otherwise specified by the District Supervisor, proper capture includes enclosing the truck load-out area with sides that extend to five feet above the top of the road grade at the entrance to the scale and, if appropriate, include wind blocking for entrance and exit points. If the load-out area inadequately captures and controls load-out emissions, the permittee shall modify the system or operation as requested by the District Supervisor. The permittee shall vent emissions collected from the truck load-out area into a filtering system or shall control the emissions by equivalent means. Any plans considered by the permittee as equivalent means shall be pre-approved in writing by the District Supervisor. The permittee shall not operate EUSILOS unless the silo load-out control system is installed, maintained and operated in a satisfactory manner **(R 336.1224, R 336.1702, R 336.1901, R 336.1910)**
3. No later than 60 days after the initial startup of EUSILOS, the permittee shall submit to the AQD District Supervisor, for review and approval, a preventative maintenance / malfunction abatement plan (PM / MAP) for the emissions capture system on the top of each storage silo and the silo load-out control system. After approval of the PM / MAP by the AQD District Supervisor, the permittee shall not operate EUSILOS unless the PM / MAP, or an alternate plan approved by the AQD District Supervisor, is implemented and maintained. The plan shall incorporate procedures recommended by the equipment manufacturer as well as incorporating standard industry practices. At a minimum, the plan shall include:
 - a) Identification of the equipment and, if applicable, air-cleaning device and the supervisory personnel responsible for overseeing the inspection, maintenance, and repair.
 - b) Description of the items or conditions to be inspected and frequency of the inspections or repairs.
 - c) Identification of the equipment and, if applicable, air-cleaning device, operating parameters that shall be monitored to detect a malfunction or failure, the normal operating range of these parameters and a description of the method of monitoring or surveillance procedures.
 - d) Identification of the major replacement parts that shall be maintained in inventory for quick replacement.
 - e) A description of the corrective procedures or operational changes that shall be taken in the event of a malfunction or failure to achieve compliance with the applicable emission limits.

The permittee shall keep records of all maintenance performed and all parameters monitored and make them available to the Department upon request. If the plan fails to address or inadequately addresses an event that meets the characteristics of a malfunction at the time the plan is initially developed, the owner or operator shall revise the plan within 45 days after such an event occurs and submit the revised plan for approval to the AQD District Supervisor. Should the AQD determine the PM / MAP to be inadequate, the AQD District Supervisor may request modification of the plan to address those inadequacies. (R 336.1205, R 336.1225, R 336.1702(a), R 336.1910, R 336.1911, R 336.1912, 40 CFR 52.21(c) & (d))

IV. DESIGN/EQUIPMENT PARAMETER(S)

NA

V. TESTING/SAMPLING

NA

VI. MONITORING/RECORDKEEPING

NA

VIII. STACK/VENT RESTRICTION(S)

NA

IX. OTHER REQUIREMENT(S)

NA

APPENDIX A FUGITIVE DUST CONTROL PLAN

PURPOSE: This plan provides dust control strategies for the areas adjacent to and associated with the equipment operations involved in the manufacture of Hot Mix Asphalt (HMA) paving materials.

1. SITE MAINTENANCE

- a) Dust on all areas where vehicular traffic will travel shall be controlled by the application of water, sweeping, vacuuming, or other acceptable dust control method. This will occur a minimum of two times per month if using calcium chloride or weekly if using water during periods of operation. Watering may not be required during periods with precipitation. The dust control method shall be acceptable as determined by the District Supervisor. If fugitive emissions are observed from haul roads or track-out occurs, abatement actions such as sweeping/watering shall increase in frequency until no further fugitive emissions or track-out occurs.
- b) The speed of vehicles on the site will be limited to 10 miles per hour or less. Signs will be posted to advise drivers entering the facility of the speed limitation.
- c) The drop heights of all material transfer points and screening operations shall be minimized
- d) The permittee shall visibly monitor all potential areas of fugitive emissions including material transfer points, storage piles, loadout, and facility entrance.

2. MANAGEMENT OF ON-SITE ROADWAYS

- a) All the roadways on which the HMA haul vehicles and aggregate haul trucks will travel must be paved with HMA. This includes the roadway on which the vehicles travel around the process equipment to be loaded with HMA paving materials and the aggregate storage yard.
- b) Any aggregate spillage on roads shall be removed immediately.

3. ON-SITE MANAGEMENT OF HAUL VEHICLES

- a) **INCOMING HAUL VEHICLES:** All haul vehicles entering the site to deliver aggregates will be required to have the loads covered.
- b) **OUT-GOING HAUL VEHICLES:** All haul vehicles leaving the site with HMA paving materials will be required to cover their loads prior to leaving the site. A sign shall be posted to advise drivers of this requirement.

4. MANAGEMENT OF FRONT-END LOADER OPERATIONS

The front-end loader operator shall be directed to avoid overfilling the bucket of the loader and the feed hoppers to prevent spillage, and to minimize the drop height of the material when loading the feed hoppers or transferring material to stockpiles.

5. RECORDKEEPING

Records of dust control activities on travel surfaces and other surfaces where fugitive dust emissions occur shall be kept on file and made available to EGLE staff upon request until the end of the paving season. The records will indicate the date, time, what was observed or the reason for the dust control activity (routine or other), and what action was taken. The record shall be maintained in the Operations Log Book.

6. FUGITIVE EMISSIONS FROM PROCESS EQUIPMENT AND FABRIC FILTER DUST COLLECTOR

Any fugitive emissions from leak(s) and malfunction(s) from any transfer system, storage bin, mixer, hopper, or fabric filter dust collector shall be immediately corrected to prevent further fugitive emissions.

7. FUGITIVE EMISSIONS FROM MINERAL AGGREGATE STOCKPILES

- a) Stock piling will be performed in a manner that minimizes freefall drop distance. The height of the front-end loader bucket shall be minimized to reduce the material drop height.
- b) Piles will be maintained to prevent fugitive dust in compliance with EUYARD SC I.1. This includes the use of watering, covering, encrusting agents or enclosure in a building.

APPENDIX B PREVENTATIVE MAINTENANCE PROGRAM FOR THE FABRIC FILTER DUST COLLECTOR

The Preventative Maintenance Program for the Fabric Filter Dust Collector is for the purpose of keeping the dust collector in good operating condition, and thereby, maintaining the rated capture efficiency of the dust collector for the control of particulate matter. ALL REFERENCES TO VISIBLE EMISSIONS IN THIS DOCUMENT, PARTICULARLY IN SEC. 5, REFER SPECIFICALLY TO VISIBLE EMISSIONS CAUSED BY A DUST (PARTICULATE) EMISSION.

1. FABRIC FILTER DUST COLLECTOR OPERATING PRESSURE DROP.

- a) The pressure drop across the fabric filter dust collector shall be continuously measured and the minimum pressure drop shall not be less than 2 inches, water gauge, except when a large number of filter bags have been replaced or other reason acceptable to the AQD.
- b) The pressure drop across the fabric filter dust collector shall be recorded once per day during operation and kept available on-site.

2. FABRIC FILTER DUST COLLECTOR / PLANT ALARM SYSTEM.

The fabric filter dust collector shall be equipped with a high temperature sensor and alarm system and pressure detection sensor and alarm system. The baghouse shall also be equipped with a bag leak detection system and alarm that directly monitors changes in particulate emissions. The high temperature alarm system shall be designed to set off an alarm when the high temperature set-point has been violated, and, to begin a sequential shut-down of the plant if the situation is not resolved within a very short period of time after the alarm sounds. The pressure detection sensor shall be designed to set off an alarm when the pressure drop across the baghouse drops below 2 inches or raises above 10 inches. A log of all alarm instances shall be maintained including the reason the alarm was activated and the actions taken.

3. HANDLING AND STORAGE OF FABRIC FILTER DUST.

Accumulated fabric filter dust (particulate) shall be stored and/or be disposed of in a manner which minimizes the introduction of the air contaminants to the outer air.

4. PIPING AND SEALS MAINTENANCE.

Piping and seals shall be replaced as needed.

5. BLACK LIGHT INSPECTIONS.

A black light test shall be conducted at least once per year - within one week of the beginning of operation for each paving season. Black light inspection equipment and materials shall be available for use at the facility and used as needed during the paving season.

6. INVENTORY OF FILTER BAGS.

An inventory of fabric filter bags shall be maintained by the facility owner or operator so that filter bags will be available to this site within four hours of requesting the filter bags. In addition, a minimum of 15 filter bags shall be kept on-site at all times. An inventory of other replacement parts for the fabric filter dust collector shall be maintained at all times.

7. FABRIC FILTER DUST COLLECTOR INSPECTION RECORD.

A written record in a bound notebook or digital format of the following shall be maintained by the owner or operator of the facility:

- Visual inspections of the interior components of the fabric filter dust collector, including date, time, and findings;
- Black light inspections, including date, time, and findings;

- Number of filter bags installed as a result of each inspection to replace filter bags already in use in the fabric filter dust collector, including date, time, location, and whether the replacement filter bag was brand new or a cleaned, previously used filter bag;
- An explanation (i.e., a description of the damage found) for each filter bag removed from the fabric filter dust collector and confirmation that another filter bag was installed to replace it;
- Each observation of visible emissions at the stack discharge point and description of response to the observed visible emission, including date and time of visible emission occurrence and results of EPA Method 9 observation, if any. Any such visible emission shall be recorded in the Daily Operations Log Book and made available upon request to the AQD.
- All significant maintenance activities performed on the fabric filter dust collector.

APPENDIX C

EMISSION ABATEMENT PLAN FOR STARTUP, SHUTDOWN AND MALFUNCTIONS

NORMAL STARTUP PROCEDURE

The plant computer controls plant startup. At startup the plant operator will enter the mix design, the tons per hour and the number of tons to be produced into the plant operations computer. Once the operator starts the equipment the computer will start the cold feed bins and set the feed rate (tons per hour) requested. The feed rate will be different for each mix design and production rate.

When the plant computer senses that aggregate is crossing over the belt scale, a timer that has been previously calibrated for the particular mix, starts to count down. When the timer reaches zero the asphalt is started and fed to the mixer. The two products (aggregate and asphalt cement) meeting together at the correct time will eliminate most dust that would escape from the mixing drum.

Material that is discharged at startup is removed by way of the drag slat and discharge gate. This material is dropped into a loader bucket, dump truck or a holding area. The material is then moved to the recycle pile. The drop height from the discharge gate is kept to the very minimum to keep any escaping dust from blowing.

NORMAL SHUTDOWN PROCEDURE

When shutting down the mixing operation, the plant computer stops the cold feed bins first. Material that is in process is allowed to proceed down the weigh belt. When the weigh belt senses that all material has cleared the belt a timer starts counting down to shut off the asphalt cement. This timer allows all of the aggregate to clear the drying drum and enter the mixer. The asphalt cement is timed for each mix design so that the last of the aggregate and the asphalt cement meet at the mixing drum together.

Any mix that is waste is discharged into the loader bucket, dump truck or into a holding area under the drag slat discharge gate and is taken to the RAP pile for later crushing

HOT STOPS - HOT STARTS

If the silos become too full, the plant operator may have to make a hot stop, (dryer and mixer full of material). No material is discharged during a hot stop. The plant can remain in this mode for up to two hours.

After a hot stop, the plant will make a hot start. The exhaust fan and burner will be started and once running, the rest of the plant will be started. Cold or off-spec material is discharged through the drag slat discharge gate and placed in the RAP pile for later use.

MALFUNCTION STOPS

If a malfunction (computer or mechanical) occurs during drying/mixing operations, a hot stop will be initiated until the problem is corrected. If the problem cannot be corrected and the dryer/mixer must be emptied, the asphalt cement can be controlled manually. This will be done only after all attempts to correct the problem are exhausted. If the asphalt pump fails and cannot be repaired, the drum will be emptied of mixed material until the discharged aggregate gets dusty. The drum will then be stopped and the asphalt pump repaired.

A water supply at each location can be used to knock down any blowing dust.

IDENTIFICATION OF SUPERVISORY AND MAINTENANCE PERSONNEL

An updated list of current supervisory and maintenance personnel shall be kept at the plant. Descriptions of the responsibilities of these individuals for operation of the plant during startups, shutdowns, or malfunctions, as well as inspections and repairs, shall be stated on the updated list.

Appendix C – Continued

DESCRIPTION OF INSPECTED ITEMS

A daily walk around inspection will be done each morning while the plant is warming up. After startup, observations will be carried out continuously throughout the day by the plant operator and the loader operator during operations. The following items shall be inspected/observed:

- Roadways (fugitive dust)
- Cold feed bins (falling aggregate)
- Aggregate feed belts (falling aggregate)
- Dryer (seals for dust escaping)
- Bucket elevator (seals for dust escaping)
- Aggregate chutes (seals for dust escaping)
- Screen (door seals for dust escaping)
- Weigh hopper (seals for dust escaping)
- Mixer (seals for dust escaping)
- Baghouse stack (opacity)
- Baghouse screws (shaft and door seals for dust escaping)
- Chutes, screw augers, and housings (for any leaks)

A more thorough inspection will be done during the winter shutdown (between December 1 and April 1) for maintenance and repairs. The following items will be inspected and repairs made as needed:

- Cold feed bins (seals and belts rollers)
- Belt lines (belts and rollers)
- Dryer (shell, seals, flights)
- Bucket elevator (chain, buckets, bearings, seals)
- Chutes (liners, seals)
- Screen (door seals, fugitive ductwork)
- Weigh hopper (seals, calibration)
- Mixer (seals, wear plate)

The baghouse will get a thorough inspection from the front inlet to the rear exhaust fan. This inspection will be done every spring before the paving season starts. (Additional visual inspections may be required before and during the paving season as required by Appendix B). The following items to be inspected are:

- Ductwork (inspected for thickness, will it last for the season)
- Blow pipes, diaphragm valves (are they working, good connections)
- Bags and cages (condition of bags, age, number replaced during last season)
- Dust screws - shaft seals and screw cover doors

REPLACEMENT PARTS

As required by Appendix B, the following shall be kept in stock at all times:

- A minimum of 15 bags.
- A minimum of 5 pounds of black light powder. (Recommended quantity for the number of square feet of baghouse cloth.)
- A minimum of two (2) tubes of silicone caulk for minor leaks around doors and seals.

Appendix C – Continued

BAGHOUSE VARIABLES AND MONITORING

The baghouse is monitored continuously (as specified in Appendix B) by the use of a magnehelic gage. The pressure differential between the dirty and clean side of the baghouse shall be maintained above 2 inches water gauge. If the pressure rises above 10 inches water gauge, signaling an inoperative diaphragm valve, the plant shall be stopped and the defective valve repaired or replaced. If the differential pressure drops below 2 inches water gauge the company shall inspect for a torn bag or a problem with the tubesheet between the dirty and clean side of the baghouse. This problem will also result in a dirty stack. The only time the baghouse will normally drop below 2 inches water gauge is if a large number of filter bags are replaced.

If a large number of bags are replaced (over 100) the pressure on the magnehelic will drop slightly. This drop will only last for a day or less depending on the production.

Monitoring of the baghouse is done by observation, magnehelic gage, pressure detection alarm, or by the high temperature alarm that is set to go off at a stack temperature of 375/400 degrees Fahrenheit.

CORRECTIVE PROCEDURES AND RESPONSIBLE PERSONS

This startup, shutdown, malfunction plan shall be followed to meet the compliance limits. If the limits are exceeded it is the responsibility of the plant supervisor, or in his absence the plant operator, to stop the plant and correct the problem immediately. Rule 336.1912 shall be followed when abnormal conditions exist.

DRUM MIX AND BATCH - NORMAL STARTUP PROCEDURES

During startup, operation and shutdown the following items will be monitored continuously:

Stack Temperature - As material starts through the plant the temperature must be brought up slowly by manually adjusting the burner. As the operator opens the burner, the exhaust fan damper must also be opened to maintain one quarter to one half inch of suction on the burner end of the drum.

Mix Temperature - As material starts flowing through the plant it is critical to watch mix discharge temperature in addition to the stack temperature. A discharge temperature that is too high will cause blue smoke. A temperature that is too low will produce an unacceptable product.

Exhaust Magnehelic - As material is fed into the drum and the burner is opened up, the differential pressure in the baghouse will increase. As the plant reaches normal operating parameters the pressure differential will settle between 2 and 10 inches water gauge. The differential pressure can be adjusted by opening or closing the exhaust damper. The operator shall keep between one quarter and one half-inch draw on the burner end for maximum efficiency.

Along with monitoring the above items the operator shall monitor the weather to determine any changes to the moisture levels in the aggregate and RAP. The moisture content determines how to adjust the burner to reach the desired mix discharge temperature.