



Non-Condensable Gas Closed Vent System Emissions Test Report

RECEIVED
JUL 06 2016
AIR QUALITY DIV.

Prepared for:

Packaging Corporation of America

Packaging Corporation of America
2246 Udell Street
Filer City, Michigan 49634

Project No. 16-4832.00
June 14, 2016

BT Environmental Consulting, Inc.
4949 Fernlee Avenue
Royal Oak, Michigan 48073
(248) 548-8070



Executive Summary

BT Environmental Consulting, Inc. (BTEC) was retained by Packaging Corporation of America (PCA) to conduct the annual performance testing on the non-condensable gas closed vent system (CVS) identified as FGMACT_SUBPART_S located at the PCA facility in Filer City, Michigan. The testing was performed to identify any leaks that may be present along the CVS that comes off the digester and evaporator system to where it exits the building, and is transferred and introduced into the flame zone of an on-site boiler. A leak is defined as a constant reading of 500 ppm above background.

Sampling was performed utilizing United States Environmental Protection Agency (USEPA) reference test methods. Testing was conducted on May 4, 2016 to determine if leaks exist at the positive pressure segments of the non-condensable closed vent system. The closed vent system exhibited compliance as defined by the appropriate regulations.

RECEIVED

JUL 06 2016

AIR QUALITY DIV.



1.0 Introduction

BT Environmental Consulting, Inc. (BTEC) was retained by Packaging Corporation of America (PCA) to conduct the annual performance testing on the non-condensable gas closed vent system (CVS) identified as FGMACT_SUBPART_S located at the PCA facility in Filer City, Michigan. The testing was performed to identify any leaks that may be present along the CVS that comes off the digester and evaporator system to where it exits the building, and is transferred and introduced into the flame zone of an on-site boiler. A leak is defined as a constant reading of 500 ppm above background.

Testing occurred on May 4, 2016. The following BTEC professionals participated in conducting this study: Todd Wessel, Senior Project Manager; and Mason Sakshaug, Environmental Technician. Ms. Sara Kaltunas with PCA provided the on-site coordination for this project.

2.0 Process Description

The low volume, high concentration (LVHC) Collection System at PCA's Filer City Mill includes various equipment (i.e. hoods, vents, ductwork, gas movers, etc.) that collects the low volume, high concentration gases from the digester and evaporator systems and conveys the gases to No. 1 or No. 2 Boiler for destruction. In addition, the Mill collects gases from the pulp washers using the LVHC Collection System and conveys these gasses to the #1 or #2 Boiler for destruction.

3.0 Measurement Location

The sampling was performed in accordance to the procedures outlined in Appendix A of 40 CFR part 60, Method 21, and the specifications described in Subpart S of 40 CFR part 63. A portable flame ionization detector (FID) was used to detect VOC emissions from individual sources within FGMACT_SUBPART_S. The instrument was calibrated prior to use using "zero air" and a mixture of methane in air. The calibration gases used were certified by the manufacturer to be within 2 percent accuracy, with a known shelf life. Calibration data can be found in Appendix C.

The probe inlet of the FID was placed at the surface of the component interface where leakage could potentially occur. The probe was moved along the interface periphery while observing the instrument readout. The probe inlet was left at the maximum reading location for approximately two (2) times the instrument response time, or eight (8) seconds.

The maximum reading during this test program did not exceed 13 ppm during this inspection. Therefore, no leaks were present on the non-condensable gas CVS as defined in 40 CFR 63.457.



4.0 Applicable Regulations

The monitoring was performed in accordance with Parts 60 and 63 of 40 CFR. The following information is provided to show the applicable regulations and standards pertaining to the CVS located at PCA in Filer City, Michigan.

§ 63.450 Standards for enclosures and closed-vent systems.

- (a) Each enclosure and closed-vent system specified in §§63.443(c), 63.444(b), and 63.445(b) for capturing and transporting vent streams that contain HAP shall meet the requirements specified in paragraphs (b) through (d) of this section.
- (b) Each enclosure shall maintain negative pressure at each enclosure or hood opening as demonstrated by the procedures specified in §63.457(e). Each enclosure or hood opening closed during the initial performance test specified in §63.457(a) shall be maintained in the same closed and sealed position as during the performance test at all times except when necessary to use the opening for sampling, inspection, maintenance, or repairs.
- (c) Each component of the closed-vent system used to comply with §§63.443(c), 63.444(b), and 63.445(b) that is operated at positive pressure and located prior to a control device shall be designed for and operated with no detectable leaks as indicated by an instrument reading of less than 500 parts per million by volume above background, as measured by the procedures specified in §63.457(d).
- (d) Each bypass line in the closed-vent system that could divert vent streams containing HAP to the atmosphere without meeting the emission limitations in §§63.443, 63.444, or 63.445 shall comply with either of the following requirements:
 - (1) On each bypass line, the owner or operator shall install, calibrate, maintain, and operate according to the manufacturer's specifications a flow indicator that is capable of taking periodic readings as frequently as specified in §63.454(e). The flow indicator shall be installed in the bypass line in such a way as to indicate flow in the bypass line; or
 - (2) For bypass line valves that are not computer controlled, the owner or operator shall maintain the bypass line valve in the closed position with a car seal or a seal placed on the valve or closure mechanism in such a way that valve or closure mechanism cannot be opened without breaking the seal

[63 FR 18617, Apr. 15, 1998, as amended at 64 FR 17563, Apr. 12, 1999; 68 FR 37348, June 23, 2003]

5.0 Summary of Results

Testing was conducted on May 4, 2016 to determine if leaks exist at the positive pressure segments of the non-condensable closed vent system. The closed vent system exhibited compliance as defined by the appropriate regulations.